

**Monitoring Report for
CSMRI Site
Third Quarter 2010**

Prepared for:

Colorado School of Mines
Golden, Colorado

Prepared by:

The S.M. Stoller Corporation
Broomfield, Colorado

November 2010

TABLE OF CONTENTS

1. INTRODUCTION.....	1
2. SAMPLING AND ANALYSIS	1
2.1 GROUNDWATER SAMPLING.....	2
2.2 SURFACE WATER SAMPLING.....	2
2.3 ANALYSES.....	2
2.3.1 Groundwater Quality Analyses.....	3
2.3.2 Surface Water Analyses.....	4
2.4 HEALTH AND SAFETY PROGRAM.....	4
3. RESULTS	4
3.1 GROUNDWATER CONDITIONS.....	5
3.2 GROUNDWATER QUALITY	5
3.2.1 Ionic Balance Evaluation.....	6
3.2.2 Comparison of Upgradient and Downgradient Groundwater Quality.....	7
3.2.3 Comparison with Previous Groundwater Quality Analyses	7
3.2.4 Comparison with Colorado Groundwater Standards.....	7
3.3 SURFACE WATER QUALITY.....	8
4. FUTURE ACTIVITIES.....	8
5. REFERENCES.....	9

LIST OF TABLES

TABLE 2-1 SUMMARY OF RADIOISOTOPES IN GROUNDWATER	10
TABLE 2-2 SUMMARY OF METALS IN GROUNDWATER	10
TABLE 2-3 SUMMARY OF ANIONS AND CATIONS IN GROUNDWATER	11
TABLE 2-4 SUMMARY OF RADIOISOTOPES IN SURFACE WATER	11
TABLE 2-5 SUMMARY OF METALS IN SURFACE WATER	11
TABLE 2-6 SUMMARY OF ANIONS AND CATIONS IN SURFACE WATER	12
TABLE 2-7 CSMRI HISTORICAL GROUNDWATER DATA (PREVIOUS CONSULTANTS).....	12

LIST OF FIGURES

FIGURE 1	GROUNDWATER POTENTIOMETRIC ELEVATION MAP – SEPTEMBER 2010
FIGURE 2	CSMRI ALL MONITOR WELLS HYDROGRAPH
FIGURE 3	CSMRI-2 HYDROGRAPH
FIGURE 4	CLEAR CREEK GAUGING GRAPH (APRIL - JUNE 2010)
FIGURE 5	CSMRI-4 HISTORICAL TOTAL URANIUM CONCENTRATION (1991 – 2010)
FIGURE 6	CSMRI-4 TOTAL URANIUM CONCENTRATION AND POTENTIOMETRIC ELEVATION
FIGURE 7	CSMRI-8 TOTAL URANIUM CONCENTRATION AND POTENTIOMETRIC ELEVATION

LIST OF APPENDICES

APPENDIX A	GROUNDWATER SAMPLING PROCEDURES
APPENDIX B	SAMPLE COLLECTION FORMS
APPENDIX C	SURFACE WATER SAMPLING PROCEDURES
APPENDIX D	DATA VALIDATION REPORTS
APPENDIX E	RESULTS OF ANALYSES ON CD
APPENDIX F	CHAIN-OF-CUSTODY DOCUMENTATION
APPENDIX G	HISTORICAL SUMMARY TABLES
APPENDIX H	ANION AND CATION BALANCES AND PIPER DIAGRAM

1. Introduction

This report presents the third quarter (July, August, September) 2010 results for groundwater and surface water monitoring conducted at the Colorado School of Mines Research Institute (CSMRI) site in Golden, Colorado. The monitoring was conducted by the S.M. Stoller Corporation (Stoller).

2. Sampling and Analysis

Stoller obtained quarterly samples of groundwater and surface water on September 8, 9, and 10, 2010, from 11 groundwater monitor wells and three Clear Creek surface water sample locations. Groundwater quality samples were obtained on September 8 (CSMRI-1B, CSMRI-6C, CSMRI-8, CSMRI-9, CSMRI-10, and CSMRI-11B); September 9 (CSMRI-1); and September 10 (CSMRI-2, CSMRI-4, CSMRI-5, and CSMRI-7B). Monitor wells CSMRI-2 and CSMRI-7B required purging on one day and sample collection on subsequent visits over the following days to obtain sufficient sample volume.

Clear Creek surface water samples were collected on September 9, 2010, from sampling locations SW-1, SW-2, and SW-3.

All aqueous samples were placed on ice in coolers and couriered to ALS Laboratory Group in Fort Collins, Colorado or to TestAmerica, Inc. in Arvada, Colorado for analyses.

Figure 1 presents the monitor well and Clear Creek surface water sample locations at the CSMRI site. The figure also shows the groundwater potentiometric surface elevations posted adjacent to each monitor well location. Potentiometric surface elevations are based on depth to groundwater relative to the surveyed top-of-casing and represent groundwater elevations as measured before purging. Groundwater levels are measured at each well to the nearest 1/100th of a foot (0.01) prior to purging and sample collection. The potentiometric surface from surveyed piezometers installed in test pits within the flood plain have been integrated into Figure 1 to further define the direction of groundwater flow. The figure shows a northeasterly component of flow on the bench terrace area and then a northerly component of flow as groundwater flows over the bench terrace slope and into the flood plain area. The figure suggests uniform flow occurring along the interface of surficial deposits and bedrock down the terrace slope; however, preferential pathways resulting from an uneven bedrock/alluvial interface are thought to exist explaining the occasionally dry well CSMRI-7B.

Figure 2 presents hydrographs of groundwater potentiometric elevations for monitor wells CSMRI-1, CSMRI-1B, CSMRI-4, CSMRI-5, CSMRI-6B (abandoned July 2008), CSMRI-6C, CSMRI-7B, CSMRI-8, CSMRI-9, CSMRI-10, CSMRI-11 (abandoned July 2008), and CSMRI-11B. Gaps in the graph denote the intermittent presence of groundwater in the monitor wells because occasionally groundwater is below the bottom depth of a monitor well, even though the bottom of the screened interval is within the underlying bedrock. Monitor wells included on Figure 2 are located within the CSMRI site proper and illustrate historical trends in the water table fluctuations throughout the site.

Figure 3 is a hydrograph of monitor well CSMRI-2. Monitor well CSMRI-2 is located near the southeast corner of the freshman parking lot on West Campus Drive and the former Welch Ditch. CSMRI-2 is upgradient of the CSMRI site and historically has been used to provide background groundwater quality conditions. Early potentiometric data reflect the use of and leakage from the nearby irrigation ditch. For example, this hydrograph shows a marked seasonal rise in the potentiometric surface during the summer months in 2005 and 2006. In 2007, the Welch Ditch was diverted upstream of CSMRI and piped to Washington Avenue in Golden and then to down-ditch users. From late 2006 through late 2007, the water level remained elevated. From early 2008 through mid-2010, water levels reflect a more typical seasonal pattern of fluctuation.

2.1 Groundwater Sampling

Water quality samples were collected following the procedure outlined in Appendix A, Groundwater Sampling Procedures.

Sample collection forms provide a record of water quality parameters as measured in the field as groundwater was purged from monitor wells. These forms also indicate the volume of water removed from each well. Sample collection forms are provided as Appendix B. After three casing volumes of groundwater were purged, water samples were filtered through a 0.45 micron (μ) filter, collected in laboratory-provided containers, and preserved in the field as appropriate for the analyte and analytical method. Monitor wells CSMRI-1B, CSMRI-2, and CSMRI-7B were purged dry before three casing volumes of groundwater were removed. Monitor wells CSMRI-1B and CSMRI-7B required multiple visits to collect sufficient sample volume because they recharge so slowly.

2.2 Surface Water Sampling

Surface water samples from Clear Creek were collected on September 9, 2010, from two locations: one upstream of the site (SW-1) and one downstream of the site (SW-2) (Figure 1). Clear Creek surface water sample SW-3 was collected at a location between the upstream and downstream sample locations and due north of monitor well CSMRI-8. Surface water at this location was sampled on September 9, 2010. All surface water samples were collected following the procedure outlined in Appendix C, Surface Water Sampling Procedures. Surface water samples are filtered through a 0.45 μ filter, collected in laboratory-provided containers, and preserved in the field as appropriate for the analyte and analytical method.

Discharge data of stream flow for Clear Creek, as measured by the U.S. Geological Survey (USGS), at Clear Creek gauging station #06719505 (USGS Surface Water Online Database) for the quarter from July 1, 2010 through September 30, 2010 are presented as Figure 4. Tabulated stream flow data for the time period of September 7, 8, 9, and 10, 2010 indicate the mean stream flow was recorded at 91, 90, 88, and 89 cubic feet per second, respectively.

2.3 Analyses

All samples collected were analyzed using a Comprehensive Environmental Response, Compensation and Liability Act (CERCLA)-certified analytical laboratory. The results received from the laboratory were evaluated based on the following parameters:

- Data completeness

- Holding times and preservation
- Instrument initial calibrations
- Instrument performance checks
- Preparation blanks
- Duplicate sample results
- Laboratory control sample results
- Compound quantization and reporting limits (full validation only)

As a quality control/quality assurance (QA/QC) check, an equipment blank sample was collected in the field by pouring distilled water through a sample bailer. The equipment blank sample was submitted for the identical analytical parameters as the groundwater and surface water samples. The results of the equipment blank analyses did not identify interferences or anomalies in the laboratory data.

Results of the QA/QC review did not identify any significant issues regarding analytical laboratory results. The Ra-228 analytical results from monitor well CSMRI-7B is estimated (J) due to the minimum detectable activity (MDA) being greater than the required detection limit (RDL).

Data validation results are presented in Appendix D.

2.3.1 Groundwater Quality Analyses

Summaries of groundwater results for radioisotopes, metals, and inorganic anions and cations are presented in Table 2-1, Table 2-2, and Table 2-3, respectively. Groundwater parameters are reported as picoCuries per liter (pCi/L) for radioisotopes, micrograms per liter ($\mu\text{g/L}$) for uranium and iron, and milligrams per liter (mg/L) for all other metals and ions.

ALS Laboratory Group in Fort Collins, Colorado and TestAmerica Laboratories, Inc. in Arvada, Colorado conducted laboratory analyses of the aqueous samples. Analytical samples submitted to ALS were analyzed for radium isotopes (Ra-226 and Ra-228), uranium (U), calcium (Ca), potassium (K), magnesium (Mg), sodium (Na), phosphorus (P), chloride (Cl), sulfate (SO_4), carbonate as calcium carbonate (CO_3), bicarbonate as calcium carbonate (HCO_3), alkalinity, and dissolved organic carbon (DOC). Pursuant to an agreement with the Colorado Department of Public Health and Environment (CDPHE), a broader analyte list of metals is sampled only during the second quarter (June) sampling event. Specifically these metals include: silver (Ag), arsenic (As), barium (Ba), cadmium (Cd), chromium (Cr), mercury (Hg), and vanadium (V).

Analytical samples submitted to TestAmerica were tested for the presence of nitrate (NO_3), nitrite (NO_2), ferrous (Fe^2) iron, ferric (Fe^3) iron, sulfide and total dissolved solids (TDS). TestAmerica conducts the short holding time analyses because of their close proximity to the CSMRI site.

Groundwater samples were measured onsite for temperature, pH, specific conductance, dissolved oxygen (DO), oxidation-reduction potential (ORP), and turbidity as nephelometer turbidity units (NTU) during the purging and sampling process using a Horiba U-22 multi-probe. Onsite

parameters measurements of groundwater and purge volumes are presented on the sample collection forms in Appendix B.

From the first quarter of monitoring in February 2005 until the last quarter of 2006, the concentration of total uranium in $\mu\text{g/L}$ was analyzed using ALS (formerly Paragon) method 714R9. With this method, the concentration of uranium is calculated based on the activity of the uranium isotopes U-234, U-235, and U-238. Effective since the first quarter 2007 sampling event, the concentration of uranium has been analyzed using mass spectrometry method EPA 6020, which analyzes for total uranium and not for the activity of the individual isotopes.

Analytical data from ALS and TestAmerica were transmitted as an electronic data deliverable (EDD) and are included in Appendix E on a compact disk. Data are formatted as series of Excel spreadsheets. Appendix F presents copies of the chain-of-custody for the CSMRI samples.

2.3.2 Surface Water Analyses

Clear Creek surface water results for radioisotopes, metals, and inorganic anions and cations are presented in Table 2-4, Table 2-5, and Table 2-6, respectively. Surface water parameters are reported as pCi/L for radioisotopes, $\mu\text{g/L}$ for uranium and iron, and mg/L for all other metals and ions. Surface water samples were measured onsite for temperature, pH, specific conductance, DO, ORP, and NTU as the sampling was conducted. Onsite parameter measurements are presented on the sample collection forms in Appendix B.

2.4 Health and Safety Program

Stoller implements a program to protect the health and safety of field personnel during the environmental monitoring at the CSMRI site. This program has been developed in accordance with requirements of 29 Code of Federal Regulations (CFR) 1910.120.

3. Results

Groundwater analytical results for samples collected from the CSMRI site during the third quarter 2010 for radioisotopes, metals, and anions and cations are summarized on Table 2-1, Table 2-2, and Table 2-3, respectively. Surface water analytical results for samples collected from the CSMRI site during the third quarter 2010 for radioisotopes, metals, and anions and cations are summarized on Table 2-4, Table 2-5, and Table 2-6, respectively. Table 2-7 presents historical data collected by previous consultants for select contaminants of potential concern in groundwater at the site. The historical uranium data presented in Table 2-7 are presented in pCi/L as “activity,” more recent (2005 through 2010) analytical data are presented in $\mu\text{g/L}$ as “mass concentration.” The December 7, 2000, *Federal Register* discusses the final uranium maximum contaminant level (MCL) and presents a conversion factor of a geometric average mass: activity ratio of 0.9 pCi/g for values near the National Primary Drinking Water Standards MCL, based on data from the National Inorganics and Radionuclides Survey.

Tables G-1 and G-2 in Appendix G present the quarterly historical groundwater radioisotopic and metals sample results, respectively, collected by Stoller since February 2005. Tables G-3 and G-4 in Appendix G present the quarterly historical Clear Creek surface water radioisotopic and metals sample results, respectively, collected by Stoller since February 2005.

3.1 Groundwater Conditions

Groundwater monitor wells are located in areas likely to detect impacts, if any, to groundwater emanating from the site and at locations that represent background water quality. Monitor wells CSMRI-4 and CSMRI-5 are downgradient of the site in the Clear Creek flood plain. Well CSMRI-1 is located along Clear Creek upstream of the site, and well CSMRI-2 is located offsite in the southeast corner of the freshman parking lot on West Campus Drive. Both monitor wells CSMRI-1 and CSMRI-2 are upgradient of the site.

In February 2007, seven new groundwater monitor wells were installed to assess the effectiveness of the source removal excavation that was conducted in 2006. Monitor well CSMRI-8 is located along Clear Creek within the flood plain area; and monitor wells CSMRI-1B, CSMRI-6B, CSMRI-7B, CSMRI-9, CSMRI-10, and CSMRI-11 are located on the bench terrace and essentially encircle the CSMRI site.

In July 2008, two monitor wells (CSMRI-6B and CSMRI-11) were abandoned due to construction activities at the CSMRI site. These two wells were replaced in December 2008 with CSMRI-6C and CSMRI-11B, respectively.

3.2 Groundwater Quality

Groundwater samples were collected from 11 monitor wells and tested for the presence of metals and radioisotopes as identified in Section 2.3.1. The sample volumes collected from monitor well CSMRI-7B was limited due to insufficient water. Because of the limited water volume at this well, analytical testing was conducted only for radioisotopes and uranium.

Uranium was detected in monitor wells CSMRI-4 at 62 µg/L, CSMRI-7B at 75 µg/L, CSMRI-8 at 520 µg/L, and CSMRI-9 at 31 µg/L at concentrations exceeding the State of Colorado groundwater standard of 30 µg/L. Uranium was also detected in the remaining seven groundwater monitor wells but at concentrations below the groundwater standard.

In the flood plain area, uranium was detected in monitor wells CSMRI-4 at 62 µg/L, CSMRI-5 at 13 µg/L, and CSMRI-8 at 520 µg/L. Monitor well CSMRI-4 historically has had elevated concentrations of uranium. Values had been declining since 1991 until the last several quarterly sampling events as depicted on Figure 5. Historically, the concentration of uranium in this monitor well spiked once in 1999 and again in 2003. The spike in the uranium concentration in 2003 was attributed to precipitation effects and removal of asphalt and concrete as discussed in New Horizons RI/FS, Section 4.2.2 of the (New Horizons 2004). The recent (2009) rise in the uranium concentration in this monitor well appears to be attributed to stormwater discharge from the new Colorado School of Mines (CSM) artificial turf soccer field subdrains. Precipitation collected in the subdrains, discharged near the northern edge of the bench terrace, and flowed down a riprap-embedded concrete rundown onto the flood plain. During the process, the discharge water became oxygenated and was introduced into the poorly oxygenated environment of the flood plain area. Uranium present in the saturated sediments of the flood plain was mobilized by the oxygenated discharge water and flowed toward monitor well CSMRI-4. In early 2010, the soccer field discharge pipe was relocated to the east. Analytical data suggest the soccer field discharge pipe is no longer affecting this monitor well.

Figure 6 presents the potentiometric surface elevation of groundwater in CSMRI-4 (left Y axis) and the uranium concentration (right Y axis) from 2005 through the third quarter 2010. The figure indicates the uranium concentration had previously been fluctuating seasonally from slightly above to slightly below the groundwater standard of 30 µg/L for seven quarterly sampling events in 2005 and 2006. An ice chest from the fourth quarter 2006 (December) sampling event was lost by the courier service resulting in a gap in the analytical data for CSMRI-4. The concentration of uranium in this well has increased since the 2006 surface soil remediation activities and also spiked during the third quarter 2009 sampling event. The uranium concentration in this monitor well has decreased significantly since the third quarter 2009 sampling event and reflects the relocation of the soccer field discharge pipe.

The uranium concentration detected in CSMRI-8 decreased slightly to 520 µg/L from the previous quarterly value of 540 µg/L. Monitor well CSMRI-8 was installed in February 2007. Figure 7 presents the potentiometric surface elevation of groundwater at this well (left Y axis) and the uranium concentration (right Y axis) from 2007 through the third quarter 2010. Quarterly monitoring will continue at this location to document seasonal variability and trends in the uranium concentration in groundwater.

The uranium concentration in CSMRI-9 of 31 µg/L has decreased to below the concentrations from the past five sampling events and is within the range of the 2007 and 2008 analytical data. This monitor well is located at the top of the bench terrace that rises above the flood plain and is downgradient of the CSMRI site.

3.2.1 Ionic Balance Evaluation

The ionic testing and balancing is conducted to determine the different groundwater hydrochemical facies within the CSMRI site and to assess the analytical laboratory quality control procedures since the sum of the major anions should equal the sum of the major cations when the ionic concentrations are converted to millequivalents per liter. Significant differences in the ionic balance of a groundwater sample suggest either an ionic species is present and not tested for or laboratory analytical procedures are not consistent.

Groundwater and surface water samples were collected and tested for major anions and cations, DOC, and at select locations (CSMRI-1, CSMRI-4, CSMRI-5, and CSMRI-8) ferric/ferrous iron. The presence of sulfide was also analyzed for in samples from the three flood plain monitor wells (CSMRI-4, CSMRI-5, and CSMRI-8). Analytical results for these parameters are presented in Table 2-3 for groundwater and Table 2-6 for surface water. AqQA[®] geochemical software is used to calculate ionic balances of water samples and to present the graphical representation of anions and cations. Ionic balance calculations for the anions and cations for the water samples generally range from 1 to 7.9 percent. Only monitor well CSMRI-2 at 13.5 percent is greater than a 10 percent balance difference.

Summary sheets from the AqQA[®] geochemical software for each of the water samples are presented in Appendix H. Dominant water types identified at the CSMRI site include Na-Cl (CSMRI-1); Ca-Cl (CSMRI-1B, CSMRI-4, CSMRI-5, CSMRI-6C, CSMRI-8, CSMRI-9, CSMRI-10, and CSMRI-11B); Ca-HCO₃ (CSMRI-2); and Ca-SO₄ (SW-1, SW-2, and SW-3 [all Clear Creek surface water samples]).

Historically, groundwater from CSMRI-1 has always been a Ca-Cl type water (since third quarter 2008). However, with the third quarter 2010 sampling event, CSMRI-1 now appears as a Na-Cl type water.

A Piper quadrilateral diagram is included in Appendix H and illustrates the overall ionic properties for each water sample. The cation triangle in the lower left of the figure indicates the cation composition of the water samples are generally similar as exhibited by the tight grouping of the plotted results. The anion triangle in the lower right of the figure indicates the anion composition of the water samples is more diverse as exhibited by the dispersed nature of the plotted results.

3.2.2 Comparison of Upgradient and Downgradient Groundwater Quality

Monitor wells CSMRI-4, CSMRI-5, and CSMRI-8 are downgradient from the upper terrace portion of the site and are located on the Clear Creek flood plain. Monitor wells CSMRI-7B and CSMRI-9 are located downgradient of the CSMRI site at the top of the bench terrace above the flood plain. Monitor wells CSMRI-10 and CSMRI-11B are located at the eastern edge of the site, and monitor wells CSMRI-1B and CSMRI-6C are located upgradient of the site.

Uranium was detected in monitor wells CSMRI-4 at concentrations of 62 µg/L, CSMRI-8 at 520 µg/L, and CSMRI-9 at 31 µg/L, exceeding the groundwater standard of 30 µg/L. Monitor well CSMRI-8 is located at the western edge of the flood plain area and is upgradient of monitor wells CSMRI-4 and CSMRI-5. Monitor well CSMRI-9 is located at the downgradient position on the bench terrace at the CSMRI site.

3.2.3 Comparison with Previous Groundwater Quality Analyses

Table 2-7 presents historical groundwater analytical results from past sampling events dating back to 1991 for radioisotopes of concern. The data indicate fluctuating concentrations of tested analytes, particularly for monitor well CSMRI-4.

As additional data are collected for each sampling quarter and trends become more defined, graphs of concentration versus time are produced and presented. These analytical data are incorporated to show long-term trends and correlation between the detected concentration of uranium in groundwater, the fluctuating water table, and seasonal variability if present.

3.2.4 Comparison with Colorado Groundwater Standards

As discussed previously, the groundwater standard of 30 µg/L for uranium in groundwater was exceeded in monitor wells CSMRI-4 (62µg/L), CSMRI-7B (75 µg/L), CSMRI-8 (520 µg/L), and CSMRI-9 (31 µg/L). In January 2008, the CDPHE Water Quality Control Commission adopted the surface water quality standard of 30 µg/L as the groundwater quality standard in an effort to keep both uranium standards consistent.

The historic spikes in the concentration of uranium in CSMRI-4, as shown on Figure 5, have been attributed to increased precipitation from December 2006 through February 2007 and surface soil remediation activities in the flood plain. Recent analytical results indicate a decreasing trend back to 2007 and 2008 levels prior to impacts from the soccer field storm drain.

No exceedances of the MCL for Ra-226 and Ra-228 were detected in any of the groundwater samples for this sampling quarter.

Monitoring wells CSMRI-7B and CSMRI-8 were abandoned in late-2010 to accommodate soil characterization activities in the flood plain. Abandonment forms were completed and submitted to the State Engineer's Office, Colorado Division of Water Resources to document the abandonment process. After soil characterization is complete, these monitor wells will be replaced and integrated into the quarterly sampling schedule. Sampling of these new wells and other site wells will continue and the reason(s) for observed elevated levels of uranium will be evaluated.

3.3 Surface Water Quality

Surface water samples are collected from three locations at the site. Location SW-1 is located over 400 feet upstream from the CSMRI site, SW-2 is downstream from the site, and SW-3 is located adjacent to the Clear Creek bank in the vicinity of monitor well CSMRI-8. All surface-water concentrations of tested parameters detected at the CSMRI site from stations SW-1, SW-2, and SW-3 are similar. Established water quality standards were not exceeded at any location.

4. Future Activities

Construction activities associated with the flood plain soil characterization effort began in mid-October 2010. The characterization activities are being conducted predominately in the vicinity of monitor well CSMRI-8 and to the west along the hillside where previous characterization studies indicate elevated concentrations of metals and radioactivity above background.

During characterization activities, monitor wells CSMRI-7B and CSMRI-8 were abandoned. These wells will be replaced following completion of the characterization effort and will be sampled, along with three new monitor wells that will be installed in the flood plain area, in either the fourth quarter 2010 or first quarter 2011 sampling events.

5. References

Colorado Department of Public Health and Environment, Water Quality Control Commission, Regulation No. 41, *The Basic Standards for Ground Water*. Amended: January 14, 2008, Effective: May 31, 2008.

ERO Resources, Inc. 2010. *Biological Assessment, CSMRI Flood Plain Site in Golden, Jefferson County, Colorado*. ERO Project #4633. February 9, 2010.

New Horizons Environmental Consultants, Inc. Remedial Investigation/Feasibility Study and Proposed Plan, Colorado School of Mines Research Institute Site, Golden, CO, January 21, 2004.

Stoller 2010. Final Work Plan, Environmental Assessment and Characterization, Colorado School of Mines Research Institute Site, Flood Plain Area, Golden, Colorado, Prepared by The S.M. Stoller Corporation For Colorado School of Mines, August 2010.

USGS Surface Water website: <http://nwis.waterdata.usgs.gov>

**Table 2-1
Summary of Radioisotopes in Groundwater**

Sample Station	Sample Date	Ra-226 (pCi/L)		Ra-228 (pCi/L)		Total U (µg/L)
		Result	Uncertainty	Result	Uncertainty	Result
CSMRI-1	9/9/10	0.13	±0.33	0.85	±0.41	2
CSMRI-1B	9/8/10	0.35	±0.24	0.61	±0.34	18
CSMRI-2	9/10/10	0.29	±0.28	1.52	±0.58	0.98
CSMRI-4	9/10/10	0.12	±0.32	1.64	±0.61	62
CSMRI-5	9/10/10	0.41	±0.26	0.39	±0.35	13
CSMRI-6C	9/8/10	0.11	±0.25	0.97	±0.42	25
CSMRI-7B	9/10/10	1.13	±0.81	0.8 J	±1.1	75
CSMRI-8	9/8/10	0.28	±0.34	0.46	±0.32	520
CSMRI-9	9/8/10	0.03	±0.15	0.46	±0.33	31
CSMRI-10	9/8/10	0.22	±0.2	0.5	±0.34	14
CSMRI-11B	9/8/10	0.04	±0.18	0.79	±0.39	18
MCL*		Total Ra = 5				30

*Maximum Contaminant Level – National Primary Drinking Water Regulations

pCi/L = picoCuries per Liter

µg/L = micrograms per Liter

NT – Not Tested

J = Estimated MDA > RDL

**Table 2-2
Summary of Metals in Groundwater
(All results in mg/L)**

Sample Station	Sample Date	Ag	As	Ba	Ca	Cd	Cr	Hg	K	Mg	Na	Pb	V
CSMRI-1	9/9/10	NT	NT	NT	39	NT	NT	NT	4.5	14	60	NT	NT
CSMRI-1B	9/8/10	NT	NT	NT	140	NT	NT	NT	5.5	63	53	NT	NT
CSMRI-2	9/10/10	NT	NT	NT	87	NT	NT	NT	6.7	39	23	NT	NT
CSMRI-4	9/10/10	NT	NT	NT	150	NT	NT	NT	19	62	59	NT	NT
CSMRI-5	9/10/10	NT	NT	NT	150	NT	NT	NT	5.1	56	64	NT	NT
CSMRI-6C	9/8/10	NT	NT	NT	130	NT	NT	NT	5	63	50	NT	NT
CSMRI-7B	9/10/10	NT	NT	NT	NT	NT	NT	NT	NT	NT	NT	NT	NT
CSMRI-8	9/8/10	NT	NT	NT	240	NT	NT	NT	19	75	64	NT	NT
CSMRI-9	9/8/10	NT	NT	NT	130	NT	NT	NT	6.8	62	51	NT	NT
CSMRI-10	9/8/10	NT	NT	NT	120	NT	NT	NT	5	46	51	NT	NT
CSMRI-11B	9/8/10	NT	NT	NT	140	NT	NT	NT	6.6	64	76	NT	NT
Detection Limits		0.01	0.01	0.1	1	0.005	0.01	0.0002	1	1	1	0.003	0.01
MCL*		NE	0.010	2	NE	0.005	0.1	0.002	NE	NE	NE	0.015	NE

*Maximum Contaminant Level – National Primary Drinking Water Regulations

NE – Not Established

ND – Tested but not detected above the Detection Limits

NT – Not Tested

B - Reported value was less than the contract lab required detection limit but equal to or greater than the lab MDL.

Table 2-3
Summary of Anions and Cations in Groundwater

Sample Station	Sample Date	Bicarbonate as CaCO ₃ (mg/L)	Carbonate as CaCO ₃ (mg/L)	Total Alkalinity as CaCO ₃ (mg/L)	Chloride (mg/L)	Total Dissolved Solids (mg/L)	Dissolved Organic Carbon (mg/L)	Ferric Iron (mg/L)	Ferrous Iron (mg/L)	Total Iron (ug/L)	Nitrate (mg/L)	Nitrite (mg/L)	Dissolved Phosphorous (mg/L)	Sulfate (mg/L)	Sulfide (mg/L)
CSMRI-1	9/9/10	95	ND	95	120	380	1	ND	ND	ND	1.3	ND	NT	61	NT
CSMRI-1B	9/8/10	260	ND	260	290	810	1.8	NT	NT	NT	5.9	ND	NT	150	NT
CSMRI-2	9/10/10	290	ND	290	30	450	1	NT	NT	NT	ND	ND	NT	90	NT
CSMRI-4	9/10/10	300	ND	300	230	900	2.1	ND	ND	ND	0.98	ND	NT	170	ND
CSMRI-5	9/10/10	220	ND	220	260	850	1.5	ND	ND	ND	4.2	ND	NT	180	ND
CSMRI-6C	9/8/10	310	ND	310	170	800	2	NT	NT	NT	9.5	ND	NT	120	NT
CSMRI-7B	9/10/10	NT	ND	NT	NT	NT	NT	NT	NT	NT	NT	NT	NT	NT	NT
CSMRI-8	9/8/10	440	ND	440	300	1,100	3.4	ND	ND	ND	ND	ND	NT	160	ND
CSMRI-9	9/8/10	260	ND	260	220	750	1.3	NT	NT	NT	5.0	ND	NT	130	NT
CSMRI-10	9/8/10	230	ND	230	190	670	1.3	NT	NT	NT	6.0	ND	NT	110	NT
CSMRI-11B	9/8/10	270	ND	270	240	920	1.5	NT	NT	NT	6.6	ND	NT	180	NT
Reporting Limits		5, 10 or 20	5, 10 or 20	5, 10 or 20	1, 2 or 4	10	1	0.20	0.20	100	0.50	0.50	0.05	5 or 20	0.050

ND – Non Detect
NT – Not Tested

Table 2-4
Summary of Radioisotopes in Surface Water

Sample Station	Sample Date	Ra-226 (pCi/L)		Ra-228 (pCi/L)		Total U (µg/L)
		Result	Uncertainty	Result	Uncertainty	Result
SW-1	9/9/10	0.04	±0.21	0.21	±0.3	1
SW-2	9/9/10	0.2	±0.18	0.16	±0.29	1
SW-3	9/9/10	0.13	±0.23	0.21	±0.29	0.98
MCL*		Total Ra = 5				30

*Maximum Contaminant Level – National Primary Drinking Water Regulations
pCi/L = picoCuries per Liter
µg/L = micrograms per Liter
J = Estimated value

Table 2-5
Summary of Metals in Surface Water
(All results in milligrams per liter)

Sample Station	Sample Date	Ag	As	Ba	Ca	Cd	Cr	Hg	K	Mg	Na	Pb	V
SW-1	9/9/10	NT	NT	NT	23	NT	NT	NT	1.7	5.1	9	NT	NT
SW-2	9/9/10	NT	NT	NT	23	NT	NT	NT	1.7	5.3	9.2	NT	NT
SW-3	9/9/10	NT	NT	NT	23	NT	NT	NT	1.7	5.2	9.3	NT	NT
Detection Limits		0.01	0.01	0.1	1	0.005	0.01	0.0002	1	1			
MCLs*		0.01	0.010	2	NE	0.005	0.1	0.002	NE	NE	NE	0.015	NE

*Maximum Contaminant Level – National Primary Drinking Water Regulations
NE – Not Established
ND = Not Detected at or above the detection limit
B = Reported value was less than the contract lab required detection limit but equal to or greater than the lab MDL.

Table 2-6
Summary of Anions and Cations in Surface Water


Sample Station	Sample Date	Bicarbonate as CaCO ₃ (mg/L)	Carbonate as CaCO ₃ (mg/L)	Total Alkalinity as CaCO ₃ (mg/L)	Chloride (mg/L)	Total Dissolved Solids (mg/L)	Dissolved Organic Carbon (mg/L)	Ferric Iron (mg/L)	Ferrous Iron (mg/L)	Total Iron (µg/L)	Nitrate (mg/L)	Nitrite (mg/L)	Total Phosphorous (mg/L)	Sulfate (mg/L)
SW-1	9/9/10	35	ND	35	13	130	1.4	NT	NT	NT	ND	ND	NT	48
SW-2	9/9/10	35	ND	35	13	130	1.3	NT	NT	NT	ND	ND	NT	48
SW-3	9/9/10	34	ND	34	13	140	1.3	NT	NT	NT	ND	ND	NT	48
Reporting Limits		5	5	5	0.2	10	1	NT	NT	NT	0.50	0.50	0.05	1

ND = Not Detected at or above the Reporting Limits
NT = Not Tested

Table 2-7
CSMRI Historical Groundwater Data (Previous Consultants)
(All results in picoCuries per liter)

Well ID (d)	Analyte	1/1991 (a)	6/1991 (a)	3/1999 (b)	6/1999 (b)	10/1999 (b)	2/2003 (c)	4/2003 (c)	7/2003 (c)	10/2003 (c)
CSMRI-1	Ra-226			0.1	0.3	0.2	<0.55	<0.45	ND (<0.38)	ND (<0.31)
	U Total			2.09	2.59	1.44	2.4	2.9	0.87	1.4
	Th-230			0.4	0.2	0.2	<0.19	0.21	ND (<0.13)	<0.15
CSMRI-2	Ra-226		1.9	1.9	1.4	1.4	1.4	2.8	2.1	1.7
	U Total	11	5.7	0.55	1.46	0.71	1.5	1.3	1.9	1.3
	Th-230		0	0.1	0.1	0.9	<0.17	0.43	0.20	0.31
CSMRI-3	Ra-226		0.6	1.5	1.2	1.6	<0.75	<0.81	ND (<0.49)	<0.98
	U Total	17	10.4	8.41	12.4	10	12	12	9	10
	Th-230		0	0.3	0.3	1.1	<0.12	ND (<0.15)	ND (<0.17)	ND (<0.14)
CSMRI-4	Ra-226		1	<0.4	0.6	0.4	<0.85	<0.42	<0.32	ND (<0.64)
	U Total	86	57.3	23.4	58.6	33.7	16	34.2	53	19
	Th-230		0	0.7	0.3	0.4	<0.099	ND (<0.15)	ND (<0.17)	ND (<0.12)
CSMRI-5	Ra-226		0.6	2.4	3.3	2.7	ND (<0.49)	1.1	2.6	1.59
	U Total	14	16.8	3.6	3.6	4	2.8	2.3	2.7	3.3
	Th-230		0	0.2	0.2	1.4	0.062	ND (<0.14)	ND (<0.19)	ND (<0.13)

Notes: ND = Not Detected
a - Samples collected by Grant and Associates and analyzed by Barringer Labs
b - Samples collected by URS Greiner Woodward Clyde and analyzed by CORE Labs
c - Samples collected by New Horizons Environmental Consultants and analyzed by Paragon Analytics; Total U activity (pCi/L) calculated from concentration (µg/L) reported by Paragon.
d - Well Identification numbers changed from the 1991 data to the 1999 data. Data presented account for this change



Explanation

- Test Pit locations
(Potentiometric Elevations where indicated)
- Monitor Well
(Potentiometric Elevations where indicated)
- Surface Water Sample Location
- - - Potentiometric Surface Contours (3 Ft.)
- CSMRI Site
- - - Fences
- Roads
- Topography (Depressions)
- Topography (10 Ft Intervals)
- Topography (2 Ft Intervals)
- Soccer Field
- Stands

Note:
 < number means that value = Elevation of the Bottom of the Well Screen

Scale: 1" = 150'

Figure 1
 Groundwater Potentiometric
 Elevation Map - September 2010

** Note: Topo Lines in this map are for general reference only.

Figure 2
CSMRI
All Monitor Wells Hydrograph




Figure 3
CSRMI-2
Hydrograph




Figure 4
Clear Creek Gauging Graph
July - September 2010




Figure 5
CSMRI-4
Historical Total Uranium Concentration
(1991 - 2010)




Figure 6
CSMRI-4
Total Uranium Concentration and Potentiometric Elevation





Figure 7
CSMRI-8
Total Uranium Concentration and Potentiometric Elevation



Appendix A

Groundwater Sampling Procedures

Groundwater Sampling

1.0 Purpose

This procedure describes actions to be used to sample groundwater from monitoring wells and piezometers. Monitoring wells are generally sampled on a semiannual, quarterly, or monthly basis, or by special request in support for specific projects. All wells are to be sampled using this procedure unless superseded by specific site, facility, or client procedures.

This procedure describes equipment decontamination and transport, site preparation, detection and sampling of immiscible layers, water level measurements, well purging, sample collection, field and analytical parameters, quality assurance/quality control (QA/QC) requirements, and documentation that shall be used for field data collection.

2.0 Scope

This document describes acceptable methods for the sampling of wells and piezometers.

3.0 Responsibilities and Qualifications

Personnel performing groundwater sampling procedures are required to have completed the initial 40-hour OSHA classroom training that meets the Department of Labor requirements at 29 CFR 1910.120(e)(3)(i), and must maintain a current training status by completing the appropriate annual 8-hour OSHA refresher courses. Personnel must also have read the appropriate project, site, or facility Health and Safety Plan(s). Prior to engaging in groundwater sampling activities, personnel must have a complete understanding of the procedures described within this procedure and, if necessary, will be given specific training regarding these procedures by other personnel experienced in the methods described within this procedure.

4.0 Groundwater Sampling Procedures

4.1 Introduction

Many monitoring wells are constructed of either 2-inch stainless steel, or 2- or 4-inch flush threaded PVC casing. Some piezometers are completed as monitoring wells, and they are usually constructed of $\frac{3}{4}$ -inch inside diameter, flush threaded PVC casing. Some wells have been constructed to incorporate a sump below the well screen. Because these vary in length, the well construction diagrams should be consulted to determine the sump lengths for specific wells. Most piezometers are constructed with a flush threaded cap at the bottom of the well screen. However, the well construction diagrams should also be consulted for information about specific piezometers.

Procedures for groundwater sampling are designed to obtain a sample that is representative of the formation water beneath the site in question. Since an analysis of the quality of formation water is desired, standing water within the well must be purged before sampling. Also, a measure of the static water elevations is important to determine the effect of seasonal horizontal and vertical flow gradient changes during site characterization activities.

Groundwater sampling procedures can be initiated after sampling personnel take the required water level measurements and purge the well in accordance with this procedure. Methods for accomplishing each of these activities are included in this procedure in the following sequence:

- Collection of immiscible layers samples, if present
- Well purging
- Groundwater sampling using a bailer

- Groundwater sampling using a peristaltic pump
- Groundwater sampling with a bladder pump

4.2 General Equipment Requirements

Down-hole sampling equipment shall be constructed of inert material such as polytetrafluoroethylene (Teflon[®]) or stainless steel. This equipment shall be assessed on an individual basis prior to use in the field.

The following is a primary list of well sampling and associated equipment:

- Bailers – Teflon[®], stainless steel, or other appropriate inert materials
- Teflon[®] coated stainless steel cable with reels
- Peristaltic pumps and tubing
- Water level measuring devices – sufficiently accurate to measure water levels to the nearest 0.01 foot
- Graduated purge water containers
- Plastic sheeting
- Distilled or deionized water
- Decontamination equipment and supplies
- Organic vapor detector (OVD)
- Gloves (nitrile)
- Calculator and watch
- Sample containers precleaned to EPA specifications
- pH paper
- Custody tape
- Coolers with sufficient blue ice to cool samples to 4°C
- Preservatives (trace metals grade)
- Disposable in-line 0.45-micron membrane filters
- Logbooks and field forms
- Black waterproof pens
- Portable laboratory equipment for measuring field parameters for pH, temperature, specific conductance, and turbidity
- Total alkalinity reagent
- Beakers and graduated cylinders

Additional equipment may be required to meet project or client health and safety standards, to perform specialized sampling, or to meet personnel and equipment decontamination requirements.

4.3 Equipment Decontamination and Transport

Equipment associated with the tasks involved in groundwater sampling shall be decontaminated upon arrival at the sampling location. All sampling equipment shall be decontaminated between

sample locations. Decontamination frequency shall be increased appropriately as field conditions dictate.

Transportation of all equipment shall be performed in a manner that eliminates any possibility of cross-contamination. Calibration solutions, fuel, decontamination solutions and wastewater, and all other sources of contamination shall be segregated from sampling equipment during transport. Purge water being transported to holding areas shall be kept in closed containers.

If the decontamination of downhole equipment is not performed at the well, used downhole equipment shall be wrapped in plastic sheeting and/or segregated from clean equipment to eliminate the possibility of cross contamination. The equipment shall then be decontaminated as soon as possible.

4.3.1 Routine Field Decontamination

Decontamination of delicate equipment and the routine decontamination of sampling equipment prior to use at each well shall consist of the following steps:

- Vigorously scrub the equipment with a brush and solution of phosphate-free laboratory grade detergent (e.g., Liquinox) and distilled water.
- Rinse the equipment thoroughly with approved distilled water.
- If the decontaminated equipment is not immediately packaged to eliminate any adhesion of airborne impurities, perform an additional final rinse, or decontamination and rinse, immediately prior to actual sampling operations.

4.3.2 Routine Decontamination of Sampling Pumps

The external surfaces of all non-dedicated pumping equipment shall be decontaminated as described in Subsection 4.3.1. Internal surfaces shall be decontaminated according to the following procedures, except under special situations where the pump(s) must be disassembled and the internal parts cleaned separately (see Subsection 4.3.3). For routine decontamination, the following procedures shall be followed.

- Pump several pump volumes of a solution of a phosphate-free laboratory grade detergent (e.g., Liquinox) and water through the equipment.
- Displace the soap solution immediately by pumping approved distilled water, equivalent to three or more volumes of the pump storage capacity, through the equipment.
- If any detergent solution remains in the pump, continue pumping distilled water through the system until the detergent is no longer visibly present. Sudsing is the common indicator used to determine incomplete rinsing.

4.3.3 Unusual Decontamination Requirements

When equipment becomes grossly contaminated, such as from the collection of immiscible layer samples (see Subsection 4.5), routine decontamination of sampling equipment is not considered sufficient and thus is not allowed. This situation and other unusual equipment decontamination problems shall be reported to the field site supervisor. Under certain circumstances, a pump can be disassembled and the parts cleaned separately using approved solvents (i.e., hexane, alcohol, etc.). If specific instructions are required, the field site supervisor shall consult with a management representative for proper decontamination procedures.

4.3.4 Disposition of Decontamination Water

All water generated during the decontamination of equipment used for the sampling of wells shall be containerized in either a satellite container or in the purge water container in the groundwater sampling vehicle. It will then be disposed of according to the procedure designated in Subsection 4.6.3 of this procedure.

4.4 Site Preparation

Sheet plastic may be used to protect clean equipment from contacting contaminated surfaces. Plastic bags and sheeting, along with the segregation of clean and dirty equipment, can be used to reduce the chances of cross contamination. If a mechanical bailer retrieval system is used, the amount of plastic appropriate for protection of sampling equipment may be lessened. The sampling crew members are responsible for determining the amount of plastic sheeting required.

Disposable nitrile gloves, or gloves made of other approved materials, shall be used at all times when handling sampling equipment. Gloves shall be changed between each site and as often as necessary to ensure the integrity of clean sampling equipment.

4.5 Collection of Immiscible Layer Samples

When specified in the project sampling plan, or when the well to be sampled contains immiscible layers, immiscible phases must be collected before purging activities begin. The method of choice for collecting light non-aqueous phase liquids (LNAPLs) is a bottom valve bailer or peristaltic pump. Dense non-aqueous phase liquids (DNAPL) or “sinkers” shall be collected with a bottom double check valve bailer or peristaltic pump.

In all cases, the bailer shall be carefully lowered into the well so that agitation of the immiscible layer is minimal. Any bailer used to collect immiscible layers shall be dedicated to the well that is sampled. Peristaltic pumps shall be equipped entirely with silicon, or other chemical compatible tubing, when sampling immiscible layers. The project manager shall be responsible for determining the type materials to be used for specific projects. Dedicated equipment used for collecting immiscible layers shall be decontaminated prior to and after use as described in Subsection 4.3 of this procedure, if removed from the well.

Immiscible layer sampling shall be performed as follows.

- Remove dedicated bailers from the well and decontaminate as specified in Subsection 4.3 of this procedure. Decontaminate dedicated pump tubing, if used, prior to use.
- For LNAPLs, carefully lower the bailer intake or sampling port to the midpoint of the immiscible layer and allow it to fill while it is held at this level. The bailer must be lowered into the immiscible layer slowly so that minimal agitation of the immiscible layer occurs. Peristaltic pump intakes must also be lowered to the midpoint of the immiscible layer.
- If a DNAPL layer is being sampled, use either the double check valve bailer or peristaltic pump. Lower the bailer into the well until bottom is encountered. Lower peristaltic pump intakes also to the well bottom. Care must be taken not to immerse the pump intake into accumulated sediments.
- Do not allow the bailer or line to touch the ground at any time or allow the ground to come in contact with other physical objects that might introduce contaminants into the well.
- Decontaminate all equipment immediately after sampling is completed. Suspend dedicated bailers in the well from the well cap above the high water level. Discard silicon tubing used with peristaltic pumps.

4.6 Well Purging

Purging stagnant water from a well is required so that the collected sample is representative of the formation groundwater. The device used (bailer or pump) depends upon aquifer properties, individual well construction, and data quality objectives. Wells that contain immiscible layers will not be purged unless specified in the site-specific work plan. Any well scheduled for purging and sampling that subsequently is found to contain immiscible layers must be reported to the site supervisor or project manager. The project manager shall be notified immediately prior to continued activities.

Before obtaining water level elevations or initiating purge activities, obtain the following information in reference to the well to be sampled, and enter the applicable information on the sample collection log.

- Location code (well number)
- Previous purge volume (information only)
- Depth to top of screen (bailed wells only)
- Well sample number
- Report Identification Number (RIN)
- Sample event number

Record the location code (well number), date, sampling team members, visitors, well condition, and any other pertinent information on the sample collection log. Enter the well number, time well is opened, and other information regarding the field activities on the Field Activity Daily Log.

The field instruments shall be standardized (to check calibration) and the results recorded on the sample collection form.

Measure the depth to the top of the water column and the total depth of the well in order to determine the height of the water column in the well. Calculate the well casing volume using the well casing inner diameter and the height of the water column in the well. The formula for calculating the volume in gallons of water in the well casing is as follows:

$$(\pi r^2 h) 7.481 = \text{gallons; where}$$

$$\pi = 3.142$$

$$r = \text{inside radius of the well pipe in feet}$$

$$h = \text{linear feet of water in well}$$

$$7.481 = \text{gallons per cubic foot of water}$$

$$1 \text{ gallon} = 3785 \text{ ml}$$

Calculations of the volume of water in typical well casings may be done as follows:

a. 2" diameter well:

$$0.16 \text{ gal./ft} \times (\text{linear ft of water}) = \text{gallons of water}$$

b. 4" diameter well:

$$0.65 \text{ gal./ft} \times (\text{linear ft of water}) = \text{gallons of water}$$

c. 3/4" diameter well:

$$87 \text{ ml./ft} \times (\text{linear ft of water}) = \text{milliliters of water}$$

4.6.1 Purging Duration

Purging shall be considered complete if any of the following conditions are met.

1. Purging is complete if at least three casing volumes of water are removed from the well, and the last three consecutive pH, specific conductance, and temperature measurements do not deviate by more than the following: 1) pH = ± 0.1 pH units; 2) Specific Conductance = $\pm 10\%$ and; 3) temperature $\pm 0.5^\circ\text{C}$. A turbidity measurement will be taken for every other purge sample for wells that are purged using a bailer. For wells that are equipped with a dedicated bladder pump, the turbidity will be measured each time the parameters are taken. The purge rate should be such that the turbidity is maintained at 5 NTU units or less (if possible). If the readings are not stabilized after three volumes, continue purging until stabilization or until five volumes have been removed. Field parameter measurements shall be collected after every half-casing volume (approximate) is removed from the well. When casing volumes are less than 1-liter, parameter measurements will be collected after each whole casing volume is removed. If readings do not stabilize after five well volumes have been recovered, obtain additional guidance from the project manager concerning the proper course of action.
2. A well is considered dewatered when only a few milliliters of water (or none) can be recovered each time the bailer is lowered into the well. When this occurs, a 10-minute recharge rate will be calculated (linearly). If, at the end of the 10-minute period, the well has not recovered sufficiently to continue the purge in thirty minutes, the purge is considered completed. If, at the end of the 10-minute period, there is sufficient water to collect the VOA samples, the samples may be collected at that time. If the well has not recovered sufficient water during the 10 minutes, and depending upon the well history, the samplers may elect to return to the well the same day (preferably within two hours), check the water level, and collect the VOA samples (first), and other samples as feasible. If the sample team cannot return the same day, the well will be checked in 24 hours to determine if sample collection is feasible. If an extended period of time is required to collect samples, the procedures in Subsection 4.8.1 shall be followed. The well will not require an additional purge before sampling.

Wells that dewater (have a slow recharge rate as specified in 2 above) will not be restricted by parameter stabilization requirements. Sampling of these wells will follow the protocol established in Subsection 4.8.

4.6.2 Purging Methods

Wells will be purged by either bailing or pumping. When purging a well, the rate of water withdrawal during purging should not exceed the rate of withdrawal at which the well was developed (if known). All purge times (initiation and completion) and the rate of purging will be recorded on the field log sheets.

4.6.2.1 Bailing

Generalized procedures for purging a well with a bailer are as follows.

- Prepare the sampling site as discussed in Subsection 4.4. Use properly decontaminated equipment to determine the static water level of the well. Measure the total depth of the well. Use this information to determine the volume of water in the well casing.

- Decontaminate all dedicated bailers prior to initiating purging as described in Subsection 4.3 of this procedure.
- Use a mechanical reel equipped with Teflon[®] coated stainless steel cable attached to a bailer for bailing and sampling operations. Lower the bailer slowly into the well until water is encountered. Minimize agitation of the well water. Avoid lowering the bailer to the bottom of the well so sediments accumulated in the bottom do not become suspended. For wells that dewater, do not allow the bailer to strike the well bottom with force. Raise and lower the bailer carefully to limit surge energy and ensure that cable does not come in contact with any potentially contaminated surfaces. Do not allow the cable to drag along the well casing or against other objects that will cause fraying. Monitor the amount of water purged.

Wells with significant levels of contamination may have dedicated bailers installed. Dedicated bailer systems shall consist of a Teflon[®] bailer with check valve or double check valve for DNAPLS and a 5-foot leader of Teflon[®] coated stainless steel cable. Bailer sampling attachments and the stainless steel reel cable will not be dedicated to individual wells.

Dedicated bailers will be decontaminated at the conclusion of sampling activities and suspended from the well cap above the high water table. If the well interval above the high water table is not adequate to allow for storage in the casing, the dedicated bailers will be stored in labeled and sealed plastic bags at the equipment trailer.

4.6.2.2 Pumping

Pump designs that meet the following criteria are allowed for purging.

- The pump is constructed of a material that does not introduce a source of contamination to the well.
- The pump drive system does not introduce a source of contamination into the well.
- All downhole parts to the pump can be easily decontaminated.
- A return check system that does not allow pumped water to return to the well is integral in the pump design.
- The pump is easily used and does not require excessive amounts of time to install, use, remove, and decontaminate.

The pumps currently in use to purge groundwater include peristaltic pumps and dedicated submersible bladder pumps. A procedure for the use of each style of pump is specific to its applications. User manuals, which accompany each pump, shall be referenced for operating procedures.

Basic operating procedures common to all pumps are as follows.

- Prepare the sampling site as described in Subsection 4.4 regardless of the type of pump being used.
- Use properly decontaminated equipment to determine the static water level and the total depth of the well. This information is utilized to determine the volume of water in the well casing.

- For wells with dedicated pumps, calculate the minimum purge volume using the pump storage volume and the volume of the discharge tubing. A total depth of a 2-inch well cannot be taken without the removal of the pump.
- Position a dedicated pump near the bottom of the well or according to the information on the well construction form. Monitor the discharge rates and the amount of water purged during purging. The pumping rate for purging can be higher than the pumping rate for sampling, however, the water level in the well should be monitored during purging to avoid excessive water level drawdown.
- Ensure that any tubing that enters the well casing is composed of inert material. Disposable silicon tubing will be used in the drive mechanism of peristaltic pumps and discarded after each well is purged. The air supply for all air-driven pumps (dedicated bladder pumps) will be free of oil (i.e., no hydrocarbon containing substances will be added to the compressor).

4.6.3 Disposition of Purge Water

All water removed from a well during sampling operations shall be collected either in a satellite container or the purge water collection container in the groundwater sampling vehicle. The water from these containers will then be transferred to another approved collection container on the sampling or project site. When the collection container is filled, or is near capacity, it will be transported for disposition or treatment in accordance with approved project plans.

4.7 Measurement of Field Parameters

The following field parameters will be measured during groundwater purging operations unless otherwise specified by the project manager or the approved project work plans.

Parameter	Relative Precision	Minimum Calibration
pH	0.01 pH units	Daily
Conductivity	10 μ S/cm	Daily
Temperature	0.1 °C	Weekly
Total Alkalinity (unfiltered)	1 mg/l	None
Turbidity (photometric)	2 FTU (or NTU)	Specified purge samples (bailed wells) Daily (dedicated bladder pump wells)

The measuring equipment shall be stored and handled in a manner that will maintain the integrity of the equipment. Appropriate field manuals will accompany each instrument in the field. Each instrument will also be given an identification number. All logbook and field form references to individual instruments will refer to this number for ease of identification.

Field parameters will be measured at the following intervals.

- Conductivity, pH, temperature, and turbidity shall be measured from the first water removed from the well when initiating well purging procedures. For bailed wells, the initial bail of water will be carefully removed from the well and the water transferred to a sample beaker by decanting the bailer through a bottom control valve. For wells

purged with a peristaltic pump, similarly collect the first water removed in a sample beaker and then measure parameters. For wells with dedicated pumps, measure the parameters of the first recovered water that is collected in the continuous sampler.

- During purging operations, conductivity, pH, and temperature shall be measured for every half-casing volume (one half of the initial casing volume as calculated on the sample collection log form) of water removed from the well (because of the accuracy of the graduated containers for the purge water, the purge volume will be estimated as close as feasible). For wells that have half volumes less than the volume of a sample bailer (approximately 1 liter), only measure parameters after each full casing volume of water is removed from the well. Turbidity will be measured on every other sample recovered for parameters for bailed wells, or wells purged with a peristaltic pump. All parameters, including turbidity, will be measured at predetermined intervals while purging wells with dedicated pumps.
- During purging, if a well is dewatered prior to the measurement of the final required set of parameters, then conductivity, pH, temperature, and turbidity shall be measured immediately before the start of sample collection. These parameters may be delayed until sampling is completed if, at the discretion of the sampling crew, the well recharge has provided insufficient water volume to collect all the samples and also measure parameters. If there is insufficient water for samples and field parameters, the parameters will not be measured.
- Total alkalinity measurements shall be collected only once upon completion of purging. For wells that do not dewater and sample collection proceeds to completion immediately after purging, alkalinity will be measured after the completion of all other final purge field parameters. Wells that dewater and require repeated visits for the collection of samples will have alkalinity measured subsequent to the collection of the sample for inorganic water chemistry. Alkalinity will not be measured if sufficient water is not available.
- For micro purged wells, a purge is considered completed when the parameters have stabilized.
- Whenever a method used to remove well water is changed, a set of field parameters shall be recorded from water removed with the new method.

4.8 Groundwater Sampling

Techniques used to withdraw groundwater samples from a well shall be based on consideration of the parameters of interest. The order of collection, collection techniques, choice of sample containers, preservatives, and equipment are all critical to ensuring that samples are not altered or contaminated. The preferred methods for collection of groundwater samples are either bailing and/or the use of bladder pumps.

Sites shall be prepared prior to sampling as described in Subsection 4.4. All necessary and appropriate information will be recorded on the sample collection log and on the Field Activity Daily Log.

4.8.1 Sample Collection

The following discussion involves collection of groundwater samples using bailers and peristaltic or bladder pumps. Regardless of the collection method, care shall be taken not to alter the chemical nature of the sample during the collection activity by agitating the sample or allowing prolonged contact with the atmosphere. To minimize the potential for

altering the sample and to maximize the available water, the following sample collection sequence is preferred.

- Radiation Screening
- VOC
- Nitrate/Nitrite, as N
- Dissolved Metals – TAL, with Cs, Li, Sr, Sn, Mo, Si
- ^{239/240}Plutonium, ²⁴¹Americium
- ^{233/234}U, ²³⁵U, ²³⁸U
- Gross alpha and beta
- ⁸⁹Strontium
- ¹³⁷Cesium
- ^{226,228}Radium
- Tritium
- Total Metals – TAL, with Cs, Li, Sr, Sn, Mo, Si
- TDS, CL, F, SO⁴, CO₃, HCO³
- TSS
- BNA
- Pesticides/PCB
- Cyanide
- Orthophosphate

VOC samples shall be collected first and as soon as possible after the well has been purged. If a well is purged using a peristaltic pump, then all other samples shall be collected prior to removing the pump from the well. The VOC sample will then be collected using a bailer.

For wells that dewater, if a sufficient volume of water for VOC sample collection has still not accumulated within 48 hours after the completion of purging, VOCs will not be collected for that well. Other samples may be collected using a maximum of five attempts to recover sufficient sample water for analysis. This procedure is discussed in the following paragraph.

The containers used for sample collection from poor producing wells may differ from those used for high yield wells in some instances due to constraints on obtaining enough sample to fill sample containers. In some instances smaller containers may be utilized, or analyte samples normally collected in separate containers may be combined into a single container. Well histories can be used to identify which wells may require a modified sample suite and an extended sampling period. These wells will initially be sampled for a period of 48 hours after the completion of purging, with the exception of VOC sample collection, which is discussed in the previous paragraphs. The completion of purging will be considered 0 hour. At the end of 48 hours, any partial sample will be measured. The accumulated sample will be compared to the minimum volume requirement identified in Table 1 and the allowed sample holding time. If the minimum volume requirement for the target analyte has not been achieved, then sampling may continue as determined from the well recharge

history. All analyte samples that have only minimum sample volumes collected, and all uncollected samples will be documented on the sample collection log.

Table 1
Sample Containers and Preservatives for Groundwater Samples

Parameter	Minimum Container ¹	Preservative	Holding Time
Radiation Screen	120 ml poly	None	NA
VOC - CLP	3 – 40 ml amber glass	Cool to 4° C	4 Days
BNA	1 L amber glass	Cool to 4° C	7 Days
Pesticides/PCB	1 L amber glass	Cool to 4° C	7 Days
TSS	125 ml poly	Cool to 4° C	7 Days
TDS, Cl, F, SO ₄ , CO ₃ , HCO ₃	1 L poly	Cool to 4° C	7 Days
Dissolved Metals - CLP, with Cs, Li, Sr, Sn, Mo, Si	1 L poly	*Filtered, HNO ₃ to pH <2, Cool to 4° C	6 Months
TOC	125 ml poly	H ₂ SO ₄ < pH2, Cool to 4° C	28 Days
COD	125 ml poly	H ₂ SO ₄ < pH2, Cool to 4° C	28 Days
Total Metals - CLP with Cs, Li, Sr, Sn, Mo, Si	1 L poly	Unfiltered, HNO ₃ to pH <2, Cool to 4° C	6 Months
Orthophosphate	250 ml poly	Filtered, Cool to 4° C	2 Days
Nitrate / Nitrite as N	250 ml poly	H ₂ SO ₄ to pH <2, Cool to 4° C	28 Days
Cyanide	1 L poly	NaOH to pH >12, Cool to 4° C	14 Days
Gross Alpha / Beta	550 ml poly	HNO ₃ to pH <2	6 Months
^{233/234} U, ²³⁵ U, ²³⁸ U	100 ml poly	Filtered, HNO ₃ to pH <2	6 Months
^{239/240} Pu	1 L poly	HNO ₃ to pH <2	6 Months
²⁴¹ Am	1 L poly	HNO ₃ to pH <2	6 Months
^{89/90} Sr	700 ml poly	Filtered, HNO ₃ to pH <2	6 Months
^{226/228} Ra	750 ml poly	Filtered, HNO ₃ to pH <2	6 Months
¹³⁷ Cs	2.5 L poly	Filtered, HNO ₃ to pH <2	6 Months

¹ The volume listed is the minimum amount required for analysis. Actual sample volumes may be slightly higher and some parameters may be combined in a single container.

* Some samples may not require filtering if taken from a well with a dedicated pump and turbidity of 5 NTU or less.

The order of sample collection may be changed at the discretion of the sampling team. Changes in the order shall be based on the predicted volume of water that will be recovered and the priority stated in the controlling document. The sampling team shall document their sample selections on the sample collection log.

Sample containers shall be stored away from sunlight and cooled to 4°C prior to filling. Immediately after collection, samples requiring cooling shall be cooled to 4°C. A chilled cooler shall be used as the storage container. Whenever a sample bottle that requires chilling is not being physically handled, it will be placed in the cooler to prevent heating or freezing, exposure to sunlight, and possible breakage.

VOC samples shall be collected using a bailer equipped with a bottom-decanting control valve or directly from the pump discharge line on wells equipped with bladder pumps. The procedures for collecting VOC samples are discussed in Subsections 4.8.1.1 and 4.8.1.2 of this procedure.

VOC vials shall never be filled and stored below capacity because of insufficient quantities of water in the well. Except for the VOC vials, adequate air space should be left in the sample bottles to allow for expansion.

Samples shall be placed in the appropriate containers and packed with ice in coolers as soon as practical. VOC samples will be stored in the cooler in an inverted position immediately after collection. When sampling is complete, the well cap shall be replaced and locked.

Sampling tools, instruments, and equipment shall be protected from sources of contamination before use and decontaminated after use as specified in Subsection 4.3. *Liquids from decontamination operations will be handled in accordance with the procedures in Subsection 4.6.3 of this procedure.* Sample containers shall also be protected from sources of contamination. Sampling personnel shall wear chemical-resistant gloves (e.g., nitrile) when handling samples, and the gloves will be disposed of between well sites.

4.8.1.1 Groundwater Sampling Using a Bailer

This subsection describes the use of a bailer for collecting groundwater samples that may be used to obtain physical, chemical, or radiological data.

A bailer attached to a Teflon[®] coated stainless steel cable is carefully lowered into the well. After filling within the well, the bailer is withdrawn by rewinding the bailer line, and the bailer contents are drained into the appropriate containers. Certain recommendations and/or constraints should be observed when using bailers for sampling groundwater monitoring wells, as follows.

- Use only bottom-filling Teflon[®] bailers or bailers made of other inert materials.
- Ensure that bailers are attached to a Teflon[®] coated stainless steel line that is pre-wound on a reel.
- Do not use bailers constructed with adhesive joints.
- Lower the bailer slowly to the interval from which the sample is to be collected.

VOC samples shall be collected using a bailer equipped with a bottom-decanting control valve. The first water through the valve assembly will be discarded into the purge water container. Vials will be filled by dispensing water through the control valve along the inside edge of the slightly tilted sample vial. Care shall be taken to eliminate aeration of the sample water. The vials will be filled beyond capacity so the resulting meniscus will produce an airtight seal when capped. The capped vial will be checked for trapped air by lightly tapping the vial in an inverted position. If air becomes trapped in the vial, the sample water shall be discarded, and the vial refilled. If two consecutive attempts to fill a VOC vial result in trapped air bubbles, the vial shall be discarded.

The remainder of the sampling water shall be collected in a stainless steel container from which the remaining sample bottles will be filled. Samples requiring filtration shall be filtered and then containerized.

4.8.1.2 Groundwater Sampling Using a Peristaltic Pump

Use of peristaltic pumps shall generally be limited to collecting sample aliquots for radionuclides, metals, and other species that are not subject to volatilization and degassing. Peristaltic pumps shall never be used to collect VOCs or other

volatile species in routine wells, although such samples may be collected for special screening applications. All downhole tubing shall be Teflon[®] except in areas of special concern (e.g., where immiscible layers exist) where special tubing, such as stainless steel or Viton[®], may be required. If so, the project manager will make this determination. Only the portion of tubing that is inserted into the mechanical drive shall be made of silicon. This drive portion of the tubing shall be discarded after each use.

4.8.1.3 Groundwater Sampling Using a Downhole Bladder Pump

Some wells are equipped with dedicated downhole bladder pumps for purging and sampling. These are wells that will normally produce an adequate amount of water during a single visit to complete the required sampling suite. The equipment required to purge and sample a well consists of a pump control unit, a portable air compressor, a continuous sampler for measuring the field parameters, and the necessary sample containers, graduated cylinders, and container(s) to collect the purge and excess water. The following precautions should be observed during the sampling operation.

- Locate the compressor used to power the pump downwind from the well to eliminate the contamination of equipment and samples with exhaust.
- If the flow-through cell will not maintain a full sample chamber (tends to drain back), then clean the check valve on the pump if it is fouled, or replace the pump.
- Calculate the minimum purge volume using the procedure in Section 4.6. Note that a purge is considered completed only when the groundwater parameters have stabilized.
- Upon completion of purging, initiate sampling with the collection of the VOC sample(s). The pump should operate with minimum interruptions while the full sample suite is collected. Allowing the pump to stop for an extended period of time will cause the water trapped in the discharge lines to equilibrate to ambient temperatures, which is not acceptable. During sampling, the pump can be slowed to any rate that allows efficient sampling while also maintaining stable field parameters.
- Measure groundwater parameters periodically during sample collection and record them on the sample collection log to document conditions during sampling.
- Because micropurging is the method used for sampling, adjust the flow rate to limit the drawdown in the well. Also adjust the rate such that the turbidity is below 5 NTU for sampling. If this criterion is met, the samples need not be filtered.
- Operate the pump, pump control unit, and the flow-through cell according to the manufacturer's recommendations.

4.8.1.4 Groundwater Sampling Using a Push Type Sampler

This portion of this procedure describes the use of a Geoprobe[®] Screen Point 15 Groundwater Sampler, or similar type equipment, for collecting groundwater samples at predetermined depths. These samples may be used to obtain physical, chemical, or radiological analyses.

A Geoprobe® Screen Point 15 Groundwater Sampler, or equivalent tool, is driven to a predetermined depth by a push type-sampling rig. The Screen Point 15 Groundwater Sampler is equipped with a 41-inch retractable screen and expendable drive point. It can then be partially or fully withdrawn (up to 41 inches) to expose a portion or the entire deployed well screen. After groundwater enters the exposed screen, a sample is collected using either the procedures in Subsection 4.8.1.1, Groundwater Sampling Using a Bailer, or in Section 4.8.1.2, Groundwater Sampling Using a Peristaltic Pump. Note that these samples are collected only for screening purposes because the sampling tool hole has not been completed as a well.

The method for obtaining QC samples using the push type-sampling tool is provided in Subsection 4.8.4.1 for groundwater sampling. Duplicate groundwater samples shall be collected only if there is enough water to collect two full suites of analytes without dewatering the annulus. If insufficient water is available for the collection of a planned QC sample, it shall be explained and documented in the field log book, and the project manager informed. If insufficient water is available for two full suites of analytes, it may be necessary to prioritize the analyte list. The prioritization sequence should be described in the project-specific work plan.

4.8.2 Sample Filtering and Preservation

Samples for dissolved metals, Gross Alpha/Beta, ^{233/234}Uranium, ²³⁵Uranium, ²³⁸Uranium, ^{89/90}Strontium, ¹³⁷Cesium, ²²⁶Radium, ²²⁸Radium, and orthophosphate shall be filtered in the field at the well location during the sampling event through a disposable 0.45-micrometer membrane filter. If a peristaltic or bladder pump is used, a disposable filter may be attached directly to the sample delivery line so that the sample is filtered directly into the sample container as it exits the delivery line. Discharge pressure shall be gauged so it does not exceed 50 psi. Alternatively, sample water may be collected in a stainless steel container and filtered with a peristaltic pump. Before sample collection, 100 to 200 milliliters of sample water shall be passed through the filter in order to rinse the filter and filtration apparatus of possible contaminating substances.

Preservatives shall be added to the sample bottles prior to the introduction of the filtered sample water. The preservative shall be added in aliquots appropriate to the size of the bottle.

After sample collection has been completed, the pH of preserved samples shall be checked as follows.

- Pour a small amount of sample from the sample bottle directly onto approved pH paper. Use care so that the threaded neck of the bottle does not contact the pH paper. Do not, under any circumstances, insert the pH paper into the sample bottle.
- Check the pH paper against the supplied color chart. If the appropriate pH has not been achieved, add additional preservative to the sample in 5 ml aliquots and repeat the pH test after each addition.

4.8.3 QA/QC Samples

The frequency and types of field QA/QC samples collected during groundwater sampling are described in project-specific work plans or quality assurance plan documents. These documents detail the applicable criteria for collecting QA/QC samples.

4.8.3.1 Duplicates

Duplicate samples shall be collected only from wells that produce enough water to collect two full suites of analytes without dewatering. Wells that produce sufficient water shall be incorporated into the sampling program such that the required duplicate frequency can be maintained.

Wells scheduled for duplicate sample collection shall be sampled as described in Subsection 4.8 of this procedure, and in relevant sections of project-specific work plans and/or quality assurance documents. Field duplicates are collected following the same sampling procedures used to obtain the real samples. With the exception of VOCs, the typical procedure for a location is to collect the real and duplicate of each sample at the same time, in two equal portions, with each portion going to the laboratory in separate containers. This is accomplished by alternately filling two sample bottles one half at a time to minimize heterogeneity. Note that real and duplicate VOC samples shall be collected independently to reduce the possibility of volatilization of the sample.

When a well with a dedicated pump is being used for sample collection, all samples shall be collected in the normal order, with duplicate VOC samples being collected first. The remaining samples will be sampled as described above.

If a well is being used for matrix spike (MS) and matrix spike duplicate (MSD) samples, the duplicate shall be collected after collection of the MS and MSD.

All duplicate samples shall be given a sample number different from the original sample and the information recorded on the sample collection log and/or the field QC sample collection log.

4.8.3.2 Matrix Spike and Matrix Spike Duplicate

MS and MSD samples shall be collected only from wells that produce enough water to collect the required suites of analytes without dewatering. MS and MSD samples are not collected on a routine basis, but will be collected if so designated in a site-specific sampling plans, or if requested by the project manager.

MS and MSD samples shall be collected as follows.

- Purge the well as described in Subsection 4.6 of this procedure..
- After completion of purging, collect VOC samples. Collect the real sample followed by the MS and MSD. Collect these samples in immediate succession.
- Collect the remaining samples not requiring filtering. For each sample parameter, collect the original sample, MS, and MSD concurrently. Fill the original sample bottle one-third full followed by the MS and MSD sample bottles, which are also filled one-third full. Rotate each bottle in the sequence, filling in one-third full until all three bottles are full. For analytes not requiring an MSD, collect only the original sample and the MS.
- After the real sample, MS, and MSD (where appropriate) are collected for one parameter, repeat the process for the next parameter.
- Similarly, collect samples requiring filtering. When a bailer is used, fill a stainless steel bucket with sample water. As samples are collected and the reservoir of water in the bucket is depleted, add more water with discretion. When a pump is used, attach the filter directly to the discharge line. Fill

sample bottles as described above, partially filling the original sample, MS, and MSD in rotating sequence until each parameter bottle is full.

- Radiochemistry samples may have more than one bottle for each parameter group. In this case, include all required bottles in the rotating sequence.
- Field parameter measurements are not be required for MS and MSD samples.
- Retain the original sample number for MS and MSD samples. However, add a suffix of MS or MSD to the sample number to correspond with each QA/QC sample. Record all information on the field QC groundwater sample collection log.

4.8.3.3 Replicates and Splits

Replicate and split samples shall be collected in the same manner as described for the MS and MSD. Seek instruction from the project manager for replicates and splits exceeding three samples. Record all information will be recorded on the groundwater sample collection logs.

4.8.3.4 Field Equipment Rinses

Wells scheduled for equipment rinsate samples shall be sampled as described in Subsection 4.8 of this procedure, and field equipment rinses shall be collected as described in this Subsection and in relevant portions of project-specific QC documents and work plans. Field equipment rinses shall be collected in a manner designed to reflect sampling techniques. All equipment used during sampling will be fully decontaminated as described in Subsection 4.3, then rinsed with distilled or deionized water. The rinse water will then be collected in bottles identical to those used for the original sample, and assigned a separate sample number. Analytes requiring filtration will be filtered using a new filter and tubing as required for the real sample. All information will be recorded on groundwater sample collection logs.

4.8.3.4.1 Bailed Wells

After completion of sampling, all equipment shall be decontaminated. Prior to leaving the well location, the equipment rinse will then be collected as follows.

- Fill the bailer with distilled or deionized water by pouring the water into the top opening.
- Decant the rinse water to the VOC vials through the bottom valve just as was done during sample collection.
- For the remaining unfiltered samples, fill the bailer with distilled or deionized water each time additional rinsate is needed. Transfer the rinsate to sample bottles or to a stainless steel bucket and then to sample containers in the same manner used during collection.
- Collect filtered samples in an identical manner as the real samples. Fill the bailer with distilled or deionized water. Then transfer the rinse water to a stainless steel bucket. Filter the rinse water in the bucket through a new disposable filter.

- Preserve rinse samples in the same manner as the real samples.

4.8.3.4.2 Pumped Wells

Rinsate samples are not routinely collected from wells that are equipped with dedicated bladder pumps because the samples from these wells are collected directly from the pump discharge line. However, wells sampled using peristaltic pumps for sampling may be selected for rinsate sampling, with equipment used in sample collection (down hole tubing, filter tubing and the stainless steel bucket used for sample water collection, etc.) being decontaminated prior to rinsate sampling. The tubing at the pump head will be replaced, and a new filter used for filtered analytes. To collect the samples, distilled or deionized water will be poured into the decontaminated stainless steel bucket and pumped, using the decontaminated tubing, into the sample containers. The equipment used to collect the real VOC samples will also be decontaminated, rinsed, and used to collect the VOC rinse samples. All samples will be preserved at the same pH levels as the real samples.

4.8.3.5 Distilled Water Blanks

Distilled water sample blanks are not submitted on a routine basis, but will be made up if so designated in a site-specific sampling plan. Samples of the distilled or deionized water used for the final decontamination of equipment will be transferred directly to sample bottles to determine any baseline contamination the water may have introduced into the samples. Five-gallon bottles of the distilled or deionized water will be opened in a controlled area, such as the bottle storage room, and then poured directly into the appropriate sample bottle. A Teflon[®], glass, or stainless steel funnel may be used to help control flows into small mouth bottles. Blank samples will be preserved to the appropriate pH required for each analyte. All information will be recorded on groundwater sample collection logs.

4.9 Sample Handling and Control

Pre-cleaned sample containers will be obtained from a contract analytical sample container source. Preserving solution will be added to the bottles by a laboratory, the sample manager or qualified sampling personnel. The bottles will be labeled to indicate the preservative added.

The sampling containers, preservation requirements, and holding times for the various types of analyses are shown in Table 1. Groundwater samples will be properly labeled so that they can be easily identified. The sample numbering system will be assigned by project-specific sampling plan documents. A sample identification (ID) number will be assigned to each sample suite. The sample ID number will contain the following information as part of a nine to twelve character, alpha-numeric code:

Character(s)	Description	Code
1 and 2	Project ID	GW
3 through 7	Sample Number	00001 to 99999
8 and 9	Subcontractor ID	Alpha (e.g. TE = Tierra Environmental Consultants)
10, 11, and 12	QA/QC	MS for matrix spike, MSD for matrix spike duplicate

In addition to a sample number, each well sampled will be assigned a current Record Identification Number (RIN), an event number (specific to the RIN), and bottle numbers that are specific to the RIN and event number.

5.0 Records

All field activities shall be recorded on a Field Activity Daily Log or Groundwater Sample Collection Log. Additional logs may be required to record QC samples and for recording well status. Refer to specific project, site, or facility work plans for further information. Summary information of the day's activities or other pertinent information should always be recorded on the field forms. Under some circumstances, the project manager may assign a bound field logbook to the field personnel that will remain in their custody during all sampling activities. The cover of each logbook shall contain the following information at a minimum:

- Name of the organization to which the book is assigned
- Book number
- Project name
- Start and end dates

Logbook pages shall be sequentially numbered and marked with the book number before any data are recorded. All data and information pertinent to field sampling shall be recorded in the logbook or on the field forms that identify all required data entries. Enough detail must be included in the documentation to reconstruct the sampling event. Field form entries shall include the following minimum information:

- Date and time
- Names of field personnel
- Names of all visitors
- Location of field activities
- Description of sampling sites including weather conditions
- All field observations and comments
- Field parameters
- Sample identification information
- References to all prepared field activity forms and chain-of-custody records

Field logbooks, when required on specific projects, shall normally be kept only by the field sampling team leaders and the site supervisor and shall typically be used only to summarize field activities and to document project information not required by the procedure field forms.

Permanent ink shall be used for all entries in the logbooks and on the field forms. Mistakes shall be crossed out with a single line, initialed, and dated. Unused pages or partial pages shall be voided by drawing a line through the blank sections and initialing and dating the mark. Any deviation from this procedure shall require documentation in the site supervisor's logbook.

The field activity daily log narrative should create a chronological record of the sampling team's activities, including the time and location of each activity. Descriptions of problems encountered, personnel contacted, deviations from the procedure, and visitors on site shall also be included. The weather conditions, date, signature of the person responsible for entries, and the number of field activity daily log sheets used to record media team activities for a given day shall also be included.

The Groundwater Levels Measurement/Calculations Form and the Chain of Custody Record (see *Containing, Preserving, Handling, and Shipping Soil and Water Samples*) shall also be completed for each site. All blank fields on the forms must be completed or voided.

6.0 References

- Environmental Protection Agency, 1982, Test Methods for Evaluating Solid Waste, SW-846, Volume II. Field Methods, 2nd edition.
- Environmental Protection Agency, 1986a, Engineering Support Branch Standard Operating Procedures and Quality Assurance Manual, EPA Region IV Environmental Service Division.
- Environmental Protection Agency, September 1986b, RCRA Ground Water Monitoring Technical Enforcement Guidance Document, OSWER-9950.1.
- Environmental Protection Agency, 1987a, A Compendium of Superfund Field Operations Methods, EPA/540/P-87/001. 1987.
- Environmental Protection Agency, 1987b, Data Quality Objectives for Remedial Activities, Development Process, EPA/540/G-87/003.
- Environmental Protection Agency, December 1988, User's Guide to the Contract Laboratory Program.

APPENDIX A
STANDARD GROUNDWATER FORMS

Appendix B
Sample Collection Forms

SM Stoller Corp.

105 Technology Dr., Suite 190
Broomfield, CO 80021
(303) 546-4300

Project Name: <i>Colorado School of Mines</i>	Sample Location: <i>CSMRI-1</i>
Project Number: <i>4349-250</i>	Date: <i>9/9/10</i>
Sample Type: <input checked="" type="checkbox"/> SW <input type="checkbox"/> SW <input type="checkbox"/> EB Duplicate Other:	Sampler: <i>N Malczyk</i>

Purge Volume Calculations		Sample Collection				
Measured TD =	<i>25.05</i> (ft) (+.28)	Analysis	Container	Preservative	Date	Time
Total Depth =	<i>25.33</i> (ft)	<i>Re-226 -228 Diss. U</i>	<i>1 gal cube</i>	<i>HNO₃</i>	<i>9/9/10</i>	<i>1200</i>
Depth to Water =	<i>7.80</i> (ft)	<i>Cations</i>	<i>500mL Plastic</i>	<i>HNO₃</i>	<i>9/9/10</i>	<i>1200</i>
Initial Water Column =	<i>17.53</i> (ft)	<i>Anions</i>	<i>500mL Plastic</i>	<i>-</i>	<i>9/9/10</i>	<i>1200</i>
Initial Water Volume =	<i>2.80</i> (gal)	<i>DOC</i>	<i>125mL Amber</i>	<i>H₂SO₄</i>	<i>9/9/10</i>	<i>1200</i>
3 X Water Volume	<i>8.40</i> (gal)	Lab: <i>ALS - Ft. Collins, Test America - Arvada</i>				

Purge Volumes and Field Water Quality Measurements								
Time	Volume (gal)	Temperature (°C/°F)	pH (SU)	Conductivity (uS/cm)	DO (mg/L)	ORP (mV)	Turbidity (NTU)	Appearance
<i>1141</i>	<i>1.40</i>	<i>14.18</i>	<i>7.44</i>	<i>900</i>	<i>12.48</i>	<i>136</i>	<i>364</i>	<i>Green</i>
<i>1144</i>	<i>2.80</i>	<i>13.62</i>	<i>7.35</i>	<i>900</i>	<i>8.39</i>	<i>125</i>	<i>1000+</i>	↓
<i>1147</i>	<i>4.20</i>	<i>13.79</i>	<i>7.15</i>	<i>999</i>	<i>11.05</i>	<i>150</i>	<i>1000+</i>	
<i>1150</i>	<i>5.60</i>	<i>13.73</i>	<i>7.16</i>	<i>999</i>	<i>10.69</i>	<i>158</i>	<i>1000+</i>	
<i>1153</i>	<i>7.00</i>	<i>14.01</i>	<i>7.02</i>	<i>999</i>	<i>7.37</i>	<i>165</i>	<i>1000+</i>	
<i>1157</i>	<i>8.40</i>	<i>13.83</i>	<i>7.05</i>	<i>900</i>	<i>6.28</i>	<i>165</i>	<i>1000+</i>	
Volume purged: <i>conductivity meter doesn't seem to be working</i>								

Comments:	Analysis	Container	Preservative	Date	Time
TA	<i>NO₂, NO₃</i>	<i>1L Plastic</i>	<i>none</i>	<i>9/9/10</i>	<i>1200</i>
TA	<i>TDS</i>	<i>1L Plastic</i>	<i>none</i>	<i>9/9/10</i>	<i>1200</i>
TA	<i>Ferrous Fe</i>	<i>1L Plastic</i>	<i>none</i>	<i>9/10/10</i>	<i>1200</i>
TA	<i>Ferrous Fe</i>	<i>500mL Plastic</i>	<i>HNO₃</i>	<i>9/10/10</i>	<i>1200</i>
TA	<i>Sulfide</i>	<i>250mL Plastic</i>	<i>Zn Ac</i>	<i>9/10/10</i>	<i>1200</i>

SM Stoller Corp.

105 Technology Dr., Suite 190
Broomfield, CO 80021
(303) 546-4300

Project Name: <i>Colorado School of Mines</i>	Sample Location: <i>CSMRI-113</i>
Project Number: <i>4349-250</i>	Date: <i>9/7/10, 9/8/10</i>
Sample Type: <u>GW</u> SW EB Duplicate Other:	Sampler: <i>N Malczyk</i>

Purge Volume Calculations		Sample Collection				
Measured TD =	<i>23.40</i> (ft) (+.28)	Analysis	Container	Preservative	Date	Time
Total Depth =	<i>23.65</i> (ft)	<i>Re-226 -228</i>	<i>1 gal</i>			
Depth to Water =	<i>18.44</i> (ft)	<i>Dist. U</i>	<i>cube</i>	<i>HNO₃</i>	<i>9/8/10</i>	<i>0900</i>
Initial Water Column =	<i>5.24</i> (ft)	<i>Cations</i>	<i>500mL</i>	<i>HNO₃</i>	<i>9/8/10</i>	<i>0900</i>
Initial Water Volume =	<i>.84</i> (gal)	<i>Anions</i>	<i>Plastic</i>	<i>-</i>	<i>9/8/10</i>	<i>0900</i>
3 X Water Volume	<i>2.52</i> (gal)	<i>DOC</i>	<i>Amber</i>	<i>H₂SO₄</i>	<i>9/8/10</i>	<i>0900</i>
Lab: <i>ALS - Ft. Collins, Test America - Arvada</i>						

Purge Volumes and Field Water Quality Measurements								
Time	Volume (gal)	Temperature (C, °F)	pH (SU)	Conductivity (uS/cm)	DO (mg/L)	ORP (mV)	Turbidity (NTU)	Appearance
<i>1327</i>	<i>0.84</i>	<i>14.04</i>	<i>6.87</i>	<i>1090</i>	<i>4.96</i>	<i>97</i>	<i>61.8</i>	<i>clear</i>
<i>1330</i>	<i>1.68</i>	<i>13.05</i>	<i>6.90</i>	<i>960</i>	<i>5.56</i>	<i>68</i>	<i>502</i>	<i>black</i>
<i>1333</i>	<i>2.52</i>	<i>13.12</i>	<i>6.85</i>	<i>940</i>	<i>9.62</i>	<i>98</i>	<i>1000+</i>	<i>↓</i>
<i>nen</i>								
Volume purged: <i>2.52 gal</i>								

Comments:	Analysis	Container	Preservative	Date	Time
<i>TA</i>	<i>NO₂, NO₃</i>	<i>1L Plastic</i>	<i>none</i>	<i>9/8/10</i>	<i>0900</i>
<i>TA</i>	<i>TDS</i>	<i>1L Plastic</i>	<i>none</i>	<i>9/8/10</i>	<i>0900</i>
<i>TA</i>	<i>Ferrous Fe</i>	<i>1L Plastic</i>	<i>none</i>	<i>9/10/10</i>	<i>nen</i>
<i>TA</i>	<i>Ferric Fe</i>	<i>500mL Plastic</i>	<i>HNO₃</i>	<i>9/10/10</i>	<i>nen</i>
<i>TA</i>	<i>Sulfide</i>	<i>250mL Plastic</i>	<i>Zn Ac</i>	<i>9/10/10</i>	<i>nen</i>

SM Stoller Corp.

105 Technology Dr., Suite 190
Broomfield, CO 80021
(303) 546-4300

Project Name: <i>Colorado School of Mines</i>	Sample Location: <i>CSMRI-2</i>
Project Number: <i>4349-250</i>	Date: <i>9/7/10, 9/10/10</i>
Sample Type: <input checked="" type="radio"/> GW SW EB Duplicate Other:	Sampler: <i>N Malczyk</i>

Purge Volume Calculations		Sample Collection				
Measured TD =	<i>45.12</i> (ft) (+.28)	Analysis	Container	Preservative	Date	Time
Total Depth =	<i>95.40</i> (ft)	<i>PC-226 -228</i>	<i>1 gal</i>			
Depth to Water =	<i>52.62</i> (ft)	<i>Diss. U</i>	<i>cube</i>	<i>HNO₃</i>	<i>9/10/10</i>	<i>0850</i>
Initial Water Column =	<i>42.78</i> (ft)	<i>Cations</i>	<i>500mL</i>	<i>HNO₃</i>	<i>9/10/10</i>	<i>0850</i>
Initial Water Volume =	<i>6.84</i> (gal)	<i>Anions</i>	<i>Plastic</i>	<i>-</i>	<i>9/10/10</i>	<i>0850</i>
3 X Water Volume	<i>20.52</i> (gal)	<i>DOC</i>	<i>125mL</i>	<i>H₂SO₄</i>	<i>9/10/10</i>	<i>0850</i>
Lab: <i>ALS - Ft. Collins, Test America - Arvada</i>						

Purge Volumes and Field Water Quality Measurements								
Time	Volume (gal)	Temperature (C, F)	pH (SU)	Conductivity (uS/cm)	DO (mg/L)	ORP (mV)	Turbidity (NTU)	Appearance
<i>1412</i>	<i>3.42</i>	<i>14.84</i>	<i>7.02</i>	<i>809</i>	<i>2.09</i>	<i>117</i>	<i>414</i>	<i>brown</i>
<i>1420</i>	<i>6.84</i>	<i>14.65</i>	<i>7.37</i>	<i>730</i>	<i>9.30</i>	<i>122</i>	<i>1000+</i>	
<i>1430</i>	<i>10.26</i>	<i>15.32</i>	<i>7.05</i>	<i>726</i>	<i>3.04</i>	<i>130</i>	<i>1000+</i>	
<i>1440</i>	<i>13.68</i>	<i>14.66</i>	<i>7.01</i>	<i>809</i>	<i>3.28</i>	<i>135</i>	<i>1000L</i>	
	<i>17.10</i>							
	<i>20.52</i>							
<i>NEM</i>								
Volume purged: <i>14 gal</i>								

Comments:	Analysis	Container	Preservative	Date	Time
TA	<i>NO₂, NO₃</i>	<i>1L Plastic</i>	<i>none</i>	<i>9/10/10</i>	<i>0850</i>
TA	<i>TDS</i>	<i>1L Plastic</i>	<i>none</i>	<i>9/10/10</i>	<i>0850</i>
TA	<i>Ferrrous Fe</i>	<i>1L Plastic</i>	<i>none</i>	<i>9/10</i>	<i>NEM</i>
TA	<i>Ferric Fe</i>	<i>500mL Plastic</i>	<i>HNO₃</i>	<i>9/10</i>	<i>NEM</i>
TA	<i>Sulfide</i>	<i>250mL Plastic</i>	<i>Zn Ac</i>	<i>9/10</i>	<i>NEM</i>

SM Stoller Corp.

105 Technology Dr., Suite 190
Broomfield, CO 80021
(303) 546-4300

Project Name: <i>Colorado School of Mines</i>	Sample Location: <i>CSMRI-4</i>
Project Number: <i>4349-250</i>	Date: 9/8/10 ^{NEM} <i>9/10/10</i>
Sample Type: <input checked="" type="checkbox"/> <i>GW</i> <input type="checkbox"/> SW <input type="checkbox"/> EB Duplicate Other:	Sampler: <i>N Malczyk</i>

Purge Volume Calculations		Sample Collection				
Measured TD =	17.34 (ft) (+.28)	Analysis	Container	Preservative	Date	Time
Total Depth =	17.62 (ft)	Re-226 -228	1 gal			
Depth to Water =	RE 17.62 <i>6.96</i>	Dist. u	cube	HNO ₃	9/10/10	0930
Initial Water Column =	10.66 (ft)	Cations	500mL Plastic	HNO ₃	9/10/10	0930
Initial Water Volume =	1.71 (gal)	Anions	500mL Plastic	-	9/10/10	0930
3 X Water Volume	5.13 (gal)	DOC	125mL Amber	H ₂ SO ₄	9/10/10	0930
Lab: <i>ALS - Ft. Collins, Test America - Arvada</i>						

Purge Volumes and Field Water Quality Measurements								
Time	Volume (gal)	Temperature (°C, °F)	pH (SU)	Conductivity (uS/cm)	DO (mg/L)	ORP (mV)	Turbidity (NTU)	Appearance
0920	1.71	15.59	6.66	1570	3.59	135	336	black
0924	3.42	15.38	6.63	1520	3.53	164	314	↓
0928	5.13	15.29	6.63	1510	4.51	180	354	↓
								NEM
Volume purged: <i>5.13 gal</i>								

Comments:	Analysis	Container	Preservative	Date	Time
TA	NO ₂ , NO ₃	1L Plastic	none	9/10/10	0930
TA	TDS	1L Plastic	none	9/10/10	0930
TA	Ferrrous Fe	1L Plastic	none	9/10/10	0930
TA	Ferric Fe	500mL Plastic	HNO ₃	9/10/10	0930
TA	Sulfide	250mL Plastic	Zn Ac	9/10/10	0930

SM Stoller Corp.

105 Technology Dr., Suite 190
Broomfield, CO 80021
(303) 546-4300

Project Name: <i>Colorado School of Mines</i>	Sample Location: <i>CSMRI-S</i>
Project Number: <i>4349-250</i>	Date: 9/8/10 <i>9/10/10</i>
Sample Type: <input checked="" type="checkbox"/> SW <input type="checkbox"/> EB Duplicate Other:	Sampler: <i>N Malczyk</i>

Purge Volume Calculations		Sample Collection				
Measured TD =	<i>10.98</i> (ft) <i>(+28)</i>	Analysis	Container	Preservative	Date	Time
Total Depth =	<i>11.26</i> (ft)	<i>Re-226</i> <i>-228</i>	<i>1 gal</i>			
Depth to Water =	<i>5.63</i> (ft)	<i>Diss. U</i>	<i>cube</i>	<i>HNO3</i>	<i>9/10/10</i>	<i>1045</i>
Initial Water Column =	<i>5.63</i> (ft)	<i>Cations</i>	<i>500mL</i>	<i>HNO3</i>	<i>9/10/10</i>	<i>1045</i>
Initial Water Volume =	<i>0.90</i> (gal)	<i>Anions</i>	<i>Plastic</i>	<i>-</i>	<i>9/10/10</i>	<i>1045</i>
3 X Water Volume	<i>2.70</i> (gal)	<i>DOC</i>	<i>Amber</i>	<i>H2SO4</i>	<i>9/10/10</i>	<i>1045</i>
Lab: <i>ALS - Ft. Collins, Test America - Arvada</i>						

Purge Volumes and Field Water Quality Measurements								
Time	Volume (gal)	Temperature (C/F)	pH (SU)	Conductivity (uS/cm)	DO (mg/L)	ORP (mV)	Turbidity (NTU)	Appearance
<i>1035</i>	<i>0.90</i>	<i>13.27</i>	<i>7.28</i>	<i>1550</i>	<i>11.75</i>	<i>-152</i>	<i>114</i>	<i>black</i>
<i>1037</i>	<i>1.80</i>	<i>12.72</i>	<i>7.12</i>	<i>1530</i>	<i>11.19</i>	<i>-91</i>	<i>152</i>	<i>↓</i>
<i>1040</i>	<i>2.70</i>	<i>12.64</i>	<i>7.04</i>	<i>1490</i>	<i>5.96</i>	<i>-32</i>	<i>147</i>	<i>↓</i>
<i>MEM</i>								
Volume purged:		<i>3 gal</i>						

Comments:	Analysis	Container	Preservative	Date	Time
TA	<i>NO2, NO3</i>	<i>1L Plastic</i>	<i>none</i>	<i>9/10/10</i>	<i>1045</i>
TA	<i>TDS</i>	<i>1L Plastic</i>	<i>none</i>	<i>9/10/10</i>	<i>1045</i>
TA	<i>Ferrrous Fe</i>	<i>1L Plastic</i>	<i>none</i>	<i>9/10/10</i>	<i>1045</i>
TA	<i>Ferric Fe</i>	<i>500mL Plastic</i>	<i>HNO3</i>	<i>9/10/10</i>	<i>1045</i>
TA	<i>Sulfide</i>	<i>250mL Plastic</i>	<i>Zn Ac</i>	<i>9/10/10</i>	<i>1045</i>

SM Stoller Corp.

105 Technology Dr., Suite 190
 Broomfield, CO 80021
 (303) 546-4300

Project Name: <i>Colorado School of Mines</i>	Sample Location: <i>CSMRI-6C</i>
Project Number: <i>4349-250</i>	Date: <i>9/8/10</i>
Sample Type: <input checked="" type="checkbox"/> GWP SW EB Duplicate Other:	Sampler: <i>N Malczyk</i>

Purge Volume Calculations		Sample Collection				
Measured TD =	<i>29.94</i> (ft)	Analysis	Container	Preservative	Date	Time
	<i>(+28)</i>	<i>Ca-226</i>	<i>1 gal</i>			
Total Depth =	<i>30.22</i> (ft)	<i>-228</i>	<i>cube</i>	<i>HNO₃</i>	<i>9/8/10</i>	<i>1340</i>
Depth to Water =	<i>24.31</i> (ft)	<i>Diss. U</i>	<i>500mL</i>			
Initial Water Column =	<i>5.91</i> (ft)	<i>Cations</i>	<i>Plastic</i>	<i>HNO₃</i>	<i>9/8/10</i>	<i>1340</i>
Initial Water Volume =	<i>0.95</i> (gal)	<i>Anions</i>	<i>500mL</i>	<i>-</i>	<i>9/8/10</i>	<i>1340</i>
3 X Water Volume	<i>2.85</i> (gal)	<i>DOC</i>	<i>125mL</i>	<i>H₂SO₄</i>	<i>9/8/10</i>	<i>1340</i>
Lab: <i>ALS - Ft. Collins, Test America - Arvada</i>						

Purge Volumes and Field Water Quality Measurements								
Time	Volume (gal)	Temperature (°C °F)	pH (SU)	Conductivity (uS/cm)	DO (mg/L)	ORP (mV)	Turbidity (NTU)	Appearance
<i>1329</i>	<i>0.95</i>	<i>12.86</i>	<i>7.58</i>	<i>1530</i>	<i>11.07</i>	<i>146</i>	<i>1000+</i>	<i>brown</i>
<i>1332</i>	<i>0.19</i>	<i>11.96</i>	<i>7.43</i>	<i>1480</i>	<i>10.65</i>	<i>152</i>	<i>1000+</i>	<i>brown</i>
<i>1335</i>	<i>2.85</i>	<i>11.77</i>	<i>7.25</i>	<i>1450</i>	<i>10.71</i>	<i>161</i>	<i>1000+</i>	<i>brown</i>
<i>rem</i>								
Volume purged: <i>2.85 gal</i>								

Comments:	Analysis	Container	Preservative	Date	Time
<i>TA</i>	<i>NO₂, NO₃</i>	<i>1L Plastic</i>	<i>none</i>	<i>9/8/10</i>	<i>1340</i>
<i>TA</i>	<i>TDS</i>	<i>1L Plastic</i>	<i>none</i>	<i>9/8/10</i>	<i>1340</i>
<i>TA</i>	<i>Ferrrous Fe</i>	<i>1L Plastic</i>	<i>none</i>	<i>9/10</i>	<i>rem</i>
<i>TA</i>	<i>Ferric Fe</i>	<i>500mL Plastic</i>	<i>HNO₃</i>	<i>9/10</i>	<i>rem</i>
<i>TA</i>	<i>Sulfide</i>	<i>250mL Plastic</i>	<i>Zn Ac</i>	<i>9/10</i>	<i>rem</i>

SM Stoller Corp.

105 Technology Dr., Suite 190

Broomfield, CO 80021

(303) 546-4300

Project Name: <i>Colorado School of Mines</i>			Sample Location: <i>CSMRI-7B</i>		
Project Number: <i>4349-250</i>			Date: <i>9/8/10, 9/10/10</i>		
Sample Type: <u>BW</u> Duplicate		SW	EB		Sampler: <i>N Malczyk</i>

Purge Volume Calculations			Sample Collection				
Measured TD =	<i>16.80</i> (ft)		Analysis	Container	Preservative	Date	Time
	<i>(+28)</i>		<i>Ca 226 -228</i>	<i>1 gal</i>			
Total Depth =	<i>17.08</i> (ft)		<i>Disse. U</i>	<i>cube</i>	<i>HNO₃</i>	<i>9/10/10</i>	<i>1115</i>
Depth to Water =	<i>15.78</i> (ft)		<i>Cations</i>	<i>Plastic</i>	<i>HNO₃</i>	<i>9/10</i>	<i>rem</i>
Initial Water Column =	<i>1.30</i> (ft)		<i>Anions</i>	<i>Plastic</i>	<i>---</i>	<i>9/10</i>	<i>rem</i>
Initial Water Volume =	<i>0.218</i> (gal)	<i>0.21</i>	<i>DOC</i>	<i>Amber</i>	<i>H₂SO₄</i>	<i>9/10</i>	<i>rem</i>
3 X Water Volume	<i>0.63</i> (gal)		Lab: <i>ALS - Ft. Collins, Test America - Arvada</i>				

Purge Volumes and Field Water Quality Measurements								
Time	Volume (gal)	Temperature (°C/°F)	pH (SU)	Conductivity (uS/cm)	DO (mg/L)	ORP (mV)	Turbidity (NTU)	Appearance
<i>0929</i>	<i>0.21</i>	<i>17.35</i>	<i>6.91</i>	<i>920</i>	<i>4.65</i>	<i>116</i>	<i>10.5</i>	<i>clear</i>
<i>0935</i>	<i>0.42</i>	<i>17.28</i>	<i>6.81</i>	<i>900</i>	<i>6.06</i>	<i>120</i>	<i>9.5</i>	<i>clear</i>
	<i>0.63</i>							<i>rem</i>
Volume purged: <i>0.75 gal</i>								

Comments:	Analysis	Container	Preservative	Date	Time
TA	<i>NO₂/NO₃</i>	<i>1L Plastic</i>	<i>none</i>	<i>9/10</i>	<i>rem</i>
TA	<i>TDS</i>	<i>1L Plastic</i>	<i>none</i>	<i>9/10</i>	<i>rem</i>
TA	<i>Ferrous Fe</i>	<i>1L Plastic</i>	<i>none</i>	<i>9/10</i>	<i>rem</i>
TA	<i>Ferrous Fe</i>	<i>500ml Plastic</i>	<i>HNO₃</i>	<i>9/10</i>	<i>rem</i>
TA	<i>Sulfide</i>	<i>250ml Plastic</i>	<i>Zn Ac</i>	<i>9/10</i>	<i>rem</i>

SM Stoller Corp.

105 Technology Dr., Suite 190
Broomfield, CO 80021
(303) 546-4300

Project Name: <i>Colorado School of Mines</i>	Sample Location: <i>CSMRI-8</i>
Project Number: <i>4349-250</i>	Date: <i>9/8/10</i>
Sample Type: <input checked="" type="checkbox"/> Duplicate <input type="checkbox"/> SW <input type="checkbox"/> EB <input type="checkbox"/> Other:	Sampler: <i>N Malczyk</i>

Purge Volume Calculations		Sample Collection				
Measured TD =	<i>17.04</i> (ft)	Analysis	Container	Preservative	Date	Time
	<i>(+28)</i>	<i>Re-226</i>	<i>1 gal</i>			
Total Depth =	<i>17.32</i> (ft)	<i>-228</i>	<i>cube</i>	<i>HNO₃</i>	<i>9/8/10</i>	<i>1105</i>
Depth to Water =	<i>7.97</i> (ft)	<i>Diss. U</i>	<i>500mL</i>			
Initial Water Column =	<i>9.35</i> (ft)	<i>Cations</i>	<i>Plastic</i>	<i>HNO₃</i>	<i>9/8/10</i>	<i>1105</i>
Initial Water Volume =	<i>1.50</i> (gal)	<i>Anions</i>	<i>500mL</i>		<i>9/8/10</i>	<i>1105</i>
3 X Water Volume	<i>4.50</i> (gal)	<i>DOC</i>	<i>125mL</i>		<i>9/8/10</i>	<i>1105</i>
		Lab: <i>ALS - Ft. Collins, Test America - Arvada</i>				

Purge Volumes and Field Water Quality Measurements								
Time	Volume (gal)	Temperature (°C, °F)	pH (SU)	Conductivity (uS/cm)	DO (mg/L)	ORP (mV)	Turbidity (NTU)	Appearance
<i>1054</i>	<i>1.50</i>	<i>15.87</i>	<i>7.25</i>	<i>2170</i>	<i>8.12</i>	<i>166</i>	<i>1000+</i>	<i>brown</i>
<i>1058</i>	<i>3.00</i>	<i>15.76</i>	<i>7.25</i>	<i>2140</i>	<i>5.06</i>	<i>172</i>	<i>1000+</i>	<i>brown</i>
<i>1101</i>	<i>4.50</i>	<i>16.15</i>	<i>7.25</i>	<i>2160</i>	<i>7.55</i>	<i>177</i>	<i>1000+</i>	<i>brown</i>
<i>rem</i>								
Volume purged:		<i>4.50 gal</i>						

Comments:	Analysis	Container	Preservative	Date	Time
<i>TA</i>	<i>NO₂, NO₃</i>	<i>1L Plastic</i>	<i>none</i>	<i>9/8/10</i>	<i>1105</i>
<i>TA</i>	<i>TDS</i>	<i>1L Plastic</i>	<i>none</i>	<i>9/8/10</i>	<i>1105</i>
<i>TA</i>	<i>Ferrrous Fe</i>	<i>1L Plastic</i>	<i>none</i>	<i>9/8/10</i>	<i>1105</i>
<i>TA</i>	<i>Ferric Fe</i>	<i>500mL Plastic</i>	<i>HNO₃</i>	<i>9/8/10</i>	<i>1105</i>
<i>TA</i>	<i>Sulfide</i>	<i>250mL Plastic</i>	<i>Zn Ac</i>	<i>9/8/10</i>	<i>1105</i>

SM Stoller Corp.

105 Technology Dr., Suite 190
Broomfield, CO 80021
(303) 546-4300

Project Name: <i>Colorado School of Mines</i>	Sample Location: <i>CSMRI-9</i>
Project Number: <i>4349-250</i>	Date: <i>9/8/10</i>
Sample Type: <input checked="" type="checkbox"/> GW Duplicate <input type="checkbox"/> SW <input type="checkbox"/> EB <input type="checkbox"/> Other:	Sampler: <i>N Malczyk</i>

Purge Volume Calculations		Sample Collection				
Measured TD =	33.11 (ft) (+.28)	Analysis	Container	Preservative	Date	Time
Total Depth =	33.39 (ft)	<i>Re-226 -228 Diss. U</i>	<i>1 gal cube</i>	<i>HNO₃</i>	<i>9/8/10</i>	<i>1010</i>
Depth to Water =	20.76 (ft)	<i>Cations</i>	<i>500mL Plastic</i>	<i>HNO₃</i>	<i>9/8/10</i>	<i>1010</i>
Initial Water Column =	12.63 (ft)	<i>Anions</i>	<i>500mL Plastic</i>	<i>-</i>	<i>9/8/10</i>	<i>1010</i>
Initial Water Volume =	2.02 (gal)	<i>DOC</i>	<i>125mL Amber</i>	<i>H₂SO₄</i>	<i>9/8/10</i>	<i>1010</i>
3 X Water Volume	6.06 (gal)	Lab: <i>ALS - Ft. Collins, Test America - Arvada</i>				

Purge Volumes and Field Water Quality Measurements								
Time	Volume (gal)	Temperature (°C/°F)	pH (SU)	Conductivity (uS/cm)	DO (mg/L)	ORP (mV)	Turbidity (NTU)	Appearance
1000	2.02	12.94	6.94	1510	9.15	180	1000+	Brown
1003	4.04	13.06	6.88	1470	8.37	184	1000+	Brown
1006	6.06	12.53	6.81	1410	8.60	189	1000+	↓
<i>seen</i>								
Volume purged: <i>6.06 gal</i>								

Comments:	Analysis	Container	Preservative	Date	Time
TA	<i>NO₂, NO₃</i>	<i>1L Plastic</i>	<i>none</i>	<i>9/8/10</i>	<i>1010</i>
TA	<i>TDS</i>	<i>1L Plastic</i>	<i>none</i>	<i>9/8/10</i>	<i>1010</i>
TA	<i>Ferric Fe</i>	<i>1L Plastic</i>	<i>none</i>	<i>9/10</i>	<i>1010</i>
TA	<i>Ferric Fe</i>	<i>500mL Plastic</i>	<i>HNO₃</i>	<i>9/10</i>	<i>1010</i>
TA	<i>Sulfide</i>	<i>250mL Plastic</i>	<i>Zn Ac</i>	<i>9/10</i>	<i>1010</i>

SM Stoller Corp.

105 Technology Dr., Suite 190
Broomfield, CO 80021
(303) 546-4300

Project Name: <i>Colorado School of Mines</i>	Sample Location: <i>ESMRI-10</i>
Project Number: <i>4349-250</i>	Date: <i>9/8/10</i>
Sample Type: <input checked="" type="radio"/> GW <input type="radio"/> SW <input type="radio"/> EB Duplicate Other:	Sampler: <i>N Malczyk</i>

Purge Volume Calculations		Sample Collection				
Measured TD =	27.86 (ft) (+.28)	Analysis	Container	Preservative	Date	Time
Total Depth =	28.14 (ft)	<i>Re-226 -228</i>	<i>1 gal cube</i>	<i>HNO₃</i>	<i>9/8/10</i>	<i>1040</i>
Depth to Water =	21.89 (ft)	<i>Disc. U</i>	<i>500ml Plastic</i>	<i>HNO₃</i>	<i>9/8/10</i>	<i>1040</i>
Initial Water Column =	6.25 (ft)	<i>Cations</i>	<i>500ml Plastic</i>	<i>HNO₃</i>	<i>9/8/10</i>	<i>1040</i>
Initial Water Volume =	1.00 (gal)	<i>Anions</i>	<i>125ml Plastic</i>	<i>-</i>	<i>9/8/10</i>	<i>1040</i>
3 X Water Volume	3.00 (gal)	<i>DOC</i>	<i>Amber</i>	<i>H₂SO₄</i>	<i>9/8/10</i>	<i>1040</i>
Lab: <i>ALS - Ft. Collins, Test America - Arvada</i>						

Purge Volumes and Field Water Quality Measurements								
Time	Volume (gal)	Temperature (°C/°F)	pH (SU)	Conductivity (uS/cm)	DO (mg/L)	ORP (mV)	Turbidity (NTU)	Appearance
1028	1.00	13.47	7.18	1350	6.41	164	514	Grey
1031	2.00	12.92	7.15	1340	6.33	166	577	Grey
1034	3.00	12.73	7.10	1340	8.04	168	573	Grey
<i>102m</i>								
Volume purged: <i>3.0 gal</i>								

Comments:	Analysis	Container	Preservative	Date	Time
TA	<i>NO₂, NO₃</i>	<i>1L Plastic</i>	<i>none</i>	<i>9/8/10</i>	<i>1040</i>
TA	<i>TDS</i>	<i>1L Plastic</i>	<i>none</i>	<i>9/8/10</i>	<i>1040</i>
TA	<i>Ferrous Fe</i>	<i>1L Plastic</i>	<i>none</i>	<i>9/10</i>	<i>non</i>
TA	<i>Ferrous Fe</i>	<i>500ml Plastic</i>	<i>HNO₃</i>	<i>9/10</i>	<i>non</i>
TA	<i>Sulfide</i>	<i>250ml Plastic</i>	<i>Zn Ac</i>	<i>9/10</i>	<i>non</i>

SM Stoller Corp.

105 Technology Dr., Suite 190
Broomfield, CO 80021
(303) 546-4300

Project Name: <i>Colorado School of Mines</i>	Sample Location: <i>CSMRI-11B</i>
Project Number: <i>4349-250</i>	Date: <i>9/8/10</i>
Sample Type: <i>SW</i> SW EB Duplicate Other:	Sampler: <i>N Malczyk</i>

Purge Volume Calculations		Sample Collection				
Measured TD =	28.55 (ft) (+.28)	Analysis	Container	Preservative	Date	Time
Total Depth =	28.87 (ft)	<i>Re-226 -228</i>	<i>1 gal</i>			
Depth to Water =	24.27 (ft)	<i>Diss. U</i>	<i>cube</i>	<i>HNO₃</i>	<i>9/8/10</i>	<i>1435</i>
Initial Water Column =	4.60 (ft)	<i>Cations</i>	<i>Plastic</i>	<i>HNO₃</i>	<i>9/8/10</i>	<i>1435</i>
Initial Water Volume =	0.74 (gal)	<i>Anions</i>	<i>Plastic</i>	<i>-</i>	<i>9/8/10</i>	<i>1435</i>
3 X Water Volume	2.22 (gal)	<i>DOC</i>	<i>Amber</i>	<i>H₂SO₄</i>	<i>9/8/10</i>	<i>1435</i>
Lab: <i>ALS - Ft. Collins, Test America - Arvada</i>						

Purge Volumes and Field Water Quality Measurements								
Time	Volume (gal)	Temperature (°C) (°F)	pH (SU)	Conductivity (uS/cm)	DO (mg/L)	ORP (mV)	Turbidity (NTU)	Appearance
<i>1423</i>	<i>0.74</i>	<i>13.70</i>	<i>7.11</i>	<i>1630</i>	<i>10.10</i>	<i>165</i>	<i>1000+</i>	<i>grey</i>
<i>1426</i>	<i>1.48</i>	<i>12.69</i>	<i>6.97</i>	<i>1680</i>	<i>8.97</i>	<i>169</i>	<i>1000+</i>	<i>grey</i>
<i>1429</i>	<i>2.22</i>	<i>12.86</i>	<i>6.86</i>	<i>1690</i>	<i>8.66</i>	<i>174</i>	<i>1000+</i>	<i>grey</i>
<i>REM</i>								
Volume purged: <i>2.22 gal</i>								

Comments:	Analysis	Container	Preservative	Date	Time
<i>TA</i>	<i>NO₂, NO₃</i>	<i>1L Plastic</i>	<i>none</i>	<i>9/9/10</i>	<i>1435</i>
<i>TA</i>	<i>TDS</i>	<i>1L Plastic</i>	<i>none</i>	<i>9/8/10</i>	<i>1435</i>
<i>TA</i>	<i>Ferrous Fe</i>	<i>1L Plastic</i>	<i>none</i>	<i>9/ /10</i>	<i>rem</i>
<i>TA</i>	<i>Ferrous Fe</i>	<i>500ml Plastic</i>	<i>HNO₃</i>	<i>9/ /10</i>	<i>rem</i>
<i>TA</i>	<i>Sulfide</i>	<i>250ml Plastic</i>	<i>Zn Ac</i>	<i>9/ /10</i>	<i>rem</i>

SM Stoller Corp.

105 Technology Dr., Suite 190
Broomfield, CO 80021
(303) 546-4300

Project Name: <i>Colorado School of Mines</i>		Sample Location: <i>SW-1</i>	
Project Number: <i>4349-250</i>		Date: <i>9/9/10</i>	
Sample Type: GW <input type="checkbox"/> Duplicate	<input checked="" type="radio"/> <i>SW</i> Other: <input type="checkbox"/>	EB	Sampler: <i>N Malczyk</i>

Purge Volume Calculations		Sample Collection				
Measured TD =	(ft)	Analysis	Container	Preservative	Date	Time
	(+ .28)	<i>Re-226</i>	<i>1 gal</i>			
Total Depth =	(ft)	<i>Disc. u</i>	<i>cube</i>	<i>HNO3</i>	<i>9/9/10</i>	<i>1125</i>
Depth to Water =	(ft)	<i>Cations</i>	<i>500ml Plastic</i>	<i>HNO3</i>	<i>9/9/10</i>	<i>1125</i>
Initial Water Column =	(ft)	<i>Anions</i>	<i>500ml Plastic</i>	<i>-</i>	<i>9/9/10</i>	<i>1125</i>
Initial Water Volume =	(gal)	<i>DOC</i>	<i>125ml Amber</i>	<i>H2SO4</i>	<i>9/9/10</i>	<i>1125</i>
3 X Water Volume	(gal)	Lab: <i>ALS - Ft. Collins, Test America - Arvada</i>				

Purge Volumes and Field Water Quality Measurements								
Time	Volume (gal)	Temperature (°C/°F)	pH (SU)	Conductivity (uS/cm)	DO (mg/L)	ORP (mV)	Turbidity (NTU)	Appearance
<i>1123</i>	<i>N/A</i>	<i>13.54</i>	<i>7.33</i>	<i>340</i>	<i>11.93</i>	<i>142</i>	<i>7.3</i>	<i>clear</i>
<i>N/A</i>								

Volume purged: *N/A*

Comments:	Analysis	Container	Preservative	Date	Time
<i>TA</i>	<i>NO2, NO3</i>	<i>1L Plastic</i>	<i>none</i>	<i>9/9/10</i>	<i>1125</i>
<i>TA</i>	<i>TDS</i>	<i>1L Plastic</i>	<i>none</i>	<i>9/9/10</i>	<i>1125</i>
<i>TA</i>	<i>Ferrous Fe</i>	<i>1L Plastic</i>	<i>none</i>	<i>9/10</i>	<i>nm</i>
<i>TA</i>	<i>Ferric Fe</i>	<i>500ml Plastic</i>	<i>HNO3</i>	<i>9/10</i>	<i>nm</i>
<i>TA</i>	<i>Sulfide</i>	<i>250ml Plastic</i>	<i>Zn Ac</i>	<i>9/10</i>	<i>nm</i>

SM Stoller Corp.

105 Technology Dr., Suite 190
Broomfield, CO 80021
(303) 546-4300

Project Name: <i>Colorado School of Mines</i>	Sample Location: <i>SW-2</i>
Project Number: <i>4349-250</i>	Date: <i>9/9/10</i>
Sample Type: GW <u>SW</u> EB Duplicate Other:	Sampler: <i>N Malczyk</i>

Purge Volume Calculations		Sample Collection				
Measured TD =	(ft)	Analysis	Container	Preservative	Date	Time
	(+28)	<i>Ca-226-228</i>	<i>1 gal</i>			
Total Depth =	(ft)	Dist. U	<i>cube</i>	<i>HNO₃</i>	<i>9/9/10</i>	<i>1345</i>
Depth to Water =	(ft)	<i>Cations</i>	<i>500mL</i>	<i>HNO₃</i>	<i>9/9/10</i>	<i>1345</i>
Initial Water Column =	(ft)	<i>Anions</i>	<i>500mL</i>	<i>-</i>	<i>9/9/10</i>	<i>1345</i>
Initial Water Volume =	(gal)		<i>125mL</i>			
3 X Water Volume	(gal)	<i>DOC</i>	<i>Amber</i>	<i>H₂SO₄</i>	<i>9/9/10</i>	<i>1345</i>
		Lab: <i>ALS - Ft. Collins, Test America - Arvada</i>				

Purge Volumes and Field Water Quality Measurements								
Time	Volume (gal)	Temperature (°C, °F)	pH (SU)	Conductivity (uS/cm)	DO (mg/L)	ORP (mV)	Turbidity (NTU)	Appearance
<i>1341</i>	<i>n/A</i>	<i>15.60</i>	<i>7.94</i>	<i>340</i>	<i>12.44</i>	<i>145</i>	<i>34.8</i>	<i>clear</i>
								<i>n/m</i>

Volume purged: *n/A*

Comments:	Analysis	Container	Preservative	Date	Time
<i>TA</i>	<i>NO₂, NO₃</i>	<i>1L Plastic</i>	<i>none</i>	<i>9/9/10</i>	<i>1345</i>
<i>TA</i>	<i>TDS</i>	<i>1L Plastic</i>	<i>none</i>	<i>9/9/10</i>	<i>1345</i>
<i>TA</i>	<i>Ferrous Fe</i>	<i>1L Plastic</i>	<i>none</i>	<i>9/10</i>	<i>n/m</i>
<i>TA</i>	<i>Ferric Fe</i>	<i>500mL Plastic</i>	<i>HNO₃</i>	<i>9/10</i>	<i>n/m</i>
<i>TA</i>	<i>Sulfate</i>	<i>250mL Plastic</i>	<i>Zn Ac</i>	<i>9/10</i>	<i>n/m</i>

SM Stoller Corp.

105 Technology Dr., Suite 190
Broomfield, CO 80021
(303) 546-4300

Project Name: <i>Colorado School of Mines</i>	Sample Location: <i>SW-3</i>
Project Number: <i>4349-250</i>	Date: <i>9/9/10</i>
Sample Type: GW Duplicate <input checked="" type="radio"/> <i>SW</i> Other: EB	Sampler: <i>N Malczyk</i>

Purge Volume Calculations		Sample Collection				
Measured TD =	(ft)	Analysis	Container	Preservative	Date	Time
	(+28)	<i>Re-226 -228</i>	<i>1 gal</i>			
Total Depth =	(ft)	<i>Dis. U</i>	<i>cube</i>	<i>HNO₃</i>	<i>9/9/10</i>	<i>1315</i>
Depth to Water =	(ft)	<i>Cations</i>	<i>500mL</i>	<i>HNO₃</i>	<i>9/9/10</i>	<i>1315</i>
Initial Water Column =	(ft)	<i>Anions</i>	<i>500mL</i>	<i>-</i>	<i>9/9/10</i>	<i>1315</i>
Initial Water Volume =	(gal)	<i>DOC</i>	<i>125mL</i>	<i>H₂SO₄</i>	<i>9/9/10</i>	<i>1315</i>
3 X Water Volume	(gal)	Lab: <i>ALS - Ft. Collins, Test America - Arvada</i>				

Purge Volumes and Field Water Quality Measurements								
Time	Volume (gal)	Temperature (C/F)	pH (SU)	Conductivity (uS/cm)	DO (mg/L)	ORP (mV)	Turbidity (NTU)	Appearance
<i>1309</i>	<i>N/A</i>	<i>15.05</i>	<i>7.92</i>	<i>340</i>	<i>12.31</i>	<i>149</i>	<i>0.0</i>	<i>clear</i>
<i>N/A</i>								

Volume purged: *N/A*

Comments:	Analysis	Container	Preservative	Date	Time
<i>TA</i>	<i>NO₂, NO₃</i>	<i>1L Plastic</i>	<i>none</i>	<i>9/9/10</i>	<i>1315</i>
<i>TA</i>	<i>TDS</i>	<i>1L Plastic</i>	<i>none</i>	<i>9/9/10</i>	<i>1315</i>
<i>TA</i>	<i>Ferrrous Fe</i>	<i>1L Plastic</i>	<i>none</i>	<i>9/10</i>	<i>N/A</i>
<i>TA</i>	<i>Ferric Fe</i>	<i>500mL Plastic</i>	<i>HNO₃</i>	<i>9/10</i>	<i>N/A</i>
<i>TA</i>	<i>Sulfide</i>	<i>250mL Plastic</i>	<i>Zn Ac</i>	<i>9/10</i>	<i>N/A</i>

SM Stoller Corp.

105 Technology Dr., Suite 190
 Broomfield, CO 80021
 (303) 546-4300

Project Name: <i>Colorado School of Mines</i>		Sample Location: <i>Equipment Block</i>	
Project Number: <i>4349-250</i>		Date: <i>9/10/10</i>	
Sample Type:	GW Duplicate	SW Other:	<input checked="" type="radio"/> EB <i>N Malczyk</i>

Purge Volume Calculations		Sample Collection				
Measured TD =	(ft)	Analysis	Container	Preservative	Date	Time
	(+28)	<i>Re-226 -228</i>	<i>1 gal cube</i>	<i>HNO₃</i>	<i>9/10/10</i>	<i>0700</i>
Total Depth =	(ft)	<i>Disc. U</i>	<i>500ml</i>	<i>HNO₃</i>	<i>9/10/10</i>	<i>0700</i>
Depth to Water =	(ft)	<i>Cations</i>	<i>Plastic</i>	<i>HNO₃</i>	<i>9/10/10</i>	<i>0700</i>
Initial Water Column =	(ft)	<i>Anions</i>	<i>Plastic</i>	<i>-</i>	<i>9/10/10</i>	<i>0700</i>
Initial Water Volume =	(gal)	<i>DOC</i>	<i>Amber</i>	<i>H₂SO₄</i>	<i>9/10/10</i>	<i>0700</i>
3 X Water Volume	(gal)	<i>Lab: ALS - Ft. Collins, Test America - Arvada</i>				

Purge Volumes and Field Water Quality Measurements								
Time	Volume (gal)	Temperature (°C, °F)	pH (SU)	Conductivity (uS/cm)	DO (mg/L)	ORP (mV)	Turbidity (NTU)	Appearance
<i>N/A</i>								
Volume purged: <i>N/A</i>								

Comments:	Analysis	Container	Preservative	Date	Time
TA	<i>NO₂, NO₃</i>	<i>1L Plastic</i>	<i>none</i>	<i>9/10/10</i>	<i>0700</i>
TA	<i>TDS</i>	<i>1L Plastic</i>	<i>none</i>	<i>9/10/10</i>	<i>0700</i>
TA	<i>Ferrous Fe</i>	<i>1L Plastic</i>	<i>none</i>	<i>9/10/10</i>	<i>nen</i>
TA	<i>Ferric Fe</i>	<i>500ml Plastic</i>	<i>HNO₃</i>	<i>9/10/10</i>	<i>nen</i>
TA	<i>Sulfide</i>	<i>250ml Plastic</i>	<i>Zn Ac</i>	<i>9/10/10</i>	<i>nen</i>

Appendix C

Surface Water Sampling Procedures

Surface Water Sampling

1.0 Scope and Objective

1.1 Scope

This procedure provides instructions and establishes requirements for the collection and documentation of surface water samples by Stoller personnel. This procedure applies to the collection of surface water samples from streams, rivers, ponds, lakes, seeps, impoundments, and other surface sources.

1.2 Objective

The objective of this procedure is to establish a uniform method for the collection of surface water samples that provides representative samples in a safe and responsible manner.

2.0 Definitions

Composite Sample – A sample that is comprised of roughly equal amounts of water collected from a set of sample locations known as a sample group.

Grab Sample – A single sample collected at one sampling point over a short period of time. Grab sample results are representative of the sample location at the time of sample collection. Also called a catch sample.

Peristaltic Pump – A self-priming, low volume pump consisting of a rotor and ball bearing rollers. Tubing placed around the rotors is squeezed by the rotors as they revolve. The squeezing produces a wavelike contractual movement which causes water to be drawn through the tubing. The peristaltic pump is limited to sampling at depths of less than 25 feet.

3.0 Responsibilities and Qualifications

3.1 Project Manager

The Project Manager is responsible for ensuring that surface water samples are properly and safely collected. This will be accomplished through staff training and by maintaining quality control (QC). At a minimum, project management shall:

- 3.1.1 Verify that personnel have reviewed, and are familiar with, site-specific work plans which address surface water sampling, this procedure, and any associated procedures.
- 3.1.2 Ensure that hazards are identified and analyzed with respect to collecting surface water samples, and develop and implement controls to minimize hazards.
- 3.1.3 Provide personnel with training in the operation of surface water sampling equipment and the requirements of this procedure.
- 3.1.4 Periodically review field generated documentation associated with surface water sampling to ensure compliance with project requirements and implement corrective action if necessary.
- 3.1.5 Receive feedback from field sampling personnel in order to continually improve surface water sampling process.

3.2 Site Supervisor

The Site Supervisor is responsible for directing and overseeing all field activities, including sampling, to ensure that site-specific plan requirements are met in a safe and efficient manner within the established safety envelope.

3.3 Field Sampling Personnel

Field sampling personnel are responsible for the proper sample collection and documentation of the sampling event in accordance with this procedure. At a minimum, field sampling personnel have the responsibility to:

- 3.3.1 Familiarize themselves with site-specific work plans, surface water sampling procedures, potential hazards, and health and safety plan.
- 3.3.2 Implement the controls to minimize hazards.
- 3.3.3 Be familiar with sampling equipment and its proper use.
- 3.3.4 Properly complete field documentation.
- 3.3.5 Provide feedback to project manager in order to improve sampling process.

4.0 Equipment/Materials and Calibration

4.1 Equipment/Materials

A number of devices are available for the collection of surface water samples. These devices are constructed of a number of materials including, but not limited to: stainless steel, glass, Teflon®, Tygon®. The sampling and analytical requirements, as well as site characteristics, must be taken into account when determining the proper surface water sampling equipment to use. The site-specific work plans should identify the specific equipment to be used, and methods for safely using equipment.

4.2 Calibration

Equipment shall be calibrated in accordance with manufacturer's recommendations and calibration documentation shall be maintained in project files.

5.0 Method

5.1 Field Preparation

Field preparation requires the organization of sample containers, sample labels, and documentation in an orderly, systematic manner to promote consistency and traceability of all data.

- 5.1.1 General sampling areas will be predetermined to ensure coverage of the various impact scenarios and should be described in project-specific work plans. The location of each sampling point shall be surveyed or mapped and staked as described in Section 5.1.6 prior to sampling.
- 5.1.2 In flowing water, surface water sampling shall be conducted from downstream locations first, then proceed to upstream locations to avoid potential cross contamination from disturbing the substrate.
- 5.1.3 Prior to sampling and between sampling locations, sampling equipment shall be decontaminated.
- 5.1.4 Appropriate personal protective equipment shall be used, as specified in the project-specific health and safety plan.
- 5.1.5 All pertinent information (date, site name, identification number, and location) shall be recorded on a Field Activity Daily Log (FADL) and a Sample Collection Log, as appropriate. Field conditions, unusual circumstances, and weather conditions shall be noted.

- 5.1.6 Due to the nature of sampling an aqueous environment, additional steps are required to verify and mark sample locations. Depending on the project needs, it may be useful to use a Global Positioning System (GPS) to verify and mark the sample locations. Refer to *Field Mapping with a Global Positioning System* for details. The following steps shall be followed by the sampler in addition to the field preparation requirements described in Section 5.1.1.
- 5.1.6.1 Place a marker (stake) on the shore approximately perpendicular to the sampling location and mark the sample number on the stake.
 - 5.1.6.2 If the sample location is accessible by foot, use a measuring tape to measure the distance between the marked point and the sample location station. Record the compass bearing from the sample location to the shore marker.
 - 5.1.6.3 If the sample location is accessible only by boat, use a rangefinder to estimate the distance to the shore marker to obtain the most accurate measurement. Record the compass bearing from the sample location to the shore marker. It is recommended that the boat's position on the water be stabilized to prevent drifting.
 - 5.1.6.4 Determine and record the distance and direction of each shore marker from a reference point shown on the topographic map and mark all points on a map or use a GPS, if available.
- 5.1.7 Quality Control samples, including field and source blanks, shall be collected in accordance with the project-specific work plan.

5.2 Surface Water Sample Collection Using a Transfer Container

The device most commonly used to collect grab surface water samples is a transfer container (beaker, flask, etc.) made of inert material such as glass, stainless steel or Teflon®. When sampling with a transfer container, the procedure is as follows:

- 5.2.1 Survey and clearly map sampling points as described in Section 5.1.6 prior to sampling. The sample should be collected as close to the mapped location as possible. If the collection point must be moved, the new location must be approved and documented.
- 5.2.2 Dip the transfer container into the surface water. Always use a clean, properly decontaminated transfer container at each sample location.
- 5.2.3 Filter the sample if required.
- 5.2.4 Fill the sample bottle, allowing the sample stream to flow gently down the inside of the bottle with minimal turbulence.
- 5.2.5 Cap the bottle and handle the sample according to the procedures outlined in Project *Sample Shipping*.
- 5.2.6 Label the sample and document the sampling event.

5.3 Surface Water Sample Collection Using a Peristaltic Pump

A device used to collect composite surface water samples is a peristaltic pump. Samples to be analyzed for volatile organic analysis cannot be composited. When sampling with a peristaltic pump, the procedure is as follows:

- 5.3.1 Survey and clearly map sampling points as described in Section 5.1.6 prior to sampling. The sample should be collected as close to the mapped location as possible. If a collection point must be moved, the new location must be approved and documented.

- 5.3.2 Attach the appropriate tubing to the peristaltic pump. Always use new tubing at each sample location. Do not try to decontaminate and reuse tubing.
- 5.3.3 If filtering is required, attach the filtering device to the discharge end of the tubing.
- 5.3.4 Lower the intake end of the tubing into the water and begin pumping. If the pump is computerized, program the pump to collect the sample at the desired intervals and flow rate. If the pump is not programmable, record the discharge rate (compute discharge rate by dividing an amount of water collected by the time it took to collect it). Collect the sample at the desired interval.
- 5.3.5 Fill the sample bottle, allowing the sample stream to flow gently down the inside of the bottle with minimal turbulence. The programmable pump will perform this automatically.
- 5.3.6 Cap the bottle and handle the sample according to the procedures outlined in Project *Sample and Shipping*.
- 5.3.7 Label the sample and document the sampling event.

6.0 Required Inspection/Acceptance Criteria

None.

7.0 Records

The following records generated as a result of implementation of this procedure shall be maintained in a safe manner and submitted to project central files for storage and disposition.

Field Activity Daily Log

Sample Collection Log

Chain of Custody

8.0 References

8.1 Others

U.S. Environmental Protection Agency. 1987. *EPA Compendium of Superfund Field Operations Methods*, EPA 540/P-87/001a, OSWER 9355.0-14. Washington, DC.

U.S. Environmental Protection Agency. 1988. *EPA Guidance for Conducting Remedial Investigation and Feasibility Studies under CERCLA*, Interim Final OSWER Directive 9355.3-01. Washington, DC.

American Public Health Association, American Water Works Association, Water Pollution Control Federation. 1985. *Standard Methods for the Examination of Water and Wastewater*, 16th Edition, American Public Health Association, Washington, DC.

Appendix D

Data Validation Reports

DATA VALIDATION REPORT

To: Robert Hill
 From: John Garrett
 Date: November 07, 2010
 Project/Site: Colorado School of Mines
 Project No.: 4349-250
 SDG No.: 1009201

This report presents the inorganic anions data validation for the data obtained for fourteen CSMRI water sample collected on September 08, 2010, September 09, 2010, and September 10, 2010 and submitted to ALS Laboratory Group on September 13, 2010 for the above referenced work assignment. The purpose of this review is to provide a technical evaluation of the inorganic anions results that were obtained by preparation method MCAWW, May 1994, and EMSL Rev 2.1 Alkalinity, Bicarbonate, and Carbonate by Method 310.1 ALS SOP 1106R8, Sulfate, and Chloride by Method 300.0 Rev 2.1 ALS SOP 1113R11 from ALS Laboratory Group. (Fort Collins, CO). The water samples were analyzed for Bicarbonate, Carbonate, and Total Alkalinity, on September 22, 2010, Sulfate and Chloride on September 20, 2010. All analyses were conducted by ALS Laboratory Group. The field sample numbers and corresponding laboratory numbers are presented below:

Client Sample Number	Laboratory Sample Number	Matrix	Collection Date
CSMRI-1B	1009201-1	Water	September 08, 2010
CSMRI-9	1009201-2	Water	September 08, 2010
CSMRI-10	1009201-3	Water	September 08, 2010
CSMRI-8	1009201-4	Water	September 08, 2010
CSMRI-6C	1009201-5	Water	September 08, 2010
CSMRI-11B	1009201-6	Water	September 08, 2010
SW-1	1009201-7	Water	September 09, 2010
CSMRI-1	1009201-8	Water	September 09, 2010
SW-2	1009201-9	Water	September 09, 2010
SW-3	1009201-10	Water	September 09, 2010
EQUIPMENT BLANK	1009201-11	Water	September 10, 2010
CSMRI-2	1009201-12	Water	September 10, 2010
CSMRI-4	1009201-13	Water	September 10, 2010
CSMRI-5	1009201-14	Water	September 10, 2010

Data validation was conducted in accordance with the USEPA Contract Laboratory Program National Functional Guidelines for Inorganic Data Review.

The Inorganic data were evaluated based on the following parameters:

- * Data Completeness
- * Holding Times and Preservation
- * Initial and Continuing Calibration Verification
- * Contract Required Detection Limit (CRDL)
- * Preparation/ Initial (ICB)/ and Continuing (CCB) Calibration Blanks
- * Interference Check Sample (ICSA) Results
- * Matrix Spike Results
- * Duplicate Sample Results
- * Laboratory Control Samples (LCS) Results
- * Serial Dilution Sample Results
- * Compound Quantitation and Reporting Limits (full validation only)

- * **All criteria were met for this parameter**

Data Completeness

The data package was complete. No results were qualified as a result of the missing data.

Holding Times and Preservation

Analytical holding times were evaluated and all criteria were.

The water samples were all found to be field filtered and had a pH less than 2. Cooler #1 was received at a temperature of 1.2°C and cooler #2 at 1.6 °C.

Initial and Continuing Calibration Verification

Initial and Continuing Calibration Verification standards were analyzed at the required frequency and all were within the required 90-110%. No action was necessary.

Contract Required Detection Limit (CRDL)

All CRDL %Rs CRI %Rs were within 80-120% limits. No action was necessary.

Preparation and Initial/ Continuing Calibration Blanks

Preparation and Initial/Continuing Calibration Blank analyses were performed at the required frequency. Preparation and Initial/ Continuing Calibration Blanks are evaluated to assess the level of contamination in the preparation and analytical processes.

Preparation and Initial/ Continuing Calibration Blanks were prepared and analyzed at the required frequencies.

All of the blanks that were analyzed had concentrations that were below their respective Reporting Limits (RLs).

However, if blank results were above the Instrument Detection Limits (IDLs) and below the RLs, it caused the associated sample results to be qualified for contamination as estimated and non-detected [UJ 107]. If blank results were below the negate IDL and above the negate RL, it caused the associated sample results to be qualified for negative contamination as estimated [J 107]. No sample results were qualified due to blank contamination.

Matrix Spike/Matrix Spike Duplicate Results

MS/MSD analyses were performed at the required frequency. All MS/MSD percent recoveries were within 75-125% limits with the following exception:

The chloride concentration was above the analytical range in the native sample CSMRI-1B and MS/MSD recoveries could not be evaluated. The associated LCS, ICV, and CCV results were within control limits and no action was necessary.

Duplicate Sample Analysis

Duplicate analyses were performed at the required frequency. All original sample/duplicate sample and MS/MSD differences were less than 20% RPD or less than the RDL for results less than (5)(RDL). No actions were necessary.

Laboratory Control Samples

LCS analyses were performed at the required frequency. The laboratory analyzed laboratory control samples for all analytes. All recoveries were within 80-120% limits. No action was necessary.

Serial Dilution Results

All %Ds were less than 10% for all analytes.

Analyte Quantitation and Reporting Limits

Analyte quantitation was evaluated for all samples. No calculation or transcription errors were found. The results and reporting limits were correctly reported.

Overall Comments

The chloride concentration was above the analytical range in the native sample CSMRI-1 and MS/MSD recoveries could not be evaluated. The associated LCS, ICV, and CCV results were within control limits and no action was necessary.

Samples CSMRI-1B, CSMRI-9, CSMRI-10, CSMRI-8, CSMRI-6C, CSMRI-11B, CSMRI-1, CSMRI-2, CSMRI-4, and CSMRI-5 were analyzed at a dilution in order to bring chloride and sulfate concentrations into range.

Reduced aliquots were analyzed for samples CSMRI-1B, CSMRI-9, CSMRI-10, CSMRI-8, CSMRI-6C, CSMRI-11B, CSMRI-1, CSMRI-2, CSMRI-4, and CSMRI-5 for chloride, sulfate, alkalinity, bicarbonate, and carbonate. The laboratory elevated the reporting limits accordingly.

DATA QUALIFIER DEFINITIONS

For the purpose of Data Validation, the following code letters and associated definitions are provided for use by the data validator to summarize the data quality.

- R - Reported value is "rejected." Resampling or reanalysis may be necessary to verify the presence or absence of the compound.
- J - The associated numerical value is an estimated quantity because the Quality Control criteria were not met.
- U J - The reported quantitation limit is estimated because Quality Control criteria were not met. Element or compound was not detected.
- U - The material was analyzed for, but was not detected above the level of the associated value. The associated value is either the sample quantitation limit or the sample detection limit.
- NR - Result was not used from a particular sample analysis. This typically occurs when more than one result for an element is reported due to dilutions and reanalyses.

DATA VALIDATION REPORT

To: Robert Hill
 From: John Garrett
 Date: September 08, 2010
 Project/Site: Colorado School of Mines
 Project No.: 4349-250
 SDG No.: 1009201 Radium-228

This report presents the radiological data validation for the data obtained during the field activities for the above referenced work assignment. The purpose of this review is to provide a technical evaluation of the radiological results that were obtained by ALS Laboratory Group PA SOP 724R10 for Radium-228 by gas proportional counting for SDG 1009201 from ALS Laboratory Group (Fort Collins, CO). This report consists of fifteen water samples for the Colorado School of Mines/4349-250 project collected on September 08, 2010, September 09, 2010, and September 10, 2010 and submitted to ALS Laboratory Group on September 13, 2010. The samples were analyzed for Radium-228 by Radon gas proportional counting on October 08, 2010, and October 18, 2010. All analyses were conducted by ALS Laboratory Group. The field sample numbers and corresponding laboratory numbers are presented below:

Client Sample Number	Laboratory Sample Number	Matrix	Collection Date
CSMRI-1B	1009201-1	Water	September 08, 2010
CSMRI-9	1009201-2	Water	September 08, 2010
CSMRI-10	1009201-3	Water	September 08, 2010
CSMRI-8	1009201-4	Water	September 08, 2010
CSMRI-6C	1009201-5	Water	September 08, 2010
CSMRI-11B	1009201-6	Water	September 08, 2010
SW-1	1009201-7	Water	September 09, 2010
CSMRI-1	1009201-8	Water	September 09, 2010
SW-2	1009201-9	Water	September 09, 2010
SW-3	1009201-10	Water	September 09, 2010
EQUIPMENT BLANK	1009201-11	Water	September 10, 2010
CSMRI-2	1009201-12	Water	September 10, 2010
CSMRI-4	1009201-13	Water	September 10, 2010
CSMRI-5	1009201-14	Water	September 10, 2010
CSMRI-7B	1009201-15	Water	September 10, 2010

Data validation was conducted in accordance with the Analytical Services Statement of Work for the following modules: Gas Proportional Counting Module RC04-v2, October 1, 2002, and U.S. DOE Quality Systems for Analytical Services Revision 2.5 (QSAS).

The radiological data were evaluated based on the following parameters:

- * Data Completeness
- * Holding Times and Preservation
- * Instrument Initial Calibrations
- * Instrument Performance Checks
- * Preparation Blanks
- * Duplicate Sample Results
- * Laboratory Control Samples (LCS) Results
- * Laboratory Control Samples Duplicate (LCSD) Results
- * Compound Quantitation and Reporting Limits (full validation only)

Data Completeness

The data package was complete as per ALS Laboratory Group Procedure SOP 724R10 for Radium-228 by gas flow proportional counting for SDG 1009201.

Holding Times and Preservation

Analytical holding times were evaluated and all criteria were met. However, holding time requirements are not applicable to radiochemistry analyses unless the isotopes of interest have short half-lives.

Calibrations

The instruments were calibrated at the required frequency.

Initial Calibration

All instruments were calibrated properly using NIST traceable SRM.

Instrument Performance Checks

All isotopes were within criteria.

Preparation Blanks

Preparation/Method Blanks were performed at the required frequency. All isotopes that were analyzed had activities that were below their respective MDC's in their QC batch preparation blanks.

Duplicate Sample Analysis

Duplicate analyses were performed at the required frequency. Due to insufficient sample volume the laboratory prepared and analyzed a Laboratory Control Sample Duplicate (LCSD) in lieu of a client sample duplicate.

All isotopic activities for Radium-228 duplicate (LCS) and original (LCSD) analysis were within the limits of the statistical test for equivalency. No action was required.

Matrix Spike/Matrix Spike Duplicates

Matrix spike/matrix spike duplicates were not performed for the samples in this SDG, nor were any required.

Laboratory Control Samples

LCS analyses were performed at the required frequency. All recoveries were within 75-125% limits. No calculation errors or transcription errors were found.

Analyte Quantitation and Reporting Limits

Analyte quantitation was evaluated for all samples. No calculation or transcription errors were found. The results and reporting limits were correctly reported.

Overall Comments

Due to analyst error samples in batch RA100929-1 were counted for 60 minutes instead of 250 minutes. The samples were re-prepared and counted for the required 250 minutes. Sample CSMRI-7B MDA exceeded the RDL and is qualified as Estimated (J).

The laboratory reported that the ICP-AES measurement of the added barium carrier prior to chemical separation had a concentration of less than the concentration added. The laboratory manually adjusted the values to the known concentration to calculate the

chemical yield in order to avoid a low bias in all samples including the QC. All samples reported barium concentrations less than that known to be added.

Radium-228 was detected above the RDL in sample CSMRI-4 at 1.64 pCi/L and is considered detected.

The following sample is qualified:

- CSMRI-7B is Qualified as Estimated (J) due to MDA >RDL.

DATA QUALIFIER DEFINITIONS

For the purpose of Data Validation, the following code letters and associated definitions are provided for use by the data validator to summarize the data quality.

- R - Reported value is "rejected." Resampling or reanalysis may be necessary to verify the presence or absence of the compound.
- J - The associated numerical value is an estimated quantity because the Quality Control criteria were not met.
- U J - The reported quantitation limit is estimated because Quality Control criteria were not met. Element or compound was not detected.
- U - The material was analyzed for, but was not detected above the level of the associated value. The associated value is either the sample quantitation limit or the sample detection limit.
- NR - Result was not used from a particular sample analysis. This typically occurs when more than one result for an element is reported due to dilutions and reanalyses.

DATA VALIDATION REPORT

To: Robert Hill
 From: John Garrett
 Date: November 06, 2010
 Project/Site: Colorado School of Mines
 Project No.: 4349-250
 SDG No.: 1009201

This report presents the inorganic metals data validation for the data obtained for fifteen dissolved metals and dissolved Uranium for the CSMRI water samples collected on September 08, 2010, September 09, 2010, and September 10, 2010 and submitted to ALS Laboratory Group on September 13, 2010 for the above referenced work assignment. The purpose of this review is to provide a technical evaluation of the inorganic metals results that were obtained by SW-846, 3rd edition, Method 6010B and ALS Laboratory Group SOP 834R7 for trace metals by Inductively Coupled Plasma (ICP) atomic emission spectrometry analysis, Method 6020A ALS Laboratory Group Procedure SOP 827R7 for dissolved metals by Inductively Coupled Plasma mass spectrometry (ICP-MS) (Uranium only) analysis for SDG 1009201 by ALS Laboratory Group (Fort Collins, CO). The water samples were extracted on September 30, 2010 and analyzed for dissolved ICP trace metals on October 02, 2010, dissolved uranium by ICP-MS on September 30, 2010. All analyses were conducted by ALS Laboratory Group. The field sample numbers and corresponding laboratory numbers are presented below:

Client Sample Number	Laboratory Sample Number	Matrix	Collection Date
CSMRI-1B	1009201-1	Water	September 08, 2010
CSMRI-9	1009201-2	Water	September 08, 2010
CSMRI-10	1009201-3	Water	September 08, 2010
CSMRI-8	1009201-4	Water	September 08, 2010
CSMRI-6C	1009201-5	Water	September 08, 2010
CSMRI-11B	1009201-6	Water	September 08, 2010
SW-1	1009201-7	Water	September 09, 2010
CSMRI-1	1009201-8	Water	September 09, 2010
SW-2	1009201-9	Water	September 09, 2010
SW-3	1009201-10	Water	September 09, 2010
EQUIPMENT BLANK	1009201-11	Water	September 10, 2010
CSMRI-2	1009201-12	Water	September 10, 2010
CSMRI-4	1009201-13	Water	September 10, 2010
CSMRI-5	1009201-14	Water	September 10, 2010
CSMRI-7B	1009201-15	Water	September 10, 2010

Data validation was conducted in accordance with the USEPA Contract Laboratory Program National Functional Guidelines for Inorganic Data Review.

The metals data were evaluated based on the following parameters:

- * Data Completeness
 - * Holding Times and Preservation
 - * Initial and Continuing Calibration Verification
 - * Contract Required Detection Limit (CRDL)
Preparation/ Initial (ICB)/ and Continuing (CCB) Calibration Blanks
 - * Interference Check Sample (ICSA) Results
 - * Matrix Spike Results
 - * Duplicate Sample Results
 - * Laboratory Control Samples (LCS) Results
Serial Dilution Sample Results
 - * Compound Quantitation and Reporting Limits (full validation only)
- * All criteria were met for this parameter**

Data Completeness

The data package was complete except for the missing CRDL (2B) and IDL (10) QC Summary Forms. No results were qualified as a result of the missing data.

Holding Times and Preservation

Analytical holding times were evaluated and all criteria were met.

The water samples were all found to be field filtered and had a pH less than 2. Cooler #1 was received at a temperature of 1.2°C and cooler #2 at 1.6 °C.

Initial and Continuing Calibration Verification

Initial and Continuing Calibration Verification standards were analyzed at the required frequency and all were within the required 90-110% limits for ICP trace. No action was necessary.

Contract Required Detection Limit (CRDL)

No CRDL or CRI standard recovery summary forms (EPA Form 2b) were included in the data package. The reviewer obtained the %Rs from the instrument raw data. All CRDL %Rs for ICP were within 80-120% limits. No action was necessary.

Preparation and Initial/ Continuing Calibration Blanks

Preparation and Initial/Continuing Calibration Blank analyses were performed at the required frequency. Preparation and Initial/ Continuing Calibration Blanks are evaluated to assess the level of contamination in the preparation and analytical processes.

Preparation and Initial/ Continuing Calibration Blanks were prepared and analyzed at the required frequencies.

All of the blanks that were analyzed had concentrations that were below their respective Reporting Limits (RLs).

However, if blank results were above the Instrument Detection Limits (IDLs) and below the RLs, it caused the associated sample results to be qualified for contamination as estimated and non-detected [UJ 107]. If blank results were below the negate IDL and above the negate RL, it caused the associated sample results to be qualified for negative contamination as estimated [J 107]. No sample results were qualified due to blank contamination.

Interference Check Sample (ICSA) Results

Interference Check Samples were prepared and analyzed at the required frequencies.

No aqueous concentrations of aluminum, calcium, iron, or magnesium exceeded the ICSA values in any of the samples. No action was necessary.

Matrix Spike/Matrix Spike Duplicate Results

MS/MSD analyses were performed at the required frequency. All ICP and ICP-MS percent recoveries were within 75-125% limits. No action was necessary.

Duplicate Sample Analysis

Duplicate analyses were performed at the required frequency. All ICP, and ICP-MS original sample/duplicate sample and MS/MSD differences were less than 20% RPD or

less than the RDL for results less than (5)(RDL). No actions were necessary.

Laboratory Control Samples

LCS analyses were performed at the required frequency. The laboratory analyzed laboratory control samples for all metals. All recoveries were within 80-120% limits. No action was necessary.

Serial Dilution Results

All %Ds were less than 10% for Uranium by ICP-MS and trace metals by ICP.

Analyte Quantitation and Reporting Limits

Analyte quantitation was evaluated for all samples. No calculation or transcription errors were found. The results and reporting limits were correctly reported.

Overall Comments

The data are acceptable as reported with the following exception:

ICP-MS samples were analyzed at a dilution in order to bring uranium into analytical range.

No CRDL or CRI standard recovery summary forms (EPA Form 2b) were included in the data package. The reviewer obtained the results from the raw data. No action was necessary.

DATA QUALIFIER DEFINITIONS

For the purpose of Data Validation, the following code letters and associated definitions are provided for use by the data validator to summarize the data quality.

- R - Reported value is "rejected." Resampling or reanalysis may be necessary to verify the presence or absence of the compound.
- J - The associated numerical value is an estimated quantity because the Quality Control criteria were not met.
- U J - The reported quantitation limit is estimated because Quality Control criteria were not met. Element or compound was not detected.
- U - The material was analyzed for, but was not detected above the level of the associated value. The associated value is either the sample quantitation limit or the sample detection limit.
- NR - Result was not used from a particular sample analysis. This typically occurs when more than one result for an element is reported due to dilutions and reanalyses.

DATA VALIDATION REPORT

To: Robert Hill
 From: John Garrett
 Date: November 08, 2010
 Project/Site: Colorado School of Mines
 Project No.: 4349-250
 SDG No.: 109201 DOC

This report presents the Dissolved Organic Carbon data validation for the data obtained for fourteen CSMRI water sample collected on September 08, 2010, September 09, 2010, and September 10, 2010 and submitted to ALS Laboratory Group on September 13, 2010 for the above referenced work assignment. The purpose of this review is to provide a technical evaluation of eleven Dissolved Organic Carbon results that were obtained by MCAWW, May 1994, Method 415.1, SOP 670R13 Dissolved Organic Carbon by Method 415.1 from ALS Laboratory Group (Fort Collins, CO). The water samples were analyzed September 21, 2010. All analyses were conducted by ALS Laboratory Group. The field sample numbers and corresponding laboratory numbers are presented below:

Client Sample Number	Laboratory Sample Number	Matrix	Collection Date
CSMRI-1B	1009201-1	Water	September 08, 2010
CSMRI-9	1009201-2	Water	September 08, 2010
CSMRI-10	1009201-3	Water	September 08, 2010
CSMRI-8	1009201-4	Water	September 08, 2010
CSMRI-6C	1009201-5	Water	September 08, 2010
CSMRI-11B	1009201-6	Water	September 08, 2010
SW-1	1009201-7	Water	September 09, 2010
CSMRI-1	1009201-8	Water	September 09, 2010
SW-2	1009201-9	Water	September 09, 2010
SW-3	1009201-10	Water	September 09, 2010
EQUIPMENT BLANK	1009201-11	Water	September 10, 2010
CSMRI-2	1009201-12	Water	September 10, 2010
CSMRI-4	1009201-13	Water	September 10, 2010
CSMRI-5	1009201-14	Water	September 10, 2010

Data validation was conducted in accordance with the USEPA Contract Laboratory Program National Functional Guidelines for Organic Data Review (CLP).

The Dissolved Organic Carbon data were evaluated based on the following parameters:

- * Data Completeness
 - * Holding Times and Preservation
 - * Initial and Continuing Calibration Verification
 - * Contract Required Detection Limit (CRDL)
 - * Preparation/ Initial (ICB)/ and Continuing (CCB) Calibration Blanks
 - * Interference Check Sample (ICSA) Results
 - * Matrix Spike Results
 - * Duplicate Sample Results
 - * Laboratory Control Samples (LCS) Results
 - * Serial Dilution Sample Results
 - * Compound Quantitation and Reporting Limits (full validation only)
- * All criteria were met for this parameter**

Data Completeness

The data package was complete. No results were qualified as a result of the missing data.

Holding Times and Preservation

Analytical holding times were evaluated and all criteria were met.

The water samples were all found to be field filtered and had a pH less than 2. Samples were received at a temperature of 1.2 °C and 1.6°C.

Initial and Continuing Calibration Verification

Initial and Continuing Calibration Verification standards were analyzed at the required frequency and all were within the required 90-110%. No action was necessary.

Contract Required Detection Limit (CRDL)

All CRDL %Rs CRI %Rs were within 80-120% limits. No action was necessary.

Preparation and Initial/ Continuing Calibration Blanks

Preparation and Initial/Continuing Calibration Blank analyses were performed at the required frequency. Preparation and Initial/ Continuing Calibration Blanks are evaluated to assess the level of contamination in the preparation and analytical processes.

Preparation and Initial/ Continuing Calibration Blanks were prepared and analyzed at the required frequencies.

All of the blanks that were analyzed had concentrations that were below their respective Reporting Limits (RLs).

However, if blank results were above the Instrument Detection Limits (IDLs) and below the RLs, it caused the associated sample results to be qualified for contamination as estimated and non-detected [UJ 107]. If blank results were below the negate IDL and above the negate RL, it caused the associated sample results to be qualified for negative contamination as estimated [J 107]. No sample results were qualified due to blank contamination.

Matrix Spike/Matrix Spike Duplicate Results

MS/MSD analyses were performed at the required frequency. All MS/MSD percent recoveries were within 75-125% limits. No action was necessary.

Duplicate Sample Analysis

Duplicate analyses were performed at the required frequency. All original sample/duplicate sample and MS/MSD differences were less than 20% RPD or less than the RDL for results less than (5)(RDL). No actions were necessary.

Laboratory Control Samples

LCS analyses were performed at the required frequency. The laboratory analyzed laboratory control samples for all analytes. All recoveries were within 80-120% limits. No action was necessary.

Serial Dilution Results

No dilutions were required.

Analyte Quantitation and Reporting Limits

Analyte quantitation was evaluated for all samples. No calculation or transcription errors were found. The results and reporting limits were correctly reported.

Overall Comments

The overall data are acceptable as reported with the following exception:

The water samples were all found to be field filtered and had a pH less than 2. Cooler #1 was received at a temperature of 5°C. However there is no documentation as to which samples were in the cooler. This should be taken into account when determining the usability of the data for all analyses except for radiochemistry analyses.

DATA QUALIFIER DEFINITIONS

For the purpose of Data Validation, the following code letters and associated definitions are provided for use by the data validator to summarize the data quality.

- R - Reported value is "rejected." Resampling or reanalysis may be necessary to verify the presence or absence of the compound.
- J - The associated numerical value is an estimated quantity because the Quality Control criteria were not met.
- U J - The reported quantitation limit is estimated because Quality Control criteria were not met. Element or compound was not detected.
- U - The material was analyzed for, but was not detected above the level of the associated value. The associated value is either the sample quantitation limit or the sample detection limit.
- NR - Result was not used from a particular sample analysis. This typically occurs when more than one result for an element is reported due to dilutions and reanalyses.

DATA VALIDATION REPORT

To: Robert Hill
 From: John Garrett
 Date: November 09, 2010
 Project/Site: Colorado School of Mines
 Project No.: 4349-250
 SDG No.: 1009201 Radium-226

This report presents the radiological data validation for the data obtained during the field activities for the above referenced work assignment. The purpose of this review is to provide a technical evaluation of the radiological results that were obtained by ALS Laboratory Group Procedure SOP 783R8 for Radium-226 by Radon Emanation Counting for SDG 1009201 from ALS Laboratory Group (Fort Collins, CO). This report consists of fifteen water samples for the Colorado School of Mines/4349-250 project collected on September 08, 2010, September 09, 2010, and September 10, 2010 and submitted to ALS Laboratory Group on September 13, 2010. The samples were analyzed for Radium-226 by Radon Emanation Counting on October 08, 2010. All analyses were conducted by ALS Laboratory Group. The field sample numbers and corresponding laboratory numbers are presented below:

Client Sample Number	Laboratory Sample Number	Matrix	Collection Date
CSMRI-1B	1009201-1	Water	September 08, 2010
CSMRI-9	1009201-2	Water	September 08, 2010
CSMRI-10	1009201-3	Water	September 08, 2010
CSMRI-8	1009201-4	Water	September 08, 2010
CSMRI-6C	1009201-5	Water	September 08, 2010
CSMRI-11B	1009201-6	Water	September 08, 2010
SW-1	1009201-7	Water	September 09, 2010
CSMRI-1	1009201-8	Water	September 09, 2010
SW-2	1009201-9	Water	September 09, 2010
SW-3	1009201-10	Water	September 09, 2010
EQUIPMENT BLANK	1009201-11	Water	September 10, 2010
CSMRI-2	1009201-12	Water	September 10, 2010
CSMRI-4	1009201-13	Water	September 10, 2010
CSMRI-5	1009201-14	Water	September 10, 2010
CSMRI-7B	1009201-15	Water	September 10, 2010

Data validation was conducted in accordance with the Analytical Services Statement of Work for the following modules: Gas Proportional Counting Module RC04-v2, October 1, 2002, and U.S. DOE Quality Systems for Analytical Services Revision 2.5 (QSAS).

The radiological data were evaluated based on the following parameters:

- * Data Completeness
- * Holding Times and Preservation
- * Instrument Initial Calibrations
- * Instrument Performance Checks
- * Preparation Blanks
- * Duplicate Sample Results
- * Laboratory Control Samples (LCS) Results
- * Laboratory Control Samples Duplicate (LCSD) Results
- * Compound Quantitation and Reporting Limits (full validation only)

Data Completeness

The data package was complete as per ALS Laboratory Group Procedure SOP 783R8 for Radium-226 by Radon Emanation counting.

Holding Times and Preservation

Analytical holding times were evaluated and all criteria were met. However, holding time requirements are not applicable to radiochemistry analyses unless the isotopes of interest have short half-lives.

Calibrations

The instruments were calibrated at the required frequency.

Initial Calibration

All instruments were calibrated properly using NIST traceable SRM.

Instrument Performance Checks

All isotopes were within criteria.

Preparation Blanks

Preparation/Method Blanks were performed at the required frequency. All isotopes that were analyzed had activities that were below their respective MDCs in their QC batch preparation blanks.

Duplicate Sample Analysis

Duplicate analyses were performed at the required frequency. Due to limited sample volume the laboratory prepared a LCSD in lieu of a client sample Duplicate. All isotopic activities for Radium-226 LCS Duplicate and LCS original analysis were within the limits of the statistical test for equivalency. No action was required.

Matrix Spike/Matrix Spike Duplicates

Matrix spike/matrix spike duplicates were not performed for the samples in this SDG, nor were any required.

Laboratory Control Samples

LCS analyses were performed at the required frequency. All recoveries were within 75-125% limits. No calculation errors or transcription errors were found.

Analyte Quantitation and Reporting Limits

Analyte quantitation was evaluated for all samples. No calculation or transcription errors were found. The results and reporting limits were correctly reported.

Overall Comments

Overall, the data are of good quality and are usable as reported by the laboratory without qualification.

Radium-226 was detected above the RDL in sample CSMRI-7B at 1.13 pCi/L and is considered detected.

The laboratory reported that the ICP-AES measurement of the added barium carrier prior to chemical separation. Several samples showed barium concentrations less than zero. The laboratory manually adjusted the values to 0.0 in order to avoid a low bias. All QC criteria were within control limits and no action was necessary. The data are not affected.

DATA QUALIFIER DEFINITIONS

For the purpose of Data Validation, the following code letters and associated definitions are provided for use by the data validator to summarize the data quality.

- R - Reported value is "rejected." Resampling or reanalysis may be necessary to verify the presence or absence of the compound.
- J - The associated numerical value is an estimated quantity because the Quality Control criteria were not met.
- U J - The reported quantitation limit is estimated because Quality Control criteria were not met. Element or compound was not detected.
- U - The material was analyzed for, but was not detected above the level of the associated value. The associated value is either the sample quantitation limit or the sample detection limit.
- NR - Result was not used from a particular sample analysis. This typically occurs when more than one result for an element is reported due to dilutions and reanalysis.

Appendix E
Results of Analyses CD

Appendix F

Chains of Custody



ALS Laboratory Group

225 Commerce Drive, Fort Collins, Colorado 80524
 TF: (800) 443-1511 PH: (970) 490-1511 FX: (970) 490-1522

Chain-of-Custody

Form 202r8

WORKORDER #	
PAGE	1 of 7

PROJECT NAME	CO School of Mines	SAMPLER	N Malczyk	DATE	9/13/10	TURNAROUND	standard	DISPOSAL	By Lab or Return to Client
PROJECT No.	4349-250	SITE ID							
COMPANY NAME	Stoller	EDD FORMAT							
SEND REPORT TO	Robert Hill	PURCHASE ORDER							
ADDRESS	105 Technology Dr #190	BILL TO COMPANY							
CITY/STATE/ZIP	Broomfield, CO 80021	INVOICE ATTN TO							
PHONE	(303) 546-4440	ADDRESS							
FAX	(303) 443-1408	CITY/STATE/ZIP							
E-MAIL	rhill@stoller.com	PHONE							
		FAX							
		E-MAIL							

Radium - 226
 Radium - 228
 Dissolved Uranium
 Cations
 Anions
 DOC

Lab ID	Field ID	Matrix	Sample Date	Sample Time	# Bottles	Pres.	QC													
	CSURJ-1B	W	9/8/10	0900	1	HNO ₃		X	X	X										
	↓				1	HNO ₃					X									
	↓				1	-						X								
	↓				1	H ₂ SO ₄							X							
	CSURJ-9			1010	1	HNO ₃		X	X	X										
	↓				1	HNO ₃					X									
	↓				1	-						X								
	↓				1	H ₂ SO ₄							X							
	CSURJ-10			1040	1	HNO ₃		X	X	X										
	↓				1	HNO ₃					X									

*Time Zone (Circle): EST CST MST PST Matrix: O=oil S=soil NS=non-soil solid W=water L=liquid E=extract F=filter

For metals or anions, please detail analytes below.

Comments: All samples were filtered Anions - HCO ₃ , CO ₃ , Alkalinity, Cl, SO ₄ Cations - Ca, Mg, K, Na	QC PACKAGE (check below)	
	<input type="checkbox"/>	LEVEL II (Standard QC)
	<input type="checkbox"/>	LEVEL III (Std QC + forms)
	<input checked="" type="checkbox"/>	LEVEL IV (Std QC + forms + raw data)
Preservative Key: 1-HCl 2-HNO ₃ 3-H ₂ SO ₄ 4-NaOH 5-NaHSO ₄ 7-Other 8-4 degrees C 9-5035		

SIGNATURE	PRINTED NAME	DATE	TIME
	Nick Malczyk	9/13/10	1130
RELINQUISHED BY			
RECEIVED BY			
RELINQUISHED BY			
RECEIVED BY			
RELINQUISHED BY			
RECEIVED BY			



LS Laboratory Group

225 Commerce Drive, Fort Collins, Colorado 80524
 TF: (800) 443-1511 PH: (970) 490-1511 FX: (970) 490-1522

C' 1-of-Custody

WORKORDER #

Form 202r8

PROJECT NAME <i>CO school of Mines</i>		SAMPLER <i>N Malczyk</i>		DATE <i>9/13/10</i>		PAGE <i>2 of 7</i>	
PROJECT No. <i>see page 1</i>		SITE ID		TURNAROUND <i>standard</i>		DISPOSAL <u>By Lab</u> or Return to Client	
COMPANY NAME		EDD FORMAT		<i>Radium-226</i> <i>Radium-228</i> <i>Dissolved Uranium</i> <i>Cations</i> <i>Anions</i> <i>DOC</i>			
SEND REPORT TO		PURCHASE ORDER					
ADDRESS		BILL TO COMPANY					
CITY / STATE / ZIP		INVOICE ATTN TO					
PHONE		ADDRESS					
FAX		CITY / STATE / ZIP					
E-MAIL		PHONE					
		FAX					
		E-MAIL					
Lab ID	Field ID	Matrix	Sample Date	Sample Time	# Bottles	Pres.	QC
	<i>CSMRI-10</i>	<i>W</i>	<i>9/8/10</i>	<i>1040</i>	<i>1</i>	<i>-</i>	
	<i>↓</i>			<i>↓</i>	<i>1</i>	<i>H₂SO₄</i>	
	<i>CSMRI-8</i>			<i>1105</i>	<i>1</i>	<i>HNO₃</i>	<i>X X X</i>
	<i>↓</i>			<i>↓</i>	<i>1</i>	<i>HNO₃</i>	<i>X</i>
	<i>↓</i>			<i>↓</i>	<i>1</i>	<i>-</i>	<i>X</i>
	<i>↓</i>			<i>↓</i>	<i>1</i>	<i>H₂SO₄</i>	<i>X</i>
	<i>CSMRI-6C</i>			<i>1340</i>	<i>1</i>	<i>HNO₃</i>	<i>X X X</i>
	<i>↓</i>			<i>↓</i>	<i>1</i>	<i>HNO₃</i>	<i>X</i>
	<i>↓</i>			<i>↓</i>	<i>1</i>	<i>-</i>	<i>X</i>
	<i>↓</i>			<i>↓</i>	<i>1</i>	<i>H₂SO₄</i>	<i>X</i>

*Time Zone (Circle): EST CST PST Matrix: O=oil S=soil NS=non-soil solid W=water L=liquid E=extract F=filter

For metals or anions, please detail analytes below.

Comments: <i>see page 1</i>	QC PACKAGE (check below)	
	<input type="checkbox"/>	LEVEL II (Standard QC)
	<input type="checkbox"/>	LEVEL III (Std QC + forms)
	<input checked="" type="checkbox"/>	LEVEL IV (Std QC + forms + raw data)
Preservative Key: 1-HCl 2-HNO3 3-H2SO4 4-NaOH 5-NaHSO4 7-Other 8-4 degrees C 9-5035		

SIGNATURE	PRINTED NAME	DATE	TIME
<i>[Signature]</i>	<i>Nick Malczyk</i>	<i>9/13/10</i>	<i>1130</i>
RELINQUISHED BY			
RECEIVED BY			
RELINQUISHED BY			
RECEIVED BY			
RELINQUISHED BY			
RECEIVED BY			



ALS Laboratory Group

225 Commerce Drive, Fort Collins, Colorado 80524
 TF: (800) 443-1511 PH: (970) 490-1511 FX: (970) 490-1522

C1 1-of-Custody

Form 202r8

WORKORDER #

PAGE 3 of 7

DISPOSAL By Lab or Return to Client

PROJECT NAME	CO School of Mines	SAMPLER	N Malczyk	DATE	9/13/10
PROJECT No.	see page 1	SITE ID		TURNAROUND	standard
COMPANY NAME		EDD FORMAT			
SEND REPORT TO		PURCHASE ORDER			
ADDRESS		BILL TO COMPANY			
CITY / STATE / ZIP		INVOICE ATTN TO			
PHONE		ADDRESS			
FAX		CITY / STATE / ZIP			
E-MAIL		PHONE			
		FAX			
		E-MAIL			

Radium-226
 Radium-228
 Dissolved Uranium
 Cations
 Anions
 DOC

Lab ID	Field ID	Matrix	Sample Date	Sample Time	# Bottles	Pres.	QC												
	CSMRI-11B	W	9/8/10	1435	1	HNO ₃		X	X	X									
	↓		↓	↓	1	HNO ₃					X								
	↓		↓	↓	1	-						X							
	SW-1		9/9/10	1125	1	H ₂ SO ₄		X	X	X									
	↓		↓	↓	1	HNO ₃					X								
	↓		↓	↓	1	-						X							
	CSMRI-1		↓	1200	1	H ₂ SO ₄		X	X	X									
	↓		↓	↓	1	HNO ₃					X								

*Time Zone (Circle): EST CST (MST) PST Matrix: O=oil S=soil NS=non-soil solid W=water L=liquid E=extract F=filter

For metals or anions, please detail analytes below.

Comments: see page 1

QC PACKAGE (check below)	
<input type="checkbox"/>	LEVEL II (Standard QC)
<input type="checkbox"/>	LEVEL III (Std QC + forms)
<input checked="" type="checkbox"/>	LEVEL IV (Std QC + forms + raw data)

Preservative Key: 1-HCl 2-HNO₃ 3-H₂SO₄ 4-NaOH 5-NaHSO₄ 7-Other 8-4 degrees C 9-5035

SIGNATURE	PRINTED NAME	DATE	TIME
<i>[Signature]</i>	Nick Malczyk	9/13/10	1130
RELINQUISHED BY			
RECEIVED BY			
RELINQUISHED BY			
RECEIVED BY			
RELINQUISHED BY			
RECEIVED BY			



ALS Laboratory Group

225 Commerce Drive, Fort Collins, CO 80524
TF: 800-443-1511 PH: 970-490-1511 FX: 970-490-1522

Chain -Custody

Project Name/No. <u>CO School of Mines</u>		Sampler(s) <u>see page 1</u>		Date <u>9/12/10</u>	Page <u>7</u> of <u>7</u>	Lab ID																															
REPORT TO:	PHONE:	FAX:	E-MAIL:	COMPANY:	ADDRESS:	Turnaround	Standard or Due	Disposal	By Lab or Return to Client																												
Provide additional information as needed in Comments below.						Circle Analytical Method Above		Circle Analytical Method Above																													
Sample ID	Date	Time	Lab ID	Matrix	Perservative (Type HCl, etc.)	No. of Containers	TPH	VOCs	BTEX + MtBE	SVOCs	OC Pesticides	PCBs	Herbicides	Explosives	TCLP Organics SW1311	TCLP Metals SW1311	Total Metals (ICP) or Hg	Dissolved Metals (ICP) or Hg	Total Metals (ICP-MS)	Dissolved Metals (ICP-MS)	Hexavalent Chromium	Inorganic Anions	Solids	pH	Perchlorate	Actinides	Gamma Isotopes	Gross Alpha / Beta	Total Alpha-Emitting Radium	Radium 226	Radium 228	Strontium 90 (Total RadioSr)	Tritium	Radon 222			
<u>CSUR I-5</u>	<u>9/12/10</u>	<u>1045</u>	<u>W1120</u>	<u>W</u>		<u>1</u>																															
<u>↓</u>	<u>↓</u>	<u>↓</u>	<u>↓</u>	<u>↓</u>		<u>1</u>																															
<u>CSUR J-7B</u>	<u>↓</u>	<u>1115</u>	<u>W1120</u>	<u>W</u>		<u>1</u>																															

* Zone (Circle): EST CST MST PST Matrix: O = oil S = soil NS = non-soil solid W = water L = liquid E = extract F = filter

For metals or anions, please detail analyte list below.

Comments: see page 1

Relinquished By: (1)	Relinquished By: (2)
Signature <u>[Signature]</u>	Signature _____
Printed Name <u>[Name]</u>	Printed Name _____
Date <u>9/12/10</u> Time <u>1130</u>	Date _____ Time _____
Company <u>skeller</u>	Company _____
Received By: (1)	Received By: (2)
Signature _____	Signature _____
Printed Name _____	Printed Name _____
Date _____ Time _____	Date _____ Time _____
Company _____	Company _____

Originator: Retain pink page or a photocopy!

Chain of Custody Record

Sampler ID _____

Temperature on Receipt _____

Drinking Water? Yes No

TestAmerica

THE LEADER IN ENVIRONMENTAL TESTING

TAL-4124-280 (0508)

Client <u>Stoller</u>		Project Manager <u>Robert Hill</u>		Date <u>7/2/10</u>	Chain of Custody Number <u>134528</u>
Address <u>105 Technology Dr #190</u>		Telephone Number (Area Code)/Fax Number <u>(303) 546-4410</u>		Lab Number	
City <u>Broomfield</u>	State <u>CO</u>	Zip Code <u>80021</u>	Site Contact <u>Lisa Urrutia</u>	Page <u>1</u> of <u>1</u>	

Project Name and Location (State) <u>CO School of Mines Golden, CO</u>		Carrier/Waybill Number		Analysis (Attach list if more space is needed)		Special Instructions/ Conditions of Receipt
Contract/Purchase Order/Quote No.				<u>NO₃</u> <u>TDS</u> <u>Iron</u> <u>Lead</u> <u>Sulfate</u>		

Sample I.D. No. and Description (Containers for each sample may be combined on one line)	Date	Time	Matrix				Containers & Preservatives						Analysis	Special Instructions/ Conditions of Receipt
			Air	Aqueous	Sed.	Soil	Unpres.	H2SO4	HNO3	HCl	NaOH	ZnAc2/NaOH		
<u>1</u>	<u>7/2/10</u>	<u>1100</u>		X									X	
<u>↓</u>		<u>↓</u>		X									X	
<u>13483-1</u>		<u>1200</u>		X									X	
<u>↓</u>		<u>↓</u>	<u>↓</u>		X								X	
<u>111-2</u>		<u>1415</u>		X									X	
<u>↓</u>		<u>↓</u>	<u>↓</u>		X								X	
<u>120-2</u>	<u>1345</u>		X									X		
<u>↓</u>	<u>↓</u>	<u>↓</u>		X								X		

Possible Hazard Identification <input checked="" type="checkbox"/> Non-Hazard <input type="checkbox"/> Flammable <input type="checkbox"/> Skin Irritant <input type="checkbox"/> Poison B <input type="checkbox"/> Unknown	Sample Disposal <input type="checkbox"/> Return To Client <input checked="" type="checkbox"/> Disposal By Lab <input type="checkbox"/> Archive For _____ Months	(A fee may be assessed if samples are retained longer than 1 month)
---	--	---

Turn Around Time Required <input type="checkbox"/> 24 Hours <input type="checkbox"/> 48 Hours <input type="checkbox"/> 7 Days <input type="checkbox"/> 14 Days <input type="checkbox"/> 21 Days <input checked="" type="checkbox"/> Other: <u>210 days</u>	QC Requirements (Specify)
---	---------------------------

1. Relinquished By <u>[Signature]</u>	Date <u>7/2/10</u>	Time <u>15:50</u>	1. Received By <u>[Signature]</u>	Date <u>7/2/10</u>	Time <u>15:50</u>
2. Relinquished By	Date	Time	2. Received By	Date	Time
3. Relinquished By	Date	Time	3. Received By	Date	Time

Comments

Chain Custody Record

Sampler ID _____

Temperature on Receipt _____

Drinking Water? Yes No

TestAmerica

THE LEADER IN ENVIRONMENTAL TESTING

TAL-4124-280 (0508)

Client Stoller		Project Manager Robert Hill		Date 9/10/10	Chain of Custody Number 132652
Address 105 Technology Dr #190		Telephone Number (Area Code)/Fax Number (303) 546-4440		Lab Number	
City Broomfield	State CO	Zip Code 80021	Site Contact	Lab Contact Lisa Uniell	Page 1 of 2
Project Name and Location (State) CO School of Mines Golden, CO			Carrier/Waybill Number		
Contract/Purchase Order/Quote No.					

Sample I.D. No. and Description (Containers for each sample may be combined on one line)	Date	Time	Matrix				Containers & Preservatives						Analysis (Attach list if more space is needed)	Special Instructions/ Conditions of Receipt		
			Air	Aqueous	Sed.	Soil	Unpres.	H2SO4	HNO3	HCl	NaOH	ZnAc/NaOH				
Equipment Blank	9/10/10	0700	X				X									
↓		↓	X				X									
CSMRI-2		0850	X				X									
↓		↓	X				X									
CSMRI-4		0930	X				X									
↓		↓	X				X									
↓		↓	X				X		X							
↓		↓	X				X			X						
CSMRI-5		1045	X				X									
↓		↓	X				X									
↓		↓	X				X									

Possible Hazard Identification: Non-Hazard Flammable Skin Irritant Poison B Unknown

Sample Disposal: Return To Client Disposal By Lab Archive For _____ Months (A fee may be assessed if samples are retained longer than 1 month)

Turn Around Time Required: 24 Hours 48 Hours 7 Days 14 Days 21 Days Other **210 days**

QC Requirements (Specify)

1. Relinquished By 	Date 9/10/10	Time 1435	1. Received By 	Date 9/10/10	Time 1435
2. Relinquished By	Date	Time	2. Received By	Date	Time
3. Relinquished By	Date	Time	3. Received By	Date	Time

Comments

Chain Custody Record

Sampler ID _____

Temperature on Receipt _____

Drinking Water? Yes No

TestAmerica

THE LEADER IN ENVIRONMENTAL TESTING

TAL-4124-280 (0508)

Client <i>Stoller</i>		Project Manager <i>Robert Hill</i>		Date <i>9/10/10</i>	Chain of Custody Number 132651
Address <i>103 Technology Dr #190</i>		Telephone Number (Area Code)/Fax Number <i>(303) 546-4440</i>		Lab Number	
City <i>Broomfield</i>	State <i>CO</i>	Zip Code <i>80021</i>	Site Contact	Lab Contact <i>Lisa Urzull</i>	Page <i>2</i> of <i>2</i>

Project Name and Location (State) <i>CO School of mines Golden, CO</i>		Carrier/Waybill Number		Analysis (Attach list if more space is needed)		Special Instructions/ Conditions of Receipt
Contract/Purchase Order/Quote No.		Matrix		Containers & Preservatives		

Sample I.D. No. and Description (Containers for each sample may be combined on one line)	Date	Time	Matrix				Containers & Preservatives						Analysis	Special Instructions/ Conditions of Receipt				
			Air	Aqueous	Sed.	Soil	Unpres.	H2SO4	HNO3	HCl	NaOH	ZnAc/ NaOH						
<i>CSMRT-5</i>	<i>9/10/10</i>	<i>10:45</i>		X														
<i>↓</i>				X														

Possible Hazard Identification			Sample Disposal			(A fee may be assessed if samples are retained longer than 1 month)		
<input checked="" type="checkbox"/> Non-Hazard	<input type="checkbox"/> Flammable	<input type="checkbox"/> Skin Irritant	<input type="checkbox"/> Poison B	<input type="checkbox"/> Unknown	<input type="checkbox"/> Return To Client	<input checked="" type="checkbox"/> Disposal By Lab	<input type="checkbox"/> Archive For _____ Months	

Turn Around Time Required			QC Requirements (Specify)		
<input type="checkbox"/> 24 Hours	<input type="checkbox"/> 48 Hours	<input type="checkbox"/> 7 Days	<input type="checkbox"/> 14 Days	<input type="checkbox"/> 21 Days	<input checked="" type="checkbox"/> Other <i><10 days</i>

1. Relinquished By <i>[Signature]</i>	Date <i>9/10/10</i>	Time <i>14:35</i>	1. Received By <i>[Signature]</i>	Date <i>9/10/10</i>	Time <i>14:35</i>
2. Relinquished By	Date	Time	2. Received By	Date	Time
3. Relinquished By	Date	Time	3. Received By	Date	Time

Comments

Appendix G

Historical Summary Tables

**Table G-1
Historical Summary of Radioisotopes in Groundwater (Stoller)**

Sample Station	Sample Date	Ra-226 (pCi/l)	Ra-228 (pCi/l)	Th-228 (pCi/l)	Th-230 (pCi/l)	Th-232 (pCi/l)	U-234 (pCi/l)	U-235 (pCi/l)	U-238 (pCi/l)	Total U (ug/l)	
CSMRI-1	2/25/2005	-0.11	0.81	0.007	0.07	0.01	0.77	0.043	0.53	1.61	
	6/14/2005	0.16	0.44	0.018	-0.021	0.012	0.43	0.011	0.217	0.64	
	9/7/2005	0.1	0.63	0.068	0.167	0.114	0.85	0.053	0.43	1.3	
	12/20/2005	-0.19	0.59	-0.045	0.32	0.014	0.94	0.073	0.46	1.41	
	3/15/2006	-0.15	0.58	0.025	0.032	-0.004	1.76	0.11	0.92	2.8	
	6/14/2006	0.42	0.05	0.15	-0.06	0.062	0.18	0.18	0.08	0.31	
	9/13/2006	0.25	0.34	0.11	-0.079	0.027	0.45	0.051	0.25	0.77	
	3/1/2007	0.32	0.78	0.052	-0.031	0.012	NT	NT	NT	1.2	
	6/27/2007	0.51	0.91	0.17	0.064	-0.005	NT	NT	NT	0.88	
	9/11/2007	-0.3	0.53	-0.031	0.019	0.001	NT	NT	NT	0.72	
	11/27/2007	-0.2	0.72	0.71	0.101	0.02	NT	NT	NT	1.2	
	2/27/2008	0.2	0.85	0.035	0.032	0.011	NT	NT	NT	1.5	
	4/18/2008	-0.02	0.66	-0.03	-0.004	0.01	NT	NT	NT	1.9	
	9/25/2008	0.26	0.88	NT	NT	NT	NT	NT	NT	0.96	
	12/3/2008	0.32	1.39	NT	NT	NT	NT	NT	NT	1.5	
	3/17/2009	0.09	0.96	NT	NT	NT	NT	NT	NT	2	
	6/24/2009	0.19	0.16 J	NT	NT	NT	NT	NT	NT	1.6	
	9/24/2009	2.64	1.01	NT	NT	NT	NT	NT	NT	2.4	
	12/17/2009	0.39	0.96	NT	NT	NT	NT	NT	NT	2.4	
	3/9/2010	0.11	0.38	NT	NT	NT	NT	NT	NT	2.9	
6/10/2010	0.1	0.93	NT	NT	NT	NT	NT	NT	2.4		
CSMRI-1B	3/8/2007	0.13	1.19	-0.03	-0.09	0.02	NT	NT	NT	2.7	
	6/26/2007	0.09	0.3	0.001	0.002	0.012	NT	NT	NT	5	
	9/11/2007	-0.13	0.65	0.019	0.012	0.001	NT	NT	NT	6.3	
	11/27/2007	0.11	1.16	0.004	0.06	0.016	NT	NT	NT	6.9	
	2/28/2008	0.32	0.61	0.01	0.058	0.033	NT	NT	NT	6.5	
	4/18/2008	0.03	0.72	-0.004	-0.046	0	NT	NT	NT	6	
	9/24/2008	0.05	0.3	NT	NT	NT	NT	NT	NT	4	
	12/5/2008	0.02	0.88	NT	NT	NT	NT	NT	NT	4.6	
	3/18/2009	0.2	1.15	NT	NT	NT	NT	NT	NT	8.1	
	6/24/2009	0.05	0.69 J	NT	NT	NT	NT	NT	NT	15	
	9/25/2009	0.08	0.89	NT	NT	NT	NT	NT	NT	34	
	12/17/2009	-0.03	0.98	NT	NT	NT	NT	NT	NT	16	
	3/11/2010	0.09	0.42	NT	NT	NT	NT	NT	NT	9.4	
	6/9/2010	0.23	-0.03 R	NT	NT	NT	NT	NT	NT	18	
	CSMRI-2	2/25/2005	0.8	1.85	0.07	-0.02	0.01	0.6	0.05	0.16	0.53
		6/14/2005	1.47	3	0.14	0.003	0.026	0.68	0.025	0.299	0.89
9/7/2005		1.78	2.71	0.162	0.108	0.049	0.65	0.05	0.31	0.94	
12/20/2005		1.35	1.62	0.108	0.285	0.024	0.83	0.002	0.35	1.06	
3/15/2006		1.25	2.53	0.03	0.204	0.012	0.83	0.066	0.45	1.36	
6/14/2006		0.99	1.79	0.25	0.22	0.049	0.69	0.04	0.25	0.76	
9/13/2006		1.01	2.35	0.088	-0.039	-0.008	0.46	0.014	0.28	0.85	
3/8/2007		0.76	2.15	0.022	-0.01	0.011	NT	NT	NT	0.72	
6/28/2007		1.4	3.2	-0.075	-0.01	-0.007	NT	NT	NT	2	
9/11/2007		0.78	3.2	0.016	0.101	0.014	NT	NT	NT	0.98	
11/27/2007		0.45	2.05	0.037	0.035	0.006	NT	NT	NT	1	
2/28/2008		1.37	2.26	0.043	0.085	0.044	NT	NT	NT	0.68	
4/17/2008		1.08	1.89	0.041	-0.021	0.008	NT	NT	NT	0.89	
9/24/2008		0.97	1.41	NT	NT	NT	NT	NT	NT	0.69	
12/5/2008		1.1	1.88	NT	NT	NT	NT	NT	NT	0.83	
3/18/2009		2.37	2.68	NT	NT	NT	NT	NT	NT	0.77	
6/24/2009		0.78	2.64 J	NT	NT	NT	NT	NT	NT	0.66	
9/25/2009		0.63	2.12	NT	NT	NT	NT	NT	NT	0.6	
12/18/2009		1.02	1.6	NT	NT	NT	NT	NT	NT	0.75	
3/11/2010		2.4	1.16	NT	NT	NT	NT	NT	NT	0.59	
6/10/2010	0.27	2.25	NT	NT	NT	NT	NT	NT	1.6		
CSMRI-4	2/25/2005	-0.03	0.16	0.019	-0.009	0.013	9.7	0.53	8.2	24.7	
	6/14/2005	0.26	0.34	0.013	0.014	0.005	11.4	0.49	10.6	31.4	
	9/7/2005	0.17	0.78	-0.013	0.164	0.086	6.4	0.33	6.4	19.3	
	12/20/2005	0.13	0.1	0.033	0.311	0.012	11.5	0.61	11.4	34.3	
	3/15/2006	0	0.38	0.004	0.174	0.007	9	0.43	9	27.1	
	6/15/2006	0.41	0.39	0.11	0.17	0.061	9.2	0.4	8.9	26.8	
	9/13/2006	-0.05	0.79	0.056	-0.015	0.007	6.5	0.35	6	17.9	
	3/8/2007	0.09	0.37	-0.034	-0.037	0.013	NT	NT	NT	48	
	6/27/2007	0.07	0.87	0.011	0.035	0.004	NT	NT	NT	66	
	9/11/2007	0.99	1.12	0.024	0.112	0.021	NT	NT	NT	49	
	11/26/2007	0.33	0.73	0.029	0.149	0.016	NT	NT	NT	48	
	2/27/2008	0.24	0.78	0.011	0.038	0.014	NT	NT	NT	58	
	4/17/2008	0.11	0.71	0.017	-0.019	0.002	NT	NT	NT	62	
	9/25/2008	0.32	0.8	NT	NT	NT	NT	NT	NT	43	
	12/5/2008	0.09	0.97	NT	NT	NT	NT	NT	NT	61	
	3/17/2009	0.54	0.56	NT	NT	NT	NT	NT	NT	80	
	6/23/2009	0.21	0.89 J	NT	NT	NT	NT	NT	NT	110	
	9/24/2009	0.11	0.73	NT	NT	NT	NT	NT	NT	160	
	12/16/2009	0.21	0.68	NT	NT	NT	NT	NT	NT	79	
	3/10/2010	8.6	0.57	NT	NT	NT	NT	NT	NT	83	
5/3/2010	0.38	NT	NT	NT	NT	NT	NT	NT	NT		
6/8/2010	0.6	1.42	NT	NT	NT	NT	NT	NT	56		
CSMRI-5	2/25/2005	1.06	0.53	0.009	0.007	0.034	1.22	0.056	0.93	2.8	
	6/14/2005	2.51	0.44	-0.018	0.039	0.011	1.51	0.086	1.2	3.57	
	9/7/2005	2.5	0.76	0.06	1.25	0.051	1.85	0.051	1.47	4.4	
	12/20/2005	1.97	0.52	0.032	0.126	0.01	1.45	0.066	1.21	3.63	
	3/15/2006	0.57	0.45	0.038	0.144	0.019	1.81	0.058	1.38	4.1	
	6/15/2006	2.13	0.87	0.145	0.08	0.043	1.03	0.13	0.92	2.8	
	9/13/2006	2.29	0.56	0.053	-0.053	0.005	3.18	0.17	2.32	7	
	3/8/2007	1.78	0.39	-0.012	-0.061	0	NT	NT	NT	5.8	
	6/27/2007	2.22	0.86	0.008	-0.023	0.013	NT	NT	NT	10	
	9/11/2007	1.91	1.2	0.091	0.003	0.006	NT	NT	NT	11	
	11/26/2007	1.52	0.49	0.004	-0.008	0.01	NT	NT	NT	6.6	
	2/27/2008	1.05	0.17	-0.011	0.02	0.051	NT	NT	NT	6.6	
	4/17/2008	1.37	0.64	0.068	0.029	0.017	NT	NT	NT	6.7	
	9/25/2008	2.87	0.47	NT	NT	NT	NT	NT	NT	10	
	12/4/2008	0.78	0.68	NT	NT	NT	NT	NT	NT	10	
	3/17/2009	0.29	1.24	NT	NT	NT	NT	NT	NT	11	
	6/23/2009	1.96	1.15 J	NT	NT	NT	NT	NT	NT	12	
	9/24/2009	-0.15	0.85	NT	NT	NT	NT	NT	NT	11	
	12/16/2009	1.28	0.44	NT	NT	NT	NT	NT	NT	9.8	
	3/10/2010	3.9	0.4	NT	NT	NT	NT	NT	NT	10	
5/3/2010	0.83	NT	NT	NT	NT	NT	NT	NT	NT		
6/8/2010	2.42	0.75	NT	NT	NT	NT	NT	NT	8.7		

**Table G-1
Historical Summary of Radioisotopes in Groundwater (Stoller)**

Sample Station	Sample Date	Ra-226 (pCi/l)	Ra-228 (pCi/l)	Th-228 (pCi/l)	Th-230 (pCi/l)	Th-232 (pCi/l)	U-234 (pCi/l)	U-235 (pCi/l)	U-238 (pCi/l)	Total U (µg/l)
CSMRI-6B	2/27/2007	NT	NT	NT	NT	NT	NT	NT	NT	NT
	6/26/2007	0.46	0.63	-0.009	-0.006	0.024	NT	NT	NT	17
	9/10/2007	0.15	0.91	0.046	0.025	0.023	NT	NT	NT	11
	11/27/2007	-0.02	0.77	-0.002	0.069	0.004	NT	NT	NT	8.2
	2/28/2008	0.26	1	-0.009	0.022	0.022	NT	NT	NT	4.7
4/18/2008	0.36	0.88	-0.005	-0.022	0.021	NT	NT	NT	5	
CSMRI-6C	7/11/08 (DRY)	NT	NT	NT	NT	NT	NT	NT	NT	NT
	12/3/08 (DRY)	NT	NT	NT	NT	NT	NT	NT	NT	NT
	3/16/09 (DRY)	NT	NT	NT	NT	NT	NT	NT	NT	NT
	6/24/2009	-0.11	1.81 J	NT	NT	NT	NT	NT	NT	19
	9/24/2009	0.09	1.39	NT	NT	NT	NT	NT	NT	17
	12/18/2009	NT	NT	NT	NT	NT	NT	NT	NT	12
	3/8/10 (DRY)	NT	NT	NT	NT	NT	NT	NT	NT	NT
	6/8/2010	0.34	1.48	NT	NT	NT	NT	NT	NT	12
CSMRI-7B	2/27/2007	NT	NT	NT	NT	NT	NT	NT	NT	NT
	6/26/2007	0.65	0.22	0.036	0.054	0.027	NT	NT	NT	68
	9/10/2007	NT	NT	NT	NT	NT	NT	NT	NT	NT
	11/26/2007	NT	NT	NT	NT	NT	NT	NT	NT	NT
	2/26/2008	NT	NT	NT	NT	NT	NT	NT	NT	NT
	4/15/08 (DRY)	NT	NT	NT	NT	NT	NT	NT	NT	NT
	9/24/08 (DRY)	NT	NT	NT	NT	NT	NT	NT	NT	NT
	12/3/08 (DRY)	NT	NT	NT	NT	NT	NT	NT	NT	NT
	3/16/09 (DRY)	NT	NT	NT	NT	NT	NT	NT	NT	NT
	6/24/09 (DRY)	NT	NT	NT	NT	NT	NT	NT	NT	NT
	9/25/09 (DRY)	NT	NT	NT	NT	NT	NT	NT	NT	NT
	12/18/2009 (DRY)	NT	NT	NT	NT	NT	NT	NT	NT	NT
	3/8/10 (DRY)	NT	NT	NT	NT	NT	NT	NT	NT	NT
6/10/2010	0.21	0.17 R	NT	NT	NT	NT	NT	NT	84	
CSMRI-8	3/8/2007	0.7	1.06	0.072	-0.031	0.016	NT	NT	NT	1,100
	6/27/2007	0.8	0.4	0.039	0.046	0.008	NT	NT	NT	810
	9/10/2007	1.31	0.9	0.031	0.05	0.009	NT	NT	NT	630
	11/27/2007	1.27	1.2	-0.02	0.074	-0.003	NT	NT	NT	1,300
	2/27/2008	1.19	1.38	0.089	0.1	0.043	NT	NT	NT	1,200
	4/17/2008	0.39	0.71	-0.015	-0.053	0.009	NT	NT	NT	770
	9/25/2008	1.5	1.02	NT	NT	NT	NT	NT	NT	890
	12/5/2008	1.55	1.44	NT	NT	NT	NT	NT	NT	1,900
	3/18/2009	0.31	0.69	NT	NT	NT	NT	NT	NT	980
	6/23/2009	-0.28	0.73 J	NT	NT	NT	NT	NT	NT	700
	9/24/2009	0.39	1.25	NT	NT	NT	NT	NT	NT	880
	12/16/2009	0.26	0.37	NT	NT	NT	NT	NT	NT	580
	3/10/2010	0.89	1.12	NT	NT	NT	NT	NT	NT	960
	6/8/2010	0.45	0.68	NT	NT	NT	NT	NT	NT	540
CSMRI-9	2/27/2007	0.12	0.53	-0.017	0.04	0.027	NT	NT	NT	7.9
	6/26/2007	0.22	0.37	0.018	0.004	-0.015	NT	NT	NT	32
	9/10/2007	0.5	1.01	0.04	-0.043	0.012	NT	NT	NT	35
	11/26/2007	0.25	0.27	0.023	0.003	0.003	NT	NT	NT	28
	2/27/2008	0.11	0.24	0.047	0.037	0.041	NT	NT	NT	24
	4/15/2008	0.27	0.65	-0.004	0.015	0.022	NT	NT	NT	22
	9/24/2008	0.11	0.48	NT	NT	NT	NT	NT	NT	28
	12/5/2008	0.13	0.65	NT	NT	NT	NT	NT	NT	26
	3/16/2009	0.17	0.45	NT	NT	NT	NT	NT	NT	34
	6/22/2009	0	0.88 J	NT	NT	NT	NT	NT	NT	99
	9/24/2009	0.24	0.59	NT	NT	NT	NT	NT	NT	43
	12/16/2009	0.45	0.61	NT	NT	NT	NT	NT	NT	39
	3/11/2010	0.2	0.36	NT	NT	NT	NT	NT	NT	41
	6/9/2010	0.41	0.64	NT	NT	NT	NT	NT	NT	48
	3/1/2007	0.19	0.63	0.014	-0.004	0.018	NT	NT	NT	7.8
CSMRI-10	6/26/2007	0.26	0.43	-0.008	0.03	-0.005	NT	NT	NT	8.8
	9/10/2007	-0.04	0.48	0.103	0.05	0.005	NT	NT	NT	9.9
	11/26/2007	-0.05	0.57	0.068	0.141	0.031	NT	NT	NT	10
	2/26/2008	0.12	0.44	0.094	0.011	0.019	NT	NT	NT	9.2
	4/15/2008	0.03	0.56	-0.006	-0.05	0.005	NT	NT	NT	8.7
	9/24/2008	0.21	0.48	NT	NT	NT	NT	NT	NT	11
	12/4/2008	0.11	0.92	NT	NT	NT	NT	NT	NT	19
	3/16/2009	0.15	1.01	NT	NT	NT	NT	NT	NT	16
	6/22/2009	0.35	0.48 J	NT	NT	NT	NT	NT	NT	12
	9/25/2009	0.25	0.62	NT	NT	NT	NT	NT	NT	13
	12/16/2009	0.17	0.85	NT	NT	NT	NT	NT	NT	14
	3/11/2010	0.41	0.47	NT	NT	NT	NT	NT	NT	13
	6/9/2010	0.37	0.66	NT	NT	NT	NT	NT	NT	9.8
CSMRI-11	3/1/2007	0.16	0.46	0.051	0.085	0.007	NT	NT	NT	4.8
	6/26/2007	0.37	0.43	0.084	0	0.008	NT	NT	NT	8.4
	9/10/2007	-0.26	0.52	0.012	0.006	0.016	NT	NT	NT	10
	11/26/2007	0.16	0.87	0.089	0.099	-0.012	NT	NT	NT	11
	2/26/2008	0.28	-0.03	0.044	0.044	0.074	NT	NT	NT	8.7
4/15/2008	0.35	0.75	-0.032	0.004	0.016	NT	NT	NT	7.6	
CSMRI-11B	12/3/08 (DRY)	NT	NT	NT	NT	NT	NT	NT	NT	NT
	3/16/09 (DRY)	NT	NT	NT	NT	NT	NT	NT	NT	NT
	6/24/2009	0.52	NT	NT	NT	NT	NT	NT	NT	12
	9/25/2009	3.5	0.88	NT	NT	NT	NT	NT	NT	17
	12/18/2009	0.89	0.51	NT	NT	NT	NT	NT	NT	14
3/8/2010	NT	NT	NT	NT	NT	NT	NT	NT	NT	
6/8/2010	0.28	0.4	NT	NT	NT	NT	NT	NT	10	
MCL*		Total Ra = 5	NE	Th 230 + Th 232 = 60**	NE	NE	NE	NE	30	

*Maximum Contaminant Level – National Primary Drinking Water Regulations

**5 CCR 1002-41 Reg 41 – Colorado Groundwater Standards

pCi/l - picocuries per liter

J - Estimated

NE – Not Established

NT – not tested

µg/l – micrograms per liter

Table G-2
Historical Summary of Metals in Groundwater (Stoller)
 (All results in milligrams per liter)

Sample Station	Sample Date	Ag	As	Ba	Ca	Cd	Cr	Hg	K	Mg	Mo	Na	Pb	Se	V	Zn	
CSMRI-1	2/25/2005	ND	ND	ND	28	ND	ND	ND	2.8	9.4	ND	29	ND	ND	ND	0.032	
	6/14/2005	ND	ND	ND	17	ND	ND	ND	2.3	5.1	ND	16	ND	ND	ND	0.032	
	9/7/2005	ND	ND	0.055 (B)	21	ND	ND	ND	2.9	6.3	0.0021 (B)	25	ND	0.0041 (B)	ND	0.034	
	12/20/2005	ND	ND	0.067 (B)	32	ND	ND	0.00034 (B)	2.9	10	ND	26	ND	ND	ND	0.052	
	3/15/2006	ND	ND	0.064 (B)	33	ND	ND	0.00002 (B)	2.6	10	0.0013 (B)	24	ND	ND	ND	0.049	
	6/14/2006	ND	ND	0.031 (B)	10	ND	ND	ND	1.9	3	0.0051 (B)	9.2	ND	0.0035 (B)	ND	0.015 (B)	
	9/13/2006	ND	ND	0.061 (B)	20	ND	0.041 (B)	ND	2.7	6	0.0038 (B)	14	ND	ND	ND	0.03	
	3/1/2007	ND	ND	0.081 (B)	39	0.00045 (B)	0.00063 (B)	0.000017 (B)	3	12	0.0059 (B)	26	ND	0.0066	ND	0.048	
	6/27/2007	ND	ND	0.063 (B)	23	ND	ND	0.000073 (B)	2.4	9	ND	21	ND	ND	ND	0.017 (B)	
	9/11/2007	ND	ND	0.065 (B)	23	ND	0.00061 (B)	0.000011 (B)	2.5	7.2	0.002 (B)	14	ND	ND	ND	0.038	
	11/27/2007	ND	ND	0.075 (B)	31	ND	ND	0.000029 (B)	2.5	9.7	0.0014 (B)	18	ND	ND	ND	0.049	
	2/27/2008	ND	ND	0.08 (B)	36	ND	ND	ND	2.5	12	0.0013 (B)	22	ND	ND	ND	0.048	
	4/18/2008	ND	ND	0.081 (B)	36	ND	ND	ND	2.7	11	0.0015 (B)	22	ND	ND	ND	0.057	
	9/25/2008	NT	NT	NT	30	NT	NT	NT	3	9	NT	18	NT	NT	NT	NT	
	12/3/2008	NT	NT	NT	39	NT	NT	NT	3.5	12	NT	25	NT	NT	NT	NT	
	3/17/2009	NT	NT	NT	46	NT	NT	NT	3	14	NT	27	NT	NT	NT	NT	
	6/24/2009	0.00078	0.0032	0.097	36	0.00016	0.00041	0.00002	3.3	13	32	0.0019	0.00035	NT	NT	NT	
	9/24/2009	NT	NT	NT	48 (J)	NT	NT	NT	3.2	18 (J)	NT	45 (J)	NT	NT	NT	NT	
	12/17/2009	NT	NT	NT	49	NT	NT	NT	3.4	16	NT	42	NT	NT	NT	NT	
	3/9/2010	NT	NT	NT	52	NT	NT	NT	3	19	NT	42	NT	NT	NT	NT	
6/10/2010	ND	ND	0.11	51	ND	ND	0.00023 (B)	4.1	15	NT	42	ND	NT	ND	NT		
CSMRI-1B	3/1/2007	ND	ND	0.098 (B)	130	ND	0.00014 (B)	0.000017 (B)	52	47	0.17	91	ND	0.0058	0.0009 (B)	ND	
	6/26/2007	ND	ND	0.071 (B)	83	ND	ND	0.000072 (B)	10	38	0.029	35	ND	ND	ND	ND	
	9/11/2007	ND	ND	0.1	93	ND	ND	0.0000094 (B)	8.4	43	0.031	36	ND	ND	ND	0.0012 (B)	
	11/27/2007	ND	ND	0.11	100	ND	ND	0.000029 (B)	9.4	46	0.024	42	ND	ND	0.00073 (B)	0.0039 (B)	
	2/28/2008	ND	ND	0.11	97	ND	0.0015 (B)	ND	9.3	45	0.029	41	ND	0.0039 (B)	ND	0.0033 (B)	
	4/18/2008	ND	ND	0.11	93	ND	ND	ND	9.1	43	0.027	39	ND	ND	0.00065 (B)	ND	
	9/24/2008	NT	NT	NT	92	NT	NT	NT	7.3	39	NT	38	NT	NT	NT	NT	
	12/5/2008	NT	NT	NT	95	NT	NT	NT	7.6	39	NT	40	NT	NT	NT	NT	
	3/18/2009	NT	NT	NT	NT	NT	NT	NT	NT	NT	NT	NT	NT	NT	NT	NT	
	6/24/2009	0.00078	0.0032	0.14	140	0.00016	0.00041	0.000022	7.2	61	59	0.0019	0.00035	NT	NT	NT	
	9/25/2009	NT	NT	NT	120 (J)	NT	NT	NT	7	55 (J)	NT	42 (J)	NT	NT	NT	NT	
	12/17/2009	NT	NT	NT	120	NT	NT	NT	7.8	51	NT	48	NT	NT	NT	NT	
	3/11/2010	NT	NT	NT	120	NT	NT	NT	6.4	51	NT	42	NT	NT	NT	NT	
	6/9/2010	ND	ND	0.1	170	ND	ND	0.00023 (B)	4.8	85	NT	61	ND	NT	ND	NT	
	CSMRI-2	2/25/2005	ND	ND	0.11	72	ND	ND	ND	7.1	32	ND	19	ND	ND	ND	0.02
		6/14/2005	ND	ND	0.1	76	ND	ND	ND	6.3	32	ND	18	ND	ND	ND	ND
		9/7/2005	ND	ND	0.11	81	ND	ND	ND	7.1	35	ND	19	ND	ND	ND	0.011 (B)
		12/20/2005	ND	ND	0.098 (B)	76	ND	ND	0.000031 (B)	6.7	33	ND	18	ND	ND	ND	0.0043 (B)
		3/15/2006	ND	ND	0.09 (B)	74	ND	ND	0.000023 (B)	6.1	31	ND	17	ND	ND	ND	0.0059 (B)
		6/14/2006	ND	ND	0.093 (B)	70	ND	ND	ND	6.3	31	0.0048 (B)	17	ND	0.0031 (B)	ND	0.0092 (B)
9/13/2006		ND	ND	0.11	81	ND	ND	ND	6.7	35	0.0014 (B)	19	ND	ND	ND	0.0092 (B)	
3/8/2007		ND	0.0058 (B)	0.12	88	ND	ND	ND	8.3	39	ND	21	ND	0.03	ND	0.0011 (B)	
6/28/2007		ND	ND	0.11	97	ND	ND	0.0000056 (B)	7.9	49	ND	26	ND	ND	0.002 (B)	0.0041 (B)	
9/11/2007		ND	ND	0.1	91	ND	ND	0.000016 (B)	7.2	43	ND	23	ND	ND	0.00086 (B)	0.0082 (B)	
11/27/2007		ND	ND	0.093 (B)	83	ND	ND	0.000023 (B)	7	38	ND	22	ND	ND	0.001 (B)	0.0075 (B)	
2/28/2008		ND	ND	0.094 (B)	81	ND	0.0018 (B)	ND	6.6	38	ND	21	ND	ND	0.0017 (B)	0.0073 (B)	
4/17/2008		ND	ND	0.092 (B)	78	ND	ND	ND	6.6	36	ND	20	ND	ND	0.0014 (B)	0.0055 (B)	
9/24/2008		NT	NT	NT	74	NT	NT	NT	6.4	34	NT	19	NT	NT	NT	NT	
12/5/2008		NT	NT	NT	75	NT	NT	NT	6.6	33	NT	20	NT	NT	NT	NT	
3/18/2009		NT	NT	NT	76	NT	NT	NT	6.4	34	NT	19	NT	NT	NT	NT	
6/23/2009		0.00078	0.0032	0.096	77	0.00016	0.00041	0.000024	6.6	35	20	0.0019	0.00035	NT	NT	NT	
9/25/2009		NT	NT	NT	76 (J)	NT	NT	NT	5.2	34 (J)	NT	19 (J)	NT	NT	NT	NT	
12/18/2009		NT	NT	NT	79	NT	NT	NT	5.9	35	NT	20	NT	NT	NT	NT	
3/11/2010		NT	NT	NT	80	NT	NT	NT	5.6	36	NT	19	NT	NT	NT	NT	
6/10/2010	ND	ND	0.098 (B)	93	ND	ND	0.000024 (B)	6.9	43	NT	25	ND	NT	0.00094 (B)	NT		
CSMRI-4	2/25/2005	ND	ND	ND	72	ND	ND	ND	5.1	31	0.017	29	ND	ND	ND	0.12	
	6/14/2005	ND	ND	ND	86	ND	ND	ND	6.6	34	0.038	34	ND	0.0063	ND	0.068	
	9/7/2005	ND	0.0035 (B)	0.055 (B)	82	ND	ND	ND	7.6	33	0.035	31	ND	0.0049 (B)	ND	0.097	
	12/20/2005	ND	ND	0.056 (B)	100	ND	ND	0.000045 (B)	6.8	43	0.024	34	ND	ND	ND	0.18	
	3/15/2006	ND	ND	0.042 (B)	81	ND	ND	0.000034 (B)	5	35	0.021	29	ND	ND	0.00056 (B)	0.21	
	6/15/2006	ND	0.0031 (B)	0.055 (B)	89	0.00085 (B)	ND	0.0000049 (B)	8.3	37	0.03	31	ND	ND	0.0011 (B)	0.11	
	9/13/2006	ND	ND	0.043 (B)	66	ND	ND	0.000016 (B)	8.3	27	0.038	30	ND	ND	ND	0.082	
	3/8/2007	ND	0.0057 (B)	0.072 (B)	120	0.00023 (B)	ND	0.000018 (B)	11	49	0.015	47	ND	0.019	ND	0.088	
	6/27/2007	ND	ND	0.067 (B)	110	ND	ND	0.000022 (B)	11	46	0.04	47	ND	ND	0.00073 (B)	0.14	
	9/11/2007	ND	0.0045 (B)	0.089 (B)	120	0.0011 (B)	0.0014 (B)	0.000037 (B)	12	49	0.05	41	ND	ND	0.0012 (B)	0.17	
	11/26/2007	ND	ND	0.081 (B)	110	0.00049 (B)	ND	0.000035 (B)	10	50	0.024	43	ND	ND	0.0011 (B)	0.1	
	2/27/2008	ND	ND	0.073 (B)	130	ND	ND	0.000016 (B)	8.2	58	0.015	45	ND	0.0034 (B)	ND	0.069	
	4/17/2008	ND	0.0063 (B)	0.089 (B)	150	0.00047 (B)	ND	0.000016 (B)	10	66	0.014	53	ND	ND	0.00078 (B)	0.087	
	9/25/2008	NT	NT	NT	130	NT	NT	NT	13	55	NT	50	NT	NT	NT	NT	
	12/5/2008	NT	NT	NT	130	NT	NT	NT	11	54	NT	48	NT	NT	NT	NT	
	3/17/2009	NT	NT	NT	100	NT	NT	NT	9.3	45	NT	63	NT	NT	NT	NT	
	6/23/2009	0.00078	0.0032	0.084	89	0.00016	0.00041	0.000013	12	38	70	0.0019	0.00068	NT	NT	NT	
	9/24/2009	NT	NT	NT	160 (J)	NT	NT	NT	14	65 (J)	NT	69 (J)	NT	NT	NT	NT	
	12/16/2009	NT	NT	NT	110	NT	NT	NT	11	49	NT	62	NT	NT	NT	NT	
	3/10/2010	NT	NT	NT	120	NT	NT	NT	11	51	NT	55	NT	NT	NT	NT	
6/8/2010	ND	ND	0.1	140	0.00029 (B)	ND	0.00007 (B)	16	55	NT	59	ND	NT	ND	NT		
CSMRI-5	2/25/2005	ND	ND	ND	54	ND	ND	ND	3.4	22	ND	27	ND	ND	ND	0.067	
	6/14/2005	ND	ND	ND	63	ND	ND	ND	3.3	23	ND	28	ND	ND	ND	0.047	
	9/7/2005	ND	ND	0.085 (B)	85	ND	ND	ND	4.2	31	0.0042 (B)	35	ND	0.0037 (B)	0.0018 (B)	0.089	
	12/20/2005	ND	ND	0.072 (B)	79	0.00071 (B)	ND	0.000048 (B)	4.1	30	0.002 (B)	31	ND	ND	0.0012 (B)	0.17	
	3/15/2006	ND	ND	0.058 (B)	70	0.00037 (B)	ND	0.000029 (B)	3.5	26	0.0031 (B)	29	ND	0.0035 (B)	0.00067 (B)	0.11	
	6/15/2006	ND	ND	0.052 (B)	51	ND	ND	0.000012 (B)	3.6	19	0.0028 (B)	26	ND	ND	ND	0.055	
	9/13/2006	ND	ND	0.087 (B)	110	ND	0.0022 (B)	ND	4.5	41	0.0027 (B)	50	ND	ND	0.001 (B)	0.11	
	3/8/2007	ND	0.0037 (B)	0.063 (B)	80	ND	ND	ND	4.5	31	0.0019 (B)	34	ND	0.015	ND	0.083	
	6/27/2007	ND	ND	0.066 (B)	98	ND	ND	0.0000091 (B)	4.5	40	0.006 (B)	40	ND	ND	0.0017 (B)	0.025	
	9/11/2007	ND	ND	0.13	110	ND	0.00082 (B)	0.000023 (B)	4.9	44	0.0042 (B)	47	ND	ND	0.0015 (B)	0.054	
	11/26/2007	ND	ND	0.087 (B)	110	ND	0.00089 (B)	0.000032 (B)	4.5	42	ND	47	ND	ND	0.0012 (B)	0.12	
	2/27/2008	ND	ND	0.073 (B)	100	ND	ND	ND	4.3	40	ND	42	ND	ND	ND	0.094	
	4/17/2008	ND	ND	0.078 (B)	100	ND	ND	0.000018 (B)	4.6	40	0.0011 (B)	41	ND	ND	0.0011 (B)	0.093	
	9/25/2008	NT	NT	NT	160	NT	NT	NT	5.5	61	NT	59	NT	NT	NT		

Table G-2
Historical Summary of Metals in Groundwater (Stoller)
(All results in milligrams per liter)

Sample Station	Sample Date	Ag	As	Ba	Ca	Cd	Cr	Hg	K	Mg	Mo	Na	Pb	Se	V	Zn
CSMRI-7B	2/27/2007	NT	NT	NT	NT	NT	NT	NT	NT	NT	NT	NT	NT	NT	NT	NT
	6/26/2007	ND	ND	0.056 (B)	70	ND	ND	0.000006 (B)	5.5	37	0.024	53	ND	ND	0.00061 (B)	0.0041 (B)
	9/10/2007	NT	NT	NT	NT	NT	NT	NT	NT	NT	NT	NT	NT	NT	NT	NT
	11/26/07 (DRY)	NT	NT	NT	NT	NT	NT	NT	NT	NT	NT	NT	NT	NT	NT	NT
	2/27/2008 (DRY)	NT	NT	NT	NT	NT	NT	NT	NT	NT	NT	NT	NT	NT	NT	NT
	4/15/08 (DRY)	NT	NT	NT	NT	NT	NT	NT	NT	NT	NT	NT	NT	NT	NT	NT
	9/24/08 (DRY)	NT	NT	NT	NT	NT	NT	NT	NT	NT	NT	NT	NT	NT	NT	NT
	12/3/08 (DRY)	NT	NT	NT	NT	NT	NT	NT	NT	NT	NT	NT	NT	NT	NT	NT
	3/16/09 (DRY)	NT	NT	NT	NT	NT	NT	NT	NT	NT	NT	NT	NT	NT	NT	NT
	6/22/09 (DRY)	NT	NT	NT	NT	NT	NT	NT	NT	NT	NT	NT	NT	NT	NT	NT
	9/23/2009 (DRY)	NT	NT	NT	NT	NT	NT	NT	NT	NT	NT	NT	NT	NT	NT	NT
	12/15/2009	NT	NT	NT	NT	NT	NT	NT	NT	NT	NT	NT	NT	NT	NT	NT
3/8/10 (DRY)	NT	NT	NT	NS	NT	NT	NT	NT	NS	NS	NT	NS	NT	NT	NT	
6/10/2010	NT	NT	NT	NT	NT	NT	NT	NT	NT	NT	NT	NT	NT	NT	NT	
3/8/2007	ND	0.0053 (B)	0.068 (B)	230	ND	ND	ND	ND	23	72	0.094	74	ND	0.034	ND	0.0024 (B)
6/27/2007	ND	ND	0.053 (B)	190	ND	ND	0.000099 (B)	19	55	0.043	52	ND	ND	ND	ND	0.069
9/10/2007	ND	0.0069 (B)	0.076 (B)	160	ND	0.00074 (B)	0.000027 (B)	15	49	0.034	54	0.0018 (B)	ND	ND	ND	0.025
11/27/2007	ND	ND	0.091 (B)	230	ND	ND	0.000024 (B)	15	67	0.026	70	ND	0.0046 (B)	0.001 (B)	0.011 (B)	0.038
2/27/2008	ND	0.036 (B)	0.07 (B)	270	ND	ND	ND	15	82	0.019	100	ND	ND	ND	ND	0.032
4/17/2008	ND	ND	0.046 (B)	210	ND	0.0011 (B)	ND	13	63	0.016	73	ND	ND	ND	ND	0.032
9/25/2008	NT	NT	NT	230	NT	NT	NT	17	68	NT	70	NT	NT	NT	NT	NT
12/5/2008	NT	NT	NT	400	NT	NT	NT	18	95	NT	84	NT	NT	NT	NT	NT
3/18/2009	NT	NT	NT	250	NT	NT	NT	13	74	NT	97	NT	NT	NT	NT	NT
6/23/2009	0.00078	0.0032	0.038	170	0.00095	0.00041	0.00003	14	48	60	0.0019	0.00035	NT	NT	NT	NT
9/24/2009	NT	NT	NT	250 (J)	NT	NT	NT	13	63 (J)	NT	78 (J)	NT	NT	NT	NT	NT
12/16/2009	NT	NT	NT	210	NT	NT	NT	12	59	NT	56	NT	NT	NT	NT	NT
3/10/2010	NT	NT	NT	250	NT	NT	NT	12	77	NT	79	NT	NT	NT	NT	NT
6/8/2010	ND	ND	0.052 (B)	170	ND	ND	0.000024 (B)	14	60	NT	48	ND	NT	ND	NT	NT
2/27/2007	ND	ND	0.08 (B)	69	ND	0.0011 (B)	0.000024 (B)	12	31	0.045	33	ND	0.011	0.001 (B)	ND	ND
6/26/2007	ND	ND	0.049 (B)	160	ND	ND	0.000002 (B)	8.5	77	0.0028	150	ND	0.0049 (B)	0.00096 (B)	0.0096 (B)	0.0096 (B)
9/10/2007	ND	0.004 (B)	0.059 (B)	100	ND	0.0009 (B)	0.000016 (B)	6	51	0.0037 (B)	49	ND	ND	0.00071 (B)	0.0097 (B)	0.0097 (B)
11/26/2007	ND	ND	0.078 (B)	110	0.00051 (B)	0.0011 (B)	0.000031 (B)	5.9	56	0.0023 (B)	52	ND	0.0054	0.0012 (B)	0.015 (B)	0.015 (B)
2/27/2008	ND	ND	0.079 (B)	110	ND	ND	ND	5.4	56	ND	49	ND	0.0033 (B)	ND	ND	0.011
4/15/2008	ND	ND	0.077 (B)	100	ND	ND	0.000013 (B)	5	52	0.0017 (B)	46	ND	ND	0.00077 (B)	0.0079 (B)	0.0079 (B)
9/24/2008	NT	NT	NT	110	NT	NT	NT	5.8	54	NT	50	NT	NT	NT	NT	NT
12/5/2008	NT	NT	NT	100	NT	NT	NT	5.3	48	NT	46	NT	NT	NT	NT	NT
3/16/2009	NT	NT	NT	100	NT	NT	NT	4.7	49	NT	45	NT	NT	NT	NT	NT
6/22/2009	0.00078	0.0032	0.054	250	0.00079	0.00041	0.000026	12	100	120	0.0019	0.00035	NT	NT	NT	NT
9/24/2009	NT	NT	NT	120 (J)	NT	NT	NT	5.6	58 (J)	NT	64 (J)	NT	NT	NT	NT	NT
12/16/2009	NT	NT	NT	140	NT	NT	NT	6.2	67	NT	59	NT	NT	NT	NT	NT
3/11/2010	NT	NT	NT	140	NT	NT	NT	5.1	67	NT	49	NT	NT	NT	NT	NT
6/9/2010	ND	ND	0.07 (B)	150	ND	ND	0.000019	6.7	69	NT	69	ND	NT	ND	NT	NT
3/1/2007	0.00051 (B)	ND	0.064 (B)	79	ND	0.0013 (B)	0.000024 (B)	7.3	33	0.01	36	ND	0.01	0.0011 (B)	ND	ND
6/26/2007	ND	ND	0.079 (B)	100	ND	ND	0.000063 (B)	4.7	44	ND	37	ND	0.0044 (B)	0.00055 (B)	ND	ND
9/10/2007	ND	0.0039 (B)	0.071 (B)	89	ND	0.0012 (B)	0.00002 (B)	4.2	38	0.0014 (B)	36	ND	ND	0.00099 (B)	0.0042 (B)	0.0042 (B)
11/26/2007	ND	ND	0.085 (B)	110	ND	ND	0.000026 (B)	4.7	43	ND	41	ND	ND	ND	ND	ND
2/26/2008	ND	ND	0.09 (B)	110	ND	ND	ND	4.6	46	ND	41	ND	ND	ND	ND	0.0052
4/15/2008	ND	ND	0.088 (B)	100	ND	0.0044 (B)	ND	4.5	44	ND	40	ND	ND	0.00059 (B)	0.0018 (B)	0.0018 (B)
9/24/2008	NT	NT	NT	100	NT	NT	NT	4.6	42	NT	41	NT	NT	NT	NT	NT
12/4/2008	NT	NT	NT	100	NT	NT	NT	4.8	41	NT	43	NT	NT	NT	NT	NT
3/16/2009	NT	NT	NT	110	NT	NT	NT	4.5	43	NT	43	NT	NT	NT	NT	NT
6/22/2009	0.00078	0.0032	0.09	100	0.00016	0.00041	0.00002	4.5	41	40	0.0019	0.00035	NT	NT	NT	NT
9/25/2009	NT	NT	NT	120 (J)	NT	NT	NT	3.8	47 (J)	NT	43 (J)	NT	NT	NT	NT	NT
12/16/2009	NT	NT	NT	130	NT	NT	NT	4.9	51	NT	49	NT	NT	NT	NT	NT
3/11/2010	NT	NT	NT	130	NT	NT	NT	4.4	52	NT	45	NT	NT	NT	NT	NT
6/9/2010	ND	ND	0.098 (B)	130	ND	ND	0.000025	4.7	48	NT	49	ND	NT	ND	NT	NT
2/27/2007	ND	ND	0.073 (B)	75	ND	0.0013 (B)	0.000023 (B)	9.7	29	0.033	33	ND	0.013	0.00073 (B)	0.0023 (B)	0.0023 (B)
6/26/2007	ND	ND	0.096 (B)	110	ND	0.0012 (B)	0.0000071 (B)	5.4	44	0.0014 (B)	39	ND	0.0064	0.00059 (B)	ND	ND
9/10/2007	ND	0.004 (B)	0.071 (B)	96	ND	0.00083 (B)	0.000016 (B)	4.5	39	0.0016 (B)	44	ND	ND	0.00078 (B)	0.0033 (B)	0.0033 (B)
11/26/2007	ND	ND	0.11	110	ND	ND	0.000028 (B)	4.9	44	0.0012 (B)	40	ND	ND	0.0013 (B)	ND	ND
2/26/2008	ND	ND	0.11	110	ND	ND	ND	4.6	42	ND	44	ND	ND	ND	ND	0.0048
4/15/2008	ND	ND	0.12	100	ND	ND	ND	4.7	41	ND	44	ND	ND	ND	ND	ND
12/3/08 (DRY)	NT	NT	NT	NT	NT	NT	NT	NT	NT	NT	NT	NT	NT	NT	NT	NT
3/16/09 (DRY)	NT	NT	NT	NT	NT	NT	NT	NT	NT	NT	NT	NT	NT	NT	NT	NT
6/24/2009	0.00078	0.0032	0.22	89	0.00043	0.00041	0.000027	19	43	48	0.0019	0.00066	NT	NT	NT	NT
9/25/2009	NT	NT	NT	130 (J)	NT	NT	NT	6.2	57 (J)	NT	49 (J)	NT	NT	NT	NT	NT
12/15/2009	NT	NT	NT	NT	NT	NT	NT	NT	NT	NT	NT	NT	NT	NT	NT	NT
3/8/2010	NT	NT	NT	NT	NT	NT	NT	NT	NT	NT	NT	NT	NT	NT	NT	NT
6/8/2010	ND	ND	0.091 (B)	130	ND	0.0013 (B)	0.000026	5.6	55	NT	49	ND	NT	ND	NT	NT
Detection Limits		0.01	0.01	0.1	1	0.005	0.01	0.0002	1	1	0.01	1	0.003	0.005	0.01	0.02
MCL*		NE	0.01	2	NE	0.005	0.1	0.002	NE	NE	NE	NE	0.015	0.05	NE	NE

*Maximum Contaminant Level – National Primary Drinking Water Regulations

ND – non detect

NE – not established

NT – not tested

(B) – Detected above Instrument Detection Level but below Reported Detection Level

Table G-3
Historical Summary of Radioisotopes in Surface Water (Stoller)

Sample Station	Sample Date	Ra-226	Ra-228	Th-228	Th-230	Th-232	U-234	U-235	U-238	Total U
		(pCi/l)	(pCi/l)	(pCi/l)	(pCi/l)	(pCi/l)	(pCi/l)	(pCi/l)	(pCi/l)	(µg/l)
SW-1	2/25/2005	0	0.58	0.018	-0.026	-0.001	0.89	0.083	0.65	1.97
	6/14/2005	0.14	0.05	0.05	-0.025	0.016	0.246	0.021	0.251	0.75
	9/7/2005	0.18	0.42	0.041	0.25	0.102	0.35	0.031	0.35	1.04
	12/20/2005	-0.31	0.47	0.028	0.197	-0.005	0.64	0.041	0.7	2.11
	3/15/2006	-0.16	0.35	0.059	0.125	0.005	0.6	0.029	0.53	1.59
	6/14/2006	0.13	0.45	0.16	0.53	0.062	0.11	0.08	0.19	0.61
	9/13/2006	-0.03	0.25	-0.019	-0.035	0.01	0.37	-0.005	0.34	1
	3/1/2007	-0.1	0.25	-0.038	0.15	0.026	NT	NT	NT	1.7
	6/27/2007	0.13	0.77	0.006	0.016	0.014	NT	NT	NT	0.6
	9/11/2007	0.15	0.74	0.063	0.088	0.012	NT	NT	NT	0.94
	11/27/2007	0.2	0.24	0.026	0.049	0.025	NT	NT	NT	1.8
	2/27/2008	0.1	0.48	0.014	0.002	0.024	NT	NT	NT	2
	4/18/2008	0.06	-0.07	-0.023	-0.026	0.012	NT	NT	NT	1.9
	9/25/2008	0.18	-0.01	NT	NT	NT	NT	NT	NT	1.1
	12/3/2008	-0.06	0.34	NT	NT	NT	NT	NT	NT	1.6
	3/16/2009	0.14	0.73	NT	NT	NT	NT	NT	NT	1.9
	6/24/2009	0.33	1.228 J	NT	NT	NT	NT	NT	NT	0.55
	9/24/2009	-0.08	0.37	NT	NT	NT	NT	NT	NT	1.1
	12/17/2009	0.1	0.42	NT	NT	NT	NT	NT	NT	1.7
	3/9/2010	-0.04	0.2	NT	NT	NT	NT	NT	NT	2
6/9/2010	0.07	0.44 (J)	NT	NT	NT	NT	NT	NT	0.46	

**Table G-3
Historical Summary of Radioisotopes in Surface Water (Stoller)**

Sample Station	Sample Date	Ra-226	Ra-228	Th-228	Th-230	Th-232	U-234	U-235	U-238	Total U
		(pCi/l)	(pCi/l)	(pCi/l)	(pCi/l)	(pCi/l)	(pCi/l)	(pCi/l)	(pCi/l)	(µg/l)
SW-2	2/25/2005	0.45	0.06	0.011	-0.016	0.033	0.8	0.066	0.42	1.29
	6/14/2005	0.04	0.29	0.071	-0.028	0.007	0.259	0.032	0.23	0.69
	9/7/2005	-0.08	0.24	-0.013	0.107	0.051	0.54	0.014	0.54	1.62
	12/20/2005	0.09	0.07	-0.003	0.126	0	0.71	0.067	0.49	1.5
	3/15/2006	-0.04	-0.15	0.009	0.184	0.01	0.79	0.004	0.51	1.52
	6/14/2006	0.03	0.04	0.172	0.24	0.1	0.39	0	0.48	1.44
	9/13/2006	0.11	0.35	0.009	-0.03	0.01	0.43	-0.006	0.3	0.89
	3/8/2007	0.12	0.73	0.047	-0.055	0	NT	NT	NT	1.7
	6/28/2007	0.02	0.78	0.028	0.014	0	NT	NT	NT	0.57
	9/11/2007	0.1	0.27	0.066	0.068	0.002	NT	NT	NT	0.97
	11/26/2007	0.11	0.36	0.007	0	0.012	NT	NT	NT	1.7
	2/26/2008	0.1	0	-0.01	0.113	0.011	NT	NT	NT	2
	4/18/2008	0.13	0.58	0.015	0.24	0.024	NT	NT	NT	1.8
	9/24/2008	-0.16	-0.02	NT	NT	NT	NT	NT	NT	0.99
	12/3/2008	0.1	0.46	NT	NT	NT	NT	NT	NT	1.5
	3/16/2009	0.2	0.29	NT	NT	NT	NT	NT	NT	1.9
	6/24/2009	0.03	0.47 J	NT	NT	NT	NT	NT	NT	0.059
	9/24/2009	0	0.28 (J)	NT	NT	NT	NT	NT	NT	1.1
	12/17/2009	0.03	0.44	NT	NT	NT	NT	NT	NT	1.9
3/9/2010	-0.03	0.27	NT	NT	NT	NT	NT	NT	2	
6/9/2010	0.07	-0.06	NT	NT	NT	NT	NT	NT	0.52	
SW-3	6/10/2010	0.39	0.01	NT	NT	NT	NT	NT	NT	0.49
MCL*		Total Ra = 5		NE	Th 230 + Th 232 = 60**		NE	NE	NE	30

*Maximum Contaminant Level – National Primary Drinking Water Regulations

**5 CCR 1002-31 Reg 31 – Colorado Surface Water Standards

pCi/l - picoCuries per liter

µg/l – micrograms per liter

Table G-4
Historical Summary of Metals in Surface Water (Stoller)
(All results in milligrams per liter)

Sample Station	Sample Date	Ag	As	Ba	Ca	Cd	Cr	Hg	K	Mg	Mo	Na	Pb	Se	V	Zn
SW-1	2/25/2005	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	0.2
	6/14/2005	ND	ND	ND	11	ND	ND	ND	1.1	2.8	ND	5.2	ND	ND	ND	0.09
	9/7/2005	ND	0.0037 (B)	0.029 (B)	20	ND	ND	ND	2.2	4.4	0.0044 (B)	8.5	ND	0.0045 (B)	ND	0.063
	12/20/2005	ND	ND	0.042 (B)	35	0.00057 (B)	ND	0.000034 (B)	3.7	7.6	0.004 (B)	19	ND	ND	ND	0.22
	3/15/2006	ND	ND	0.04 (B)	37	0.00084 (B)	0.00047 (B)	0.000024 (B)	3.7	8.5	0.0048 (B)	23	ND	ND	0.00067 (B)	0.19
	6/14/2006	0.0012 (B)	0.0032 (B)	0.011 (B)	8.2	ND	ND	ND	1	1.9	0.0042 (B)	3.1	ND	ND	ND	0.029
	9/13/2006	ND	ND	0.03 (B)	21	ND	ND	ND	2.1	4.4	0.0049 (B)	8.6	ND	ND	ND	0.053
	3/1/2007	ND	ND	0.049 (B)	44	0.0011 (B)	0.00092 (B)	0.000023 (B)	4.3	11	0.0046 (B)	26	ND	ND	ND	0.22
	6/27/2007	ND	ND	0.018 (B)	10	ND	ND	0.000068 (B)	0.93 (B)	2.5	0.0017 (B)	3.2	ND	ND	ND	0.067
	9/11/2007	ND	ND	0.032 (B)	21	ND	ND	0.000019	1.7	5	0.0029 (B)	7.4	ND	ND	ND	0.078
	11/27/2007	ND	ND	0.042 (B)	33	0.00076 (B)	ND	0.00027 (B)	2.8	8.2	0.0032 (B)	15	ND	ND	ND	0.18
	2/27/2008	ND	ND	0.042 (B)	36	ND	ND	ND	3.3	9.6	0.0022 (B)	19	ND	ND	ND	0.15
	4/18/2008	ND	ND	0.044 (B)	35	0.00044 (B)	ND	ND	3.4	9	0.0034 (B)	23	ND	ND	ND	0.13
	9/25/2008	NT	NT	NT	23	NT	NT	NT	1.9	5.1	NT	9	NT	NT	NT	NT
	12/3/2008	NT	NT	NT	32	NT	NT	NT	3	7.1	NT	15	NT	NT	NT	NT
	3/16/2009	NT	NT	NT	35	NT	NT	NT	3.1	8.9	NT	17	NT	NT	NT	NT
	6/24/2009	0.00078	0.0032	0.017	8.7	0.00016	0.00041	0.000024	0.92	2.1	3.3	0.0019	0.00035	NT	NT	NT
	9/24/2009	NT	NT	NT	25 (J)	NT	NT	NT	1.4	5.5 (J)	NT	9.7 (J)	NT	NT	NT	NT
	12/17/2009	NT	NT	NT	39	NT	NT	NT	2.8	8.5	NT	18	NT	NT	NT	NT
	3/9/2010	NT	NT	NT	40	NT	NT	NT	2.8	11	NT	21	NT	NT	NT	NT
6/9/2010	ND	ND	0.012 (B)	8.4	ND	0.001 (B)	0.000027 (B)	0.47 (B)	1.9	NT	2.8	ND	NT	ND	NT	
SW-2	2/25/2005	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	0.17
	6/14/2005	ND	ND	ND	11	ND	ND	ND	1.1	2.8	ND	4.8	ND	ND	ND	0.085
	9/7/2005	ND	ND	0.028 (B)	20	ND	ND	ND	2.1	4.4	0.0037 (B)	8.7	ND	0.0037 (B)	ND	0.051
	12/20/2005	ND	ND	0.042 (B)	35	0.00043 (B)	ND	0.000034 (B)	3.8	8	0.0038 (B)	19	ND	ND	ND	0.21
	3/15/2006	ND	ND	0.042 (B)	39	0.00053 (B)	0.00055 (B)	0.000022 (B)	3.8	8.9	0.0046 (B)	25	ND	ND	0.00053 (B)	0.2
	6/14/2006	ND	0.0022 (B)	0.011 (B)	8.4	ND	ND	ND	1	1.9	0.0045 (B)	3	ND	ND	ND	0.031
	9/13/2006	ND	ND	0.03 (B)	21	ND	ND	ND	2.1	4.4	0.0048 (B)	8.5	ND	ND	ND	0.04
	3/8/2007	ND	0.0053 (B)	0.049 (B)	39	0.00064 (B)	ND	ND	4.2	9.8	0.0014 (B)	22	ND	ND	ND	0.17
	6/28/2007	ND	ND	0.019 (B)	10	ND	ND	0.000056 (B)	0.93 (B)	2.6	ND	3.3	ND	ND	ND	0.075
	9/11/2007	ND	ND	0.033 (B)	21	ND	ND	0.00001	1.7	5.1	0.0035 (B)	7.5	ND	ND	ND	0.084
	11/26/2007	ND	ND	0.044 (B)	35	0.0005 (B)	ND	0.00027 (B)	2.9	8.6	0.0027 (B)	15	ND	ND	ND	0.19
	2/26/2008	ND	ND	0.051	35	0.0005 (B)	ND	ND	3.1	9.2	0.0023 (B)	21	ND	ND	ND	0.15
	4/18/2008	ND	ND	0.045 (B)	35	0.0005 (B)	ND	ND	3.4	9.1	0.0031 (B)	23	ND	ND	ND	0.14
	9/24/2008	NT	NT	NT	23	NT	NT	NT	1.9	5.1	NT	9	NT	NT	NT	NT
	12/3/2008	NT	NT	NT	31	NT	NT	NT	3	7.5	NT	15	NT	NT	NT	NT
	3/16/2009	NT	NT	NT	37	NT	NT	NT	3.5	9.7	NT	19	NT	NT	NT	NT
	6/24/2009	0.00078	0.0032	0.016	8.7	0.00016	0.00041	0.000027	0.9	2.2	3.3	0.0019	0.00035	NT	NT	NT
	9/24/2009	NT	NT	NT	25 (J)	NT	NT	NT	1.4	5.5 (J)	NT	9.4 (J)	NT	NT	NT	NT
	12/17/2009	NT	NT	NT	42	NT	NT	NT	3	9.8	NT	19	NT	NT	NT	NT
	3/9/2010	0.01	0.01	0.1	1	0.005	0.01	0.0002	1	1	NT	1	0.003	NT	0.01	NT
6/9/2010	ND	ND	0.012 (B)	8	ND	ND	0.000024 (B)	0.49 (B)	1.9	NT	2.7	ND	NT	ND	NT	
SW-3	6/10/2010	ND	ND	0.012 (B)	8.4	ND	ND	0.000024 (B)	0.5 (B)	1.9	NT	2.7	ND	NT	ND	NT
Detection Limits		0.01	0.01	0.1	1	0.005	0.01	0.0002	1	1	0.01	1	0.003	0.005	0.01	0.02
MCL*		0.01	0.01	2	NE	0.005	0.1	0.002	NE	NE	NE	NE	0.015	0.05	NE	NE

*Maximum Contaminant Level – National Primary Drinking Water Regulations

ND – Non Detect



NE – Not Established

(B) – Detected above Instrument Detection Level but below Reported Detection Level

Appendix H

Anion and Cation Balances and Piper Diagram

Piper Diagram CSMRI 2010 Quarter 3



CSMRI-1

Water Type	Na-Cl		
Dissolved Solids	381.02 mg/kg	380 mg/L	Measured
Density	0.99732 g/cm ³		Calculated
Conductivity	900 µmho/cm		Measured
Hardness (as CaCO₃)			
Total	155.45 mg/kg	155.04 mg/L	Calculated
Carbonate	155.45	155.04	
Non-Carbonate	0.0	0.0	

Primary Tests

Anion-Cation Balance

Anions	5.98	
Cations	5.82	
% Difference	1.312	OK

Measured TDS = Calculated TDS

Measured	381.022	
Calculated	395.862	
Ratio	0.963	Not within range 1.0 to 1.2

Measured EC = Calculated EC

Measured	900.000	
Calculated	609.659	
Ratio	1.476	Not within range 0.9 to 1.1

Secondary Tests

Measured EC and Ion Sums:

Anions (0.9-1.1)	0.664239	Not within preferred range
Cations (0.9-1.1)	0.647031	Not within preferred range
Calculated TDS to EC ratio (0.55-0.7)	0.440	Not within preferred range
Measured TDS to EC ratio (0.55-0.7)	0.423	Not within preferred range

Organic Mass Balance

DOC ≥ Sum of Organics

DOC unavailable

CSMRI-1B

Water Type	Ca-Cl		
Dissolved Solids	811.91 mg/kg	810 mg/L	Measured
Density	0.99764 g/cm ³		Calculated
Conductivity	940 µmho/cm		Measured
Hardness (as CaCO₃)			
Total	610.45 mg/kg	609.01 mg/L	Calculated
Carbonate	427.5	426.49	
Non-Carbonate	182.96	182.52	

Primary Tests

Anion-Cation Balance

Anions	14.7	
Cations	14.6	
% Difference	0.242	OK

Measured TDS = Calculated TDS

Measured	811.913	
Calculated	969.685	
Ratio	0.837	Not within range 1.0 to 1.2

Measured EC = Calculated EC

Measured	940.000	
Calculated	1377.428	
Ratio	0.682	Not within range 0.9 to 1.1

Secondary Tests

Measured EC and Ion Sums:

Anions (0.9-1.1)	1.562518	Not within preferred range
Cations (0.9-1.1)	1.554968	Not within preferred range
Calculated TDS to EC ratio (0.55-0.7)	1.032	Not within preferred range
Measured TDS to EC ratio (0.55-0.7)	0.864	Not within preferred range

Organic Mass Balance

DOC ≥ Sum of Organics

Dissolved Organic Carbon	1.800 mg/L	
Sum of Organics	0.000 mg/L	OK

CSMRI-10

Water Type	Ca-Cl		
Dissolved Solids	671.65 mg/kg	670 mg/L	Measured
Density	0.99754 g/cm ³		Calculated
Conductivity	1340 µmho/cm		Measured
Hardness (as CaCO₃)			
Total	490.28 mg/kg	489.07 mg/L	Calculated
Carbonate	378.21	377.28	
Non-Carbonate	112.06	111.79	

Primary Tests

Anion-Cation Balance

Anions	11	
Cations	12.1	
% Difference	4.960	OK

Measured TDS = Calculated TDS

Measured	671.654	
Calculated	759.871	
Ratio	0.884	Not within range 1.0 to 1.2

Measured EC = Calculated EC

Measured	1340.000	
Calculated	1091.139	
Ratio	1.228	Not within range 0.9 to 1.1

Secondary Tests

Measured EC and Ion Sums:

Anions (0.9-1.1)	0.818992	Not within preferred range
Cations 1.1)	0.904470	Within preferred range (0.9-

Calculated TDS to EC ratio 0.567 OK

Measured TDS to EC ratio 0.501 Not within preferred range

(0.55-0.7)

Organic Mass Balance

DOC ≥ Sum of Organics

Dissolved Organic Carbon	1.300 mg/L	
Sum of Organics	0.000 mg/L	OK

CSMRI-11B

Water Type	Ca-Cl		
Dissolved Solids	922.1 mg/kg	920 mg/L	Measured
Density	0.99773 g/cm ³		Calculated
Conductivity	1690 µmho/cm		Measured
Hardness (as CaCO₃)			
Total	614.53 mg/kg	613.13 mg/L	Calculated
Carbonate	443.9	442.89	
Non-Carbonate	170.63	170.24	

Primary Tests

Anion-Cation Balance

Anions	14.1	
Cations	15.7	
% Difference	5.602	Not within ± 5%

Measured TDS = Calculated TDS

Measured	922.096	
Calculated	985.440	
Ratio	0.936	Not within range 1.0 to 1.2

Measured EC = Calculated EC

Measured	1690.000	
Calculated	1377.501	
Ratio	1.227	Not within range 0.9 to 1.1

Secondary Tests

Measured EC and Ion Sums:

Anions (0.9-1.1)	0.831884	Not within preferred range
Cations 1.1)	0.930625	Within preferred range (0.9-1.1)
Calculated TDS to EC ratio	0.583	OK
Measured TDS to EC ratio (0.55-0.7)	0.546	Not within preferred range

Organic Mass Balance

DOC ≥ Sum of Organics

Dissolved Organic Carbon	1.500 mg/L	
Sum of Organics	0.000 mg/L	OK

CSMRI-2

Water Type	Ca-HCO ₃		
Dissolved Solids	451.19 mg/kg	450 mg/L	Measured
Density	0.99737 g/cm ³		Calculated
Conductivity	809 µmho/cm		Measured
Hardness (as CaCO₃)			
Total	378.84 mg/kg	377.84 mg/L	Calculated
Carbonate	378.84	377.84	
Non-Carbonate	0.0	0.0	

Primary Tests

Anion-Cation Balance

Anions	6.65	
Cations	8.72	
% Difference	13.509	Not within ± 2%

Measured TDS = Calculated TDS

Measured	451.186	
Calculated	567.191	
Ratio	0.795	Not within range 1.0 to 1.2

Measured EC = Calculated EC

Measured	809.000	
Calculated	701.756	
Ratio	1.153	Not within range 0.9 to 1.1

Secondary Tests

Measured EC and Ion Sums:

Anions (0.9-1.1)	0.821569	Not within preferred range
Cations 1.1)	1.078203	Within preferred range (0.9-1.1)
Calculated TDS to EC ratio (0.55-0.7)	0.701	Not within preferred range
Measured TDS to EC ratio	0.558	OK

Organic Mass Balance

DOC ≥ Sum of Organics

DOC unavailable

CSMRI-4

Water Type	Ca-Cl		
Dissolved Solids	902.06 mg/kg	900 mg/L	Measured
Density	0.99771 g/cm ³		Calculated
Conductivity	1510 µmho/cm		Measured
Hardness (as CaCO₃)			
Total	631.31 mg/kg	629.87 mg/L	Calculated
Carbonate	493.23	492.1	
Non-Carbonate	138.08	137.76	

Primary Tests

Anion-Cation Balance

Anions	13.3	
Cations	15.6	
% Difference	7.931	Not within ± 5%

Measured TDS = Calculated TDS

Measured	902.064	
Calculated	993.253	
Ratio	0.908	Not within range 1.0 to 1.2

Measured EC = Calculated EC

Measured	1510.000	
Calculated	1347.574	
Ratio	1.121	Not within range 0.9 to 1.1

Secondary Tests

Measured EC and Ion Sums:

Anions (0.9-1.1)	0.883537	Not within preferred range
Cations 1.1)	1.035749	Within preferred range (0.9-

Calculated TDS to EC ratio 0.658 OK

Measured TDS to EC ratio 0.597 OK

Organic Mass Balance

DOC ≥ Sum of Organics

Dissolved Organic Carbon	2.100 mg/L	
Sum of Organics	0.000 mg/L	OK

CSMRI-5

Water Type	Ca-Cl		
Dissolved Solids	851.98 mg/kg	850 mg/L	Measured
Density	0.99767 g/cm ³		Calculated
Conductivity	1490 µmho/cm		Measured
Hardness (as CaCO₃)			
Total	606.57 mg/kg	605.16 mg/L	Calculated
Carbonate	361.72	360.88	
Non-Carbonate	244.85	244.28	

Primary Tests

Anion-Cation Balance

Anions	14.2	
Cations	15	
% Difference	2.840	OK

Measured TDS = Calculated TDS

Measured	851.982	
Calculated	941.490	
Ratio	0.905	Not within range 1.0 to 1.2

Measured EC = Calculated EC

Measured	1490.000	
Calculated	1371.442	
Ratio	1.086	OK

Secondary Tests

Measured EC and Ion Sums:

Anions	0.951601	Within preferred range (0.9-1.1)
Cations	1.007241	Within preferred range (0.9-1.1)

Calculated TDS to EC ratio 0.632 OK

Measured TDS to EC ratio 0.572 OK

Organic Mass Balance

DOC ≥ Sum of Organics

Dissolved Organic Carbon	1.500 mg/L	
Sum of Organics	0.000 mg/L	OK

CSMRI-6C

Water Type	Ca-Cl		
Dissolved Solids	801.9 mg/kg	800 mg/L	Measured
Density	0.99764 g/cm ³		Calculated
Conductivity	1450 µmho/cm		Measured
Hardness (as CaCO₃)			
Total	585.43 mg/kg	584.04 mg/L	Calculated
Carbonate	509.71	508.51	
Non-Carbonate	75.716	75.537	

Primary Tests

Anion-Cation Balance

Anions	12	
Cations	14	
% Difference	7.623	Not within ± 5%

Measured TDS = Calculated TDS

Measured	801.896	
Calculated	859.532	
Ratio	0.933	Not within range 1.0 to 1.2

Measured EC = Calculated EC

Measured	1450.000	
Calculated	1179.127	
Ratio	1.230	Not within range 0.9 to 1.1

Secondary Tests

Measured EC and Ion Sums:

Anions (0.9-1.1)	0.827218	Not within preferred range
Cations 1.1)	0.963744	Within preferred range (0.9-

Calculated TDS to EC ratio 0.593 OK

Measured TDS to EC ratio 0.553 OK

Organic Mass Balance

DOC ≥ Sum of Organics

Dissolved Organic Carbon	2.000 mg/L	
Sum of Organics	0.000 mg/L	OK

CSMRI-8

Water Type	Ca-Cl		
Dissolved Solids	1102.4 mg/kg	1100 mg/L	Measured
Density	0.99786 g/cm ³		Calculated
Conductivity	2160 µmho/cm		Measured
Hardness (as CaCO₃)			
Total	910.08 mg/kg	908.13 mg/L	Calculated
Carbonate	723.3	721.75	
Non-Carbonate	186.78	186.38	

Primary Tests

Anion-Cation Balance

Anions	18.3	
Cations	21.4	
% Difference	7.942	Not within ± 5%

Measured TDS = Calculated TDS

Measured	1102.356	
Calculated	1300.780	
Ratio	0.847	Not within range 1.0 to 1.2

Measured EC = Calculated EC

Measured	2160.000	
Calculated	1732.635	
Ratio	1.247	Not within range 0.9 to 1.1

Secondary Tests

Measured EC and Ion Sums:

Anions (0.9-1.1)	0.845657	Not within preferred range
Cations 1.1)	0.991578	Within preferred range (0.9-1.1)
Calculated TDS to EC ratio	0.602	OK
Measured TDS to EC ratio (0.55-0.7)	0.510	Not within preferred range

Organic Mass Balance

DOC ≥ Sum of Organics

Dissolved Organic Carbon	3.400 mg/L	
Sum of Organics	0.000 mg/L	OK

CSMRI-9

Water Type	Ca-Cl		
Dissolved Solids	751.81 mg/kg	750 mg/L	Measured
Density	0.9976 g/cm ³		Calculated
Conductivity	1410 µmho/cm		Measured
Hardness (as CaCO₃)			
Total	581.32 mg/kg	579.93 mg/L	Calculated
Carbonate	427.52	426.49	
Non-Carbonate	153.81	153.44	

Primary Tests

Anion-Cation Balance

Anions	12.2	
Cations	14	
% Difference	6.777	Not within ± 5%

Measured TDS = Calculated TDS

Measured	751.806	
Calculated	866.882	
Ratio	0.867	Not within range 1.0 to 1.2

Measured EC = Calculated EC

Measured	1410.000	
Calculated	1223.937	
Ratio	1.152	Not within range 0.9 to 1.1

Secondary Tests

Measured EC and Ion Sums:

Anions (0.9-1.1)	0.865729	Not within preferred range
Cations 1.1)	0.991606	Within preferred range (0.9-1.1)
Calculated TDS to EC ratio	0.615	OK
Measured TDS to EC ratio (0.55-0.7)	0.533	Not within preferred range

Organic Mass Balance

DOC ≥ Sum of Organics

Dissolved Organic Carbon	1.300 mg/L	
Sum of Organics	0.000 mg/L	OK

SW-1

Water Type	Ca-SO ₄		
Dissolved Solids	130.37 mg/kg	130 mg/L	Measured
Density	0.99713 g/cm ³		Calculated
Conductivity	340 µmho/cm		Measured
Hardness (as CaCO₃)			
Total	78.659 mg/kg	78.433 mg/L	Calculated
Carbonate	57.577	57.412	
Non-Carbonate	21.081	21.021	

Primary Tests

Anion-Cation Balance

Anions	1.89	
Cations	2	
% Difference	3.012	OK

Measured TDS = Calculated TDS

Measured	130.374	
Calculated	135.188	
Ratio	0.964	Not within range 1.0 to 1.2

Measured EC = Calculated EC

Measured	340.000	
Calculated	216.076	
Ratio	1.574	Not within range 0.9 to 1.1

Secondary Tests

Measured EC and Ion Sums:

Anions (0.9-1.1)	0.554509	Not within preferred range
Cations (0.9-1.1)	0.588952	Not within preferred range
Calculated TDS to EC ratio (0.55-0.7)	0.398	Not within preferred range
Measured TDS to EC ratio (0.55-0.7)	0.383	Not within preferred range

Organic Mass Balance

DOC ≥ Sum of Organics

Dissolved Organic Carbon	1.400 mg/L	
Sum of Organics	0.000 mg/L	OK

SW-2

Water Type	Ca-SO ₄		
Dissolved Solids	130.37 mg/kg	130 mg/L	Measured
Density	0.99713 g/cm ³		Calculated
Conductivity	340 µmho/cm		Measured
Hardness (as CaCO₃)			
Total	79.485 mg/kg	79.256 mg/L	Calculated
Carbonate	57.577	57.412	
Non-Carbonate	21.907	21.844	

Primary Tests

Anion-Cation Balance

Anions	1.93	
Cations	2.03	
% Difference	2.502	OK

Measured TDS = Calculated TDS

Measured	130.374	
Calculated	135.589	
Ratio	0.962	Not within range 1.0 to 1.2

Measured EC = Calculated EC

Measured	340.000	
Calculated	218.940	
Ratio	1.553	Not within range 0.9 to 1.1

Secondary Tests

Measured EC and Ion Sums:

Anions (0.9-1.1)	0.567226	Not within preferred range
Cations (0.9-1.1)	0.596340	Not within preferred range
Calculated TDS to EC ratio (0.55-0.7)	0.399	Not within preferred range
Measured TDS to EC ratio (0.55-0.7)	0.383	Not within preferred range

Organic Mass Balance

DOC ≥ Sum of Organics

Dissolved Organic Carbon	1.300 mg/L	
Sum of Organics	0.000 mg/L	OK

SW-3

Water Type	Ca-SO ₄		
Dissolved Solids	140.4 mg/kg	140 mg/L	Measured
Density	0.99714 g/cm ³		Calculated
Conductivity	340 μmho/cm		Measured
Hardness (as CaCO₃)			
Total	79.071 mg/kg	78.845 mg/L	Calculated
Carbonate	55.932	55.772	
Non-Carbonate	23.139	23.073	

Primary Tests

Anion-Cation Balance

Anions	1.91	
Cations	2.02	
% Difference	2.845	OK

Measured TDS = Calculated TDS

Measured	140.402	
Calculated	134.585	
Ratio	1.043	OK

Measured EC = Calculated EC

Measured	340.000	
Calculated	218.126	
Ratio	1.559	Not within range 0.9 to 1.1

Secondary Tests

Measured EC and Ion Sums:

Anions (0.9-1.1)	0.562268	Not within preferred range
Cations (0.9-1.1)	0.595199	Not within preferred range
Calculated TDS to EC ratio (0.55-0.7)	0.396	Not within preferred range
Measured TDS to EC ratio (0.55-0.7)	0.413	Not within preferred range

Organic Mass Balance

DOC ≥ Sum of Organics

Dissolved Organic Carbon	1.300 mg/L	
Sum of Organics	0.000 mg/L	OK